

**County of Harnett
Building Inspections Department
Planning Services**

Certificate of Compliance: ___ Occupancy: X

Certificate issued pursuant to the requirements of North Carolina General Statute 153A-363 and Harnett County Zoning Ordinances. This certifies at the time of issuance, this structure was in compliance with the various ordinances of the County of Harnett and the North Carolina State Building Codes. For the following:

Use Classification: SFD

Permit Numbers

Name: Gasper Nunez

Building: 11-50026096

Electrical: 11-50026096

Address: 1320 Rawls Church Road

Insulation: 11-50026096

Angier NC 27501

Plumbing: 11-50026096

Mechanical: 11-50026096

MFG Home: NANANANANANA

Date: 09-23-2011

Building Official: BSutton

ADDRESS . . : 1320 RAWLS CHURCH RD SUBDIV:
 CONTRACTOR : PHONE :
 OWNER . . : GASPAR NUNEZ PHONE :
 PARCEL . . : 04-0674- - -0022- - -
 APPL NUMBER: 11-50026096 CP NEW RESIDENTIAL (SFD)
 DIRECTIONS : T/S: 02/21/2011 09:30 AM VBROWN ----
 RAWLS CHURCH RD, HWY 210 TO ANGIER,
 LEFT ON 55W, GO TO RAWLS CHURCH RD,
 TURN LEFT ON RAWLS CH RD GO 3/4 MI,
 PROPERTY ON THE RIGHT.
 T/S: 03/30/2011 09:57 AM RDCONTE ---
 PREMISE # 02464880

STRUCTURE: 000 000 54X58 3BDR 2.5BATH SFD W GAR,DECK SCINPC

FLOOD ZONE : FLOOD ZONE X
 # BEDROOMS : 3.00 PROPOSED USE : SFD
 SEPTIC - EXISTING? : NEW TANK WATER SUPPLY : COUNTY

PERMIT: CPSF 00 CP * SFD

TYP/SQ	REQUESTED COMPLETED	INSP RESULT	DESCRIPTION RESULTS/COMMENTS
B101 01	3/21/11 3/21/11	BS AP	R*BLDG FOOTING / TEMP SVC POLE VRU #: 002056596 T/S: March 21, 2011 10:06 AM BSUTTON ----- T/S: 03/30/2011 09:58 AM NTART -----
B103 01	4/19/11 4/19/11	BS AP	R*BLDG FOUND & TEMP SVC POLE VRU #: 002069458 T/S: April 19, 2011 02:04 PM BSUTTON -----
A814 01	4/19/11 4/18/11	TW AP	ADDRESS CONFIRMATION TIME: 17:00 VRU #: 002069474 1320 RAWLS CHURCH RD ANGIER 27501 T/S: 04/18/2011 03:13 PM TWARD ----- T/S: 04/18/2011 03:13 PM TWARD ----- T/S: 04/18/2011 03:13 PM TWARD -----
B105 01	4/29/11 4/29/11	KS AP	R*OPEN FLOOR VRU #: 002073393
R427 01	6/07/11 6/07/11	BS DA	FOUR TRADE ROUGH IN >2500 TIME: 17:00 VRU #: 002089373 T/S: 06/06/2011 07:55 AM NTART ----- 1.Plywood inside garage wall at doors. 2. Electrical and HVAC not firecaulked. 3.Install missing windows. 4. No baffles for insulation in cathdrals 5. Plywood walkway to attic unit must be raised for insulation 6. Top of stairs are wrong. 7. Winders must have minimum 4 inches of tread depth. 8. Rafters over living room and screen porch must be tied back across 3 ceiling joiosts minimum.9. Screw all headers over doors, windows and openings with 2 rows of screws 12 inches on center, LVL over kitchen should have 3 rows 12 inches on center. 10. Support ridge valley splices with RS70 hangers per plan. DO NOT INSULATE
R427 02	6/14/11 6/14/11	BS AP	FOUR TRADE ROUGH IN >2500 VRU #: 002093771 T/S: June 14, 2011 08:51 PM BSUTTON -----
I129 01	6/21/11 6/21/11	DT AP	R*INSULATION INSPECTION TIME: 17:00 VRU #: 002096964 T/S: 06/17/2011 02:54 PM VBROWN -----
H824 01	7/20/11 7/20/11	JM AP	ENVIR. OPERATIONS PERMIT TIME: 17:00 VRU #: 002112829 T/S: 07/21/2011 08:40 AM SZIMMER ----- T/S: 07/21/2011 08:41 AM SZIMMER -----
R431 01	9/09/11 9/09/11	BS DA	FOUR TRADE FINAL >2500 TIME: 17:00 VRU #: 002133510 T/S: 09/07/2011 09:24 AM DJOHNSON -----

PREPARED 9/22/11, 14:01:58
Harnett County

INSPECTION TICKET
INSPECTOR: IVR

PAGE 11
DATE 9/23/11

ADDRESS . . : 1320 RAWLS CHURCH RD
CONTRACTOR :
OWNER . . . : GASPAR NUNEZ
PARCEL . . . : 04-0674- - -0022- - -
APPL NUMBER: 11-50026096 CP NEW RESIDENTIAL (SFD)

SUBDIV:
PHONE :
PHONE :

TYP/SQ REQUESTED INSP DESCRIPTION
COMPLETED RESULT RESULTS/COMMENTS

1. Window beside rear door at sunroom must be tempered glass (bottom sash only) 2. Underside of stairs must be sheetrocked where there is access from the garage. 3. seal around foundation access door and insulate door. Call to reschedule

R431 02 9/23/11 TI FOUR TRADE FINAL >2500 TIME: 17:00 VRU #: 002140085
T/S: 09/22/2011 12:38 PM VBROWN -----

----- COMMENTS AND NOTES -----

Josh Smith

919 244 6742