

HTE# 11-5-27421

Harnett County Department of Public Health Improvement Permit

26713

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: ATLANTIC CONSTRUCTION PROPERTY LOCATION: WILL LUCAS RD
 NEW REPAIR EXPANSION SUBDIVISION: SWEETWATER LOT # 64
 Type of Structure: SFO (62x38) Site Improvements required prior to Construction Authorization Issuance: _____
 Proposed Wastewater System Type: CONVENTIONAL
 Projected Daily Flow: 360 GPD
 Number of bedrooms: 3 Number of Occupants: 6 max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well 100 feet
 Permit conditions: _____ Permit valid for: Five years
 No expiration

Authorized State Agent: [Signature] Date: 9/26/11 SEE ATTACHED SITE SKETCH
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: ATLANTIC CONSTRUCTION PROPERTY LOCATION: WILL LUCAS RD
 Facility Type: SFO (62x38) New Expansion Repair
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** CONVENTIONAL (Initial) Wastewater Flow: 360 GPD
 (See note below, if applicable CONVENTIONAL (Repair))

Installation Requirements/Conditions
 Septic Tank Size 1000 gallons
 Pump Tank Size _____ gallons
 Number of trenches 1
 Exact length of each trench 300 feet
 Trench Spacing: 9 Feet on Center
 Trenches shall be installed on contour at a
 Maximum Trench Depth of: 36-40 inches (Maximum soil cover shall not exceed 36" above the trench bottom)
 (Trench bottoms shall be level to +/- 1/4" 40-45 or 36" above the trench bottom)
 in all directions)
 Pump Requirements: _____ ft. TDH vs. _____ GPM
 Aggregate Depth: 6 inches below pipe
2 inches above pipe
12 inches total
 or 12/6/11

Conditions: TRENCH DEPTH CHANGED DUE TO CHANGE IN SYSTEM AREA BECAUSE OF INSTALLATION SITUATION. NO REDUCTION IN DRAINLINE MAY BE TAKEN.
 WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
 NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____
 This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 9/26/11
 Construction Authorization Expiration Date: 9/26/16

HTE# 11-5-27421

Permit # 26713

Harnett County Department of Public Health Site Sketch

ISSUED TO: ATLANTIC CONSTRUCTION PROPERTY LOCATOR: Will Lucas Rd
SUBDIVISION SNEETWATER LOT # 64
Authorized State Agent: [Signature] REHS Date: 12/6/11

* MEET ON SITE PRIOR TO ANY FURTHER WORK!

* TANK MUST BE LEVEL.
IF TANK IS DAMAGED
IT MUST BE REPLACED!

* IF DITCH DEPTHS
CANNOT BE DONE
AS STATED ON PERMIT
DO NOT CONTINUE
WITH WORK!

* DO NOT WORK UNDER
WET CONDITIONS OF
ANY KIND!

* NO REDUCTION OF
DRAINLINE MAY BE
TAKEN PER STATE
REGULATIONS!

