

HTE# 11-5-27451

Harnett County Department of Public Health

Improvement Permit

26529

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: DAVID + Pamela BYRD PROPERTY LOCATION: Highway 55
 NEW REPAIR EXPANSION SUBDIVISION: Pointers Creek LOT # 3
 Type of Structure: SFD Site Improvements required prior to Construction Authorization Issuance: _____
 Proposed Wastewater System Type: 25% REDUCTION
 Projected Daily Flow: 960 GPD
 Number of bedrooms: 8 Number of Occupants: 16 max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well 100 feet
 Permit conditions: _____ Permit valid for: Five years No expiration

Authorized State Agent: James E. Markham JR Date: 9-15-11 SEE ATTACHED SITE SKETCH
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: DAVID + Pamela BYRD PROPERTY LOCATION: Highway 55
 Facility Type: SFD New Expansion Repair SUBDIVISION: Pointers Creek LOT # 3
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** MANHOLE TO 25% REDUCTION (Initial) Wastewater Flow: 960 GPD
 (See note below, if applicable MANHOLE TO 25% REDUCTION (Repair))

Installation Requirements/Conditions

Septic Tank Size 2000 gallons Number of trenches 5
 Pump Tank Size 1500 gallons 2000 Exact length of each trench 150 feet
 Trench Spacing: 9 Feet on Center
 Trenches shall be installed on contour at a Soil Cover: 6 inches
 Maximum Trench Depth of: 24 inches (Maximum soil cover shall not exceed 36" above the trench bottom)
 (Trench bottoms shall be level to +/- 1/4" in all directions)
 Pump Requirements: _____ ft. TDH vs. _____ GPM
 Conditions: _____ Aggregate Depth: 6 inches below pipe
2 inches above pipe
12 inches total

**WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.**

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.
 Owner/Legal Representative Signature: _____ Date: _____
 This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: James E. Markham JR Date: 9-15-11
 Construction Authorization Expiration Date: 9-15-16

HTE# 11-5-27451

Permit # 26529

Harnett County Department of Public Health Site Sketch

ISSUED TO: DAVID + Pamela Byrd PROPERTY LOCATOR: HWY 55
SUBDIVISION: Potter's Creek LOT # 3

Authorized State Agent: James E. Markin Date: 9-15-11

