

MOSS HOME BUILDERS

Improvement Permit

~~DEANA MANNING REALTY~~

A building permit cannot be issued with only an Improvement Permit

PROPERTY LOCATION: McDOUGALD RD

ISSUED TO: WYNN CONSTRUCTION INC SUBDIVISION SUMMERHILL LOT # 11

NEW REPAIR EXPANSION Site Improvements required prior to Construction Authorization Issuance:

Type of Structure: SFO (60'x60') (50'x50') (60'x40')

Proposed Wastewater System Type: 25% REDUCTION SYSTEM

Projected Daily Flow: 360 GPD

Number of bedrooms: 3 Number of Occupants: 2 max

Basement Yes No

Pump Required: Yes No May be required based on final location and elevations of facilities

Type of Water Supply: Community Public Well Distance from well 100 feet

Permit valid for: Five years No expiration

Authorized State Agent: REMS Date: 1/23/12 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of the permit.

REVISED 5/14/14 REMS REVISED 1/3/16 REMS

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

~~DEANA MANNING REALTY~~ MOSS HOME BUILDERS

ISSUED TO: WYNN CONSTRUCTION INC PROPERTY LOCATION: McDOUGALD RD

(60'x40') SUBDIVISION SUMMERHILL LOT # 11

Facility Type: SFO (60'x60') (50'x50') New Expansion Repair

Basement? Yes No Basement Fixtures? Yes No

Type of Wastewater System** 25% REDUCTION SYSTEM (Initial) Wastewater Flow: 360 GPD

(See note below, if applicable) 25% REDUCTION (Repair)

Installation Requirements/Conditions

Septic Tank Size 1000 gallons Number of trenches 343

Pump Tank Size _____ gallons Exact length of each trench 70 feet Trench Spacing: 9 Feet on Center

Trenches shall be installed on contour at a Soil Cover: 12-18 inches

Maximum Trench Depth of: 24-30 inches (Maximum soil cover shall not exceed

in all directions) 36" above the trench bottom)

Pump Requirements: _____ ft. TDH vs. _____ GPM _____ inches below pipe

Aggregate Depth: _____ inches above pipe

Conditions: _____ inches total

**WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.**

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: REMS Date: 1/23/12

REVISED 5/19/14 REMS Construction Authorization Expiration Date: 1/23/17

HTE# 11-5-27985RRR

Permit # 26872

Harnett County Department of Public Health Site Sketch

MISS HOME BUILDERS

~~DEBRA MANNING REALTY~~

PROPERTY LOCATOR: MCDUGGARD RD

ISSUED TO: ~~WYNN CONSTRUCTION INC~~ SUBDIVISION SUMMERHILL LOT # 11

Authorized State Agent: ~~REHS (OLIVER TOLSONOFF)~~ Date: 1/23/12

REVISED 5/19/14
REVISED 1/13/16

