

**County of Harnett**  
**Building Inspections Department**  
**Planning Services**

**Certificate of Compliance: \_\_\_ Occupancy:**

Certificate issued pursuant to the requirements of North Carolina General Statute 153A-363 and Harnett County Zoning Ordinances. This certifies at the time of issuance, this structure was in compliance with the various ordinances of the County of Harnett and the North Carolina State Building Codes. For the following:

Use Classification: SFD

**Permit Numbers**

Name: Jamie Johnson

Building: \_\_\_\_\_

Electrical: \_\_\_\_\_

Address: 614 Beard Rd

Insulation: \_\_\_\_\_

Plumbing: \_\_\_\_\_

Mechanical: \_\_\_\_\_

Date: 9-15-12

Building Official: Jamie Hall

11-50028696



ADDRESS : 614 BYRD RD  
CONTRACTOR :  
OWNER : JOHNSON JAMIE  
PARCEL : 12-0567- - 0046- -05-  
APPL NUMBER: 12-50028696 CP NEW RESIDENTIAL (SFD)

SUBDIV: MRS OCTA M BYRD DIVISION  
PHONE :  
PHONE :

DIRECTIONS : T/S: 04/11/2012 11:49 AM JBROCK ----  
401 TAKE A RIGHT ON BYRD RD GO .75 JOB  
ON RIGHT

**STRUCTURE: 000 000 69X50 3BDR CRAWL W/ GARAGE**

FLOOD ZONE : FLOOD ZONE X  
# BEDROOMS : 3.00  
SEPTIC - EXISTING? : NEW TANK  
PROPOSED USE : SFD  
WATER SUPPLY : COUNTY

**PERMIT: CPSF 00 CP \* SFD**

TYP/SQ	REQUESTED COMPLETED	INSP RESULT	DESCRIPTION RESULTS/COMMENTS
B101 01	5/17/12 5/17/12	JH AP	R*BLDG FOOTING / TEMP SVC POLE TIME: 17:00 VRU #: 002227494 T/S: 05/16/2012 08:43 AM VBROWN
A814 01	5/23/12 5/25/12	TW AP	ADDRESS CONFIRMATION TIME: 17:00 VRU #: 002229953 614 Byrd Rd Bunnlevel 28323 # should be on home and by LONG driveway 910-814-2038 Tward T/S: 05/25/2012 09:13 AM TWARD
B103 01	5/25/12 5/25/12	JH AP	R*BLDG FOUND & TEMP SVC POLE VRU #: 002230829
B113 01	5/25/12 5/25/12	JH AP	R*BLDG WATER/DAMP PROOFING VRU #: 002230837
B105' 01	6/04/12 6/04/12	JH DA	R*OPEN FLOOR VRU #: 002234516 1)Nail each side of I joist to sill plate or girder per manufacture instructions.2)Missing I joist on end wall number 10 joist needs to be shifted 6" & add extra I joist.
B105 02	6/05/12 6/05/12	JH AP	R*OPEN FLOOR VRU #: 002234789
R427 01	6/25/12 6/25/12	JH DA	FOUR TRADE ROUGH IN >2500 VRU #: 002243228 1)Need 2 jack studs under each end of 2 windows in master bathroom on back wall.2)Missing front door & garage pass through door.3)Missing double lvls in front & back bedrooms per plans for rafter support.4)Support 2" vent pipe in back right bedroom.5)Need 5 studs under ridge beam load point left of fire place.6)Seal all cracks in air barriers per code.7)Need 3studs under valley bearing ponits upstairs.8)Double rafter upstairs @ end wall of half bath.9)Need hangers on each end of 2x10 beam @ dormer in living room.
I129 01	6/28/12 6/28/12	DT AP	R*INSULATION INSPECTION VRU #: 002244994 T/S: 06/28/2012 11:00 AM DETAYLOR
R427 02	6/28/12 6/28/12	DT AP	FOUR TRADE ROUGH IN >2500 TIME: 17:00 VRU #: 002245363 T/S: 06/28/2012 11:01 AM DETAYLOR
H824 01	7/26/12 7/27/12	OT AP	ENVIR. OPERATIONS PERMIT TIME: 17:00 VRU #: 002258242 T/S: 07/27/2012 11:07 AM SSTEWARD T/S: 07/27/2012 11:07 AM SSTEWARD
R431 01	8/15/12	TI	FOUR TRADE FINAL >2500 TIME: 17:00 VRU #: 002266070



PREPARED 8/14/12, 16:26:30  
Harnett County

INSPECTION TICKET  
INSPECTOR: IVR

PAGE 2  
DATE 8/15/12

ADDRESS . . : 614. BYRD RD  
CONTRACTOR :  
OWNER . . . : JOHNSON JAMIE  
PARCEL . . . : 12-0567- - -0046- -05-  
APPL NUMBER: 12-50028696 CP NEW RESIDENTIAL (SFD)

SUBDIV: MRS OCTA M BYRD DIVISION  
PHONE :  
PHONE :

TYP/SQ	REQUESTED COMPLETED	INSP RESULT	DESCRIPTION RESULTS/COMMENTS
--------	------------------------	----------------	---------------------------------

*8-15-12 APTW*

COMMENTS AND NOTES

