

HTE# 12-5-28833

Harnett County Department of Public Health

Improvement Permit

26846

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: STANCIU BUILDERS PROPERTY LOCATION: 521437 Balland RD
NEW REPAIR EXPANSION SUBDIVISION: Hadden Pointe LOT # 4

Type of Structure: SPD Site Improvements required prior to Construction Authorization Issuance:

Proposed Wastewater System Type: 25% REDUCTION SYSTEM

Projected Daily Flow: 360 GPD

Number of bedrooms: 3 Number of Occupants: 6 max

Basement Yes No Pump Required: Yes No May be required based on final location and elevations of facilities

Type of Water Supply: Community Public Well Distance from well _____ feet Permit valid for: Five years

Permit conditions: _____ No expiration

Authorized State Agent: James E. Mahan Date: 5-8-12 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: STANCIU BUILDERS PROPERTY LOCATION: 521437 Balland RD
Facility Type: SPD New Expansion Repair
SUBDIVISION: Hadden Pointe LOT # 4

Basement? Yes No Basement Fixtures? Yes No

Type of Wastewater System** 25% REDUCTION SYSTEM (Initial) Wastewater Flow: 360 GPD
(See note below, if applicable)

MANAGE to 25% REDUCTION (Repair)

Installation Requirements/Conditions
Septic Tank Size 1000 gallons Number of trenches 4
Pump Tank Size _____ gallons Exact length of each trench 80 feet Trench Spacing: 9 Feet on Center
Trenches shall be installed on contour at a Maximum Trench Depth of: 24" inches Soil Cover: 6 inches
(Trench bottoms shall be level to $\pm 1/4$ " in all directions) (Maximum soil cover shall not exceed 36" above the trench bottom)

Pump Requirements: _____ ft. TDH vs. _____ GPM Aggregate Depth: 6 inches below pipe

Conditions: _____ 2 inches above pipe
12 inches total

**WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.**

***If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.*

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: James E. Mahan Date: 5-8-12
Construction Authorization Expiration Date: 5-8-17

HTE# 12-5-28833

Permit # 26846

Harnett County Department of Public Health Site Sketch

ISSUED TO: STANCI ROEDERS INC PROPERTY LOCATOR: SC 1437 Ballard Rd
SUBDIVISION Madde Ponte LOT # 4

Authorized State Agent: James E. Markham Date: 5-8-12

