

HTE# 12-5-29080

Harnett County Department of Public Health

Improvement Permit

27010

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: STANCI Builders Inc PROPERTY LOCATION: 521403 Cokesburg RD
 NEW REPAIR EXPANSION SUBDIVISION: Cokesburg Park LOT # 82
 Type of Structure: SFD Site Improvements required prior to Construction Authorization Issuance:
 Proposed Wastewater System Type: _____
 Projected Daily Flow: 360 GPD
 Number of bedrooms: 3 Number of Occupants: 6 max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well _____ feet Permit valid for: Five years
 Permit conditions: _____ No expiration

Contact Bill with any questions on layout

Authorized State Agent: James E. Martin Date: 6-14-12 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: STANCI Builders Inc PROPERTY LOCATION: 521403 Cokesburg RD
 Facility Type: SFD New Expansion Repair
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** Manhole to 25% reduction system (Initial) Wastewater Flow: 360 GPD
 (See note below, if applicable)

Manhole to 25% reduction system (repair)

Installation Requirements/Conditions

Septic Tank Size <u>1000</u> gallons	Number of trenches <u>3</u>	Trench Spacing: <u>9</u> Feet on Center
Pump Tank Size <u>1000</u> gallons	Exact length of each trench <u>80</u> feet	Soil Cover: <u>6</u> inches
<u>3 x 1/2" sch 40 valves</u>	Trenches shall be installed on contour at a Maximum Trench Depth of: <u>24"-22"-20"</u> inches (Trench bottoms shall be level to <u>+1-1/4"</u> in all directions)	(Maximum soil cover shall not exceed 36" above the trench bottom)
Pump Requirements: _____ ft. TDH vs. _____ GPM		Aggregate Depth: <u>6</u> inches below pipe <u>2</u> inches above pipe <u>12</u> inches total

Conditions: Contact E.H. with questions on layout

WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: James E. Martin Date: 6-14-12
 Construction Authorization Expiration Date: 6-14-17

HTE# 12-5-29080

Permit # 27010

Harnett County Department of Public Health Site Sketch

ISSUED TO: STANLEY Boelden PROPERTY LOCATOR: 501403 Cokesbury RD
SUBDIVISION Cokesbury Park LOT # 82

Authorized State Agent: James C. Markon Date: 12-14-12

- * Follow Layout
- * Contact E.I.T. WITH Questions.
- * STEPDOWN WILL BE N.B.B.D.B.A
- * Hold systems to ALL setbacks AS TIGHT AS WELL ALLOW

