HTE# 12-5-29524

## Harnett County Department of Public Health

## **Improvement Permit**

27097

A building permit cannot be issued with only an Improvement Permit PROPERTY LOCATION: WIRE RO ISSUED TO: SEYLY HOMES SUBDIVISION KENZAN FARMS EXPANSION Site Improvements required prior to Construction Authorization Issuance: Type of Structure: SFO (57 >56) Proposed Wastewater System Type: 25% REDUCTION SYSTEM 480 Projected Daily Flow: Number of Occupants: 8 Number of bedrooms: Basement □Yes Pump Required: □Yes ► No ☐ May be required based on final location and elevations of facilities Type of Water Supply: 

Community Public 

Well Distance from well 100 feet Five years Permit valid for: Permit conditions: ☐ No expiration Authorized State Agent::

| SEE ATTACHED SITE SKETCH | The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit. **Construction Authorization** (Required for Building Permit) The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958. and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout, ISSUED TO: Sour Homes LZC PROPERTY LOCATION: WIRE RO SUBDIVISION KENLAN FARMS LOT # 76 Facility Type: SED (57~50') New 🗆 Expansion 🗆 Repair Basement? Yes No Basement Fixtures? Yes 25% REDUCTION SYSTEM (Initial) Wastewater Flow: 480 GPD Type of Wastewater System\*\* (See note below, if applicable ) 25% REDUCTION SYSTEM (Repair) Installation Requirements/Conditions Number of trenches 2 Exact length of each trench \_\_\_\_\_ \ OO Trench Spacing: \_\_\_\_\_\_ Feet on Center Septic Tank Size 1000 gallons Pump Tank Size gallons Trenches shall be installed on contour at a Soil Cover: G-18 Maximum Trench Depth of: 18-30 (Maximum soil cover shall not exceed (Trench bottoms shall be level to +/-1/4" 36" above the trench bottom) in all directions) Pump Requirements: \_\_\_\_\_ft. TDH vs. \_\_\_\_ \_\_\_\_\_ inches below pipe Aggregate Depth: \_\_\_\_\_\_ inches above pipe WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA. \*\*If applicable: / understand the system type specified is different from the type specified on the application. I accept the specifications of this permit. Owner/Legal Representative Signature: This Construction Authorization is subject to revocation in the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH Authorized State Agent: \_

Construction Authorization Expiration Date: 8

## Harnett County Department of Public Health Site Sketch

	PROPERTY LOCATON: WICE RO	
ISSUED TO: SAVY HOTHER LLC		7/
1330 [0.	TOTAL TOTAL LINES	#_76_
Authorized State Agent:	ETS (OLIVER TOLKSDORF) Date: 8/23/32	
Authorized state Agent.	194,	
•	1010	
*SYSTEM FLAGGED		
* RUN INTO HILL		
	REPAIR	
	I I KILL	
	ARCH _	
	$  \cdot \cdot \cdot   / \cdot (T)  $	
,		
2.70		
	1 4	
	PATIO	
	\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	
	HOUSE	
	- 32-	
	R 37	
	1 4 1	