HTE# 12-5-29878

## Harnett County Department of Public Health

## **Improvement Permit**

27136

ISSUED TO: 5tancil Builder PROPERTY LOCATION: 7ingen Rd.

SUBDIVISION Substitute Control of Structure Control of S Type of Structure: 5FD 61x42 Proposed Wastewater System Type: 257. Reduction System Projected Daily Flow: 360 GPD Number of Occupants: \_\_\_\_\_\_ max Number of bedrooms: No Basement □Yes Pump Required: □Yes □ No ☐ May be required based on final location and elevations of facilities Type of Water Supply: 

Community Public 

Well Distance from well \_\_\_\_\_\_\_ feet Five years Permit valid for: Permit conditions: ☐ No expiration Authorized State Agent:: Date: 10 /18/242 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit. Construction Authorization (Required for Building Permit) The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout. Basement Fixtures? 

Yes Basement? Yes 25% Reduction System (Initial) Wastewater Flow: 360 GPD Type of Wastewater System\*\* (See note below, if applicable □) Pump to 25% Reduction System (Repair) Number of trenches 2

Exact length of each trench 75 feet Trench Spacing: 9 Feet on Center

Soil Cover: 6-18 inches inches Installation Requirements/Conditions Septic Tank Size 1000 gallons Pump Tank Size \_\_\_\_\_ gallons Maximum Trench Depth of: 16.36 inches (Maximum soil cover shall not exceed (Trench bottoms shall be level to +/-1/4" 36" above the trench bottom) in all directions) Pump Requirements: ft. TDH vs. GPM inches below pipe Aggregate Depth: \_\_\_\_\_\_ inches above pipe WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA. \*\*If applicable: / understand the system type specified is different from the type specified on the application. / accept the specifications of this permit. Owner/Legal Representative Signature: SEE ATTACHED SITE SKETCH Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. Authorized State Agent: Super Proving REHS Date: 10/18/2012 Construction Authorization Expiration Date: 18/2017

## Harnett County Department of Public Health Site Sketch

_	PROPERTY LOCATON: Tingen Rd.	
ISSUED TO: Stancil Builder	SUBDIVISION Surset Ridge	LOT # _ <i>_3</i>
Authorized State Agent: Aryan M wain,	Pá H	0/18/2012
Authorized State Agent: Authorized State Agent:	Date:	017072012

