

HTE# 12-5-383112

Harnett County Department of Public Health Improvement Permit

27240

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Comfort Homes Inc
NEW REPAIR EXPANSION

PROPERTY LOCATION: 501441 Chalkbeats Springs RD
SUBDIVISION Meredith station LOT # 9

Site Improvements required prior to Construction Authorization Issuance:

Type of Structure: SFD

Proposed Wastewater System Type: _____

Projected Daily Flow: 360 GPD

Number of bedrooms: 3 Number of Occupants: 6 max

Basement Yes No

Pump Required: Yes No May be required based on final location and elevations of facilities

Type of Water Supply: Community Public Well Distance from well _____ feet

Permit valid for: Five years
 No expiration

Permit conditions:

NO WATER OR POWER LINES IN SYSTEM OR REPAIR AREA

Authorized State Agent: [Signature] Date: 1-25-13

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Comfort Homes Inc

PROPERTY LOCATION: 501441 Chalkbeats Springs RD
SUBDIVISION Meredith station LOT # 9

Facility Type: _____ New Expansion Repair

Basement? Yes No Basement Fixtures? Yes No

Type of Wastewater System** Pump to 25% REDUCED system (Initial) Wastewater Flow: 360 GPD
(See note below, if applicable)

Pump to 25% REDUCED / LPP (Repair)

Installation Requirements/Conditions

Number of trenches 3

Septic Tank Size 1000 gallons

Exact length of each trench 100 feet

Trench Spacing: 9 Feet on Center

Pump Tank Size 1000 gallons

Trenches shall be installed on contour at a

Soil Cover: 6 inches

Maximum Trench Depth of: 24-318 inches

(Maximum soil cover shall not exceed

(Trench bottoms shall be level to +/-1/4"

36" above the trench bottom)

in all directions)

Pump Requirements: _____ ft. TDH vs. _____ GPM

6 inches below pipe

Aggregate Depth: 2 inches above pipe

Conditions: NO WATER LINES OR POWER LINES IN SEPTIC SYSTEM OR REPAIR AREA.

12 inches total

WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.

NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This

Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 1-25-13
Construction Authorization Expiration Date: 1-25-17

HTE# ^{30311R} 13-5-~~30124R~~

Permit # 27240

Harnett County Department of Public Health Site Sketch

ISSUED TO: Comfort Homes Inc PROPERTY LOCATOR: 301441 Chalybeate Springs RD
SUBDIVISION Meredith Station LOT # 9

Authorized State Agent James E. Markham Date: 1-25-13

**NO WATER OR POWER LINES IN SYSTEM
OR Repair AREAS.*

