## HTE# 13-5-305841 Harnett County Department of Public Health

## Improvement Permit

27284

A building permit cannot be issued with only an Improvement Permit
ISSUED TO: GROV ROBINSON HOMES SUBDIVISION GWEN ONKS LOT # 104
NEW 🖂 REPAIR 🗆 EXPANSION 🗆 Site Improvements required prior to Construction Authorization Issuance:
Type of Structure: SPS (50,50)  Proposed Wastewater System Type: Purplo 25% Reduction
Projected Daily Flow: GPD
Number of bedrooms: Number of Occupants: max
Basement $\square$ Yes $\square$ No $\square$
Pump Required: Likes
Type of Water Supply:   Community   Public   Well Distance from well   Community   Permit valid for:   No expiration
The same of the sa
Authorized State Agent:  Date: 3 14 13  SEE ATTACHED SITE SKETCH
Authorized State Agent::  The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.
Construction Authorization
(Required for Building Permit)
The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958. and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.
ISSUED TO: GAZY ROSINSON HOMES PROPERTY LOCATION: NOTOS
SUBDIVISION CHEN OPKS LOT # 104
Facility Type: STO (SOXGO)  New   Expansion   Repair
Basement?  Yes No Basement Fixtures? Yes No
Type of Wastewater System** PUMPTO 25% REDUCTION SYSTEM (Initial) Wastewater Flow: 480 GPD
(See note below, if applicable ) Rune To 25% REDUCTION (Repair)
Installation Requirements/Conditions  Number of trenches
Septic Tank Size 1000 gallons Exact length of each trench 75 feet Trench Spacing: Feet on Center
fully fall size Surrous many size in the s
Maximum Trench Depth of: 12 inches (Maximum soil cover shall not exceed
(Trench bottoms shall be level to $\pm 1/4$ " 36" above the trench bottom)
in all directions)
Pump Requirements:ft. TDH vs GPM inches below pipe
Aggregate Depth: inches above pipe
Conditions: MINIMUM 6" OF COVER NEWED OVER DRAINFIELD inches above pipe inches total
WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.
**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.
Owner/Legal Representative Signature: Date:
This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This
Construction Authorization is subject to compliance with the perfisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.  SEE ATTACHED SITE SKETCH
Authorized State Agent: Date: 31473
Construction Authorization Expiration Date: 3 4 1

Permit # 27284

## Harnett County Department of Public Health Site Sketch

PROPERTY LOCATON: NC2JOS

ISSUED TO: GREY ROBINSON HOMES SUBDIVISION GWEN ORKS

LOT # 104

Authorized State Agent: Date: 3 2 13

TIMEA - OBSURE TIME 3 - BINE TIME 7 - BINK \* TIME 7 - AETTON

