## Harnett County Department of Public Health

28317

**Improvement Permit** 

A building permit cannot be issued with only an Improvement Permit SAYLY HOMES LLC PROPERTY LOCATION: SUBDIVISION KENLAN FARMS NEW REPAIR | EXPANSION |

Type of structure: STO 34 × 40

Proposed Wastewater System Type: 25% RESUCTION 575.

Projected Daily Flow: 480 GPD Site Improvements required prior to Construction Authorization Issuance: Number of Occupants: 8 max Number of bedrooms: Pump Required: Tes In No May be required based on final location and elevations of facilities Type of Water Supply: 

Community Public 

Well Distance from well 100 feet Five years Permit valid for: Permit conditions: ☐ No expiration DCH 5 Date: Authorized State Agent:: SEE ATTACHED SITE SKETCH The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.. **Construction Authorization** (Required for Building Permit) The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958. and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout. ISSUED TO: SAYN HOMES LLC PROPERTY LOCATION: SUBDIVISION KENLAN FARMS LOT #5; New 🗆 Expansion 🗆 Repair No Basement Fixtures? The KNO System (Initial) Wastewater Flow: 480 GPD Basement? Yes Type of Wastewater System\*\* (See note below, if applicable  $\square$ ) 25% REDUCTION (Repair) Installation Requirements/Conditions Number of trenches Trench Spacing: Feet on Center Soil Cover: 6-12 inches Septic Tank Size 1000 gallons Exact length of each trench 240 Pump Tank Size gallons Trenches shall be installed on contour at a Maximum Trench Depth of: 18-24 inches (Maximum soil cover shall not exceed (Trench bottoms shall be level to +/-1/4" 36" above the trench bottom) in all directions) Pump Requirements: \_\_\_\_\_ft. TDH vs. \_\_\_\_GPM \_\_\_\_\_ inches below pipe Aggregate Depth: \_\_\_\_\_\_ inches above pipe \_\_\_\_\_inches total WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA. \*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit. Owner/Legal Representative Signature: This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH Authorized State Agent: Date: Construction Authorization Expiration Date:

HTE#		3	<u>.5</u>	-30	722	2
------	--	---	-----------	-----	-----	---

Permit # \_ 283 17

## Harnett County Department of Public Health Site Sketch

PROPERTY LOCATON:	
ISSUED TO: DAVAY HORES LLC SUBDIVISION KENLAN FARMS	LOT # 5)
Authorized State Agent: Date: 4 2015	
1 the first the same of the sa	

