HTE# 13-5-30730

Harnett County Department of Public Health

27300

Improvement Permit		27300			
A building permit cannot be issued with only an Improvement Permit					
PROPERTY LOCATION: W					
ISSUED TO: SAVY HOMES LLC SUBDIVISION KENZAN	FARMS	lot # <u>68</u>			
	ements required prior to Construction Authori	zation Issuance:			
Type of Structure: SFD					
Proposed Wastewater System Type: Pume To 25% REDUCTION					
Projected Daily Flow: <u>4780</u> GPD					
Number of bedrooms: Number of Occupants: max					
Basement □Yes X No					
Pump Required: ElYes D No D May be required based on final location and elevations of facili					
Type of Water Supply: \Box Community \bowtie Public \Box Well Distance from well <u>100</u>	feet Permit valid for:	Five years			
Permit con ditions:		No expiration			
Authorized State Agent:: REITS Date: 3151	Э SEE ATTA	CHED SITE SKETCH			
Authorized State Agent:: Date:					
site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a cha	ange in ownership of the site. This permit is subject to o	compliance with the provisions of			
the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit					
Construction Authorizat	ion				
(Required for Building Permit)					
The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958. and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance					
with the attached system layout.	, , , , ,				
ISSUED TO: SAVY HOMES LLC PROPERTY LOCATION:	When Ro				
		LOT # 68			
SUBDIVISION KEN		LUI # <u>68</u>			
Facility Type: SFD X New C Expansion	Repair				
Basement? 🗆 Yes 🖾 No Basement Fixtures? 🛄 Yes 🛣 No					
Type of Wastewater System** PUME TO 25% REDUCTION	(Initial) Wastewater Flow: _	<u>ARO</u> GPD			
(See note below, if applicable 🗆)					
Pumetty 25% REDUCTION (Repair)					
Installation Requirements/Conditions Number of trenches 3	C				
Septic Tank Size <u>1000</u> gallons Exact length of each trench <u>70</u>		Feet on Center			
Pump Tank Size 1000 gallons Trenches shall be installed on contour at a	Soil Cover: <u>6-72</u> i	nches			
Maximum Trench Depth of: <u>18–24</u>	_ inches (Maximum soil cover shall n	ot exceed			
(Trench bottoms shall be level to +/-1/4"	36" above the trench botto	om)			
in all directions)		,			
Pump Requirements:ft. TDH vs GPM		inches below pipe			
	Aggregate Depth:				
Conditions: SUPPLY LINE TO EASEMENT ALREADY INSTA	-	inches total			
		menco cotur			

WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit. Owner/Legal Representative Signature: _ Date: This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This T......... SEE ATTACHED SITE SKETCH al Bulan for C له مد اد. diation of all Cor

Construction Authorization A suplect	to compliance with the previsions of	the Laws and Rules for Sewage Treatment an	d Disposal and to the conditions of this permit.	SEE ATTACHED SHE SKEICH
Authorized State Agent: _		Construction Author	Date: 3)35)33 Tization Expiration Date: 315/18	

