

135 30745

DAVID MILLER, PE  
6300 Creedmoor Rd, STE 170#363  
Raleigh, NC 27612  
(919) 422-8932 (Office) ; DAVE@DMA-PA.COM

April 23, 2014

Stancil Builders  
466 Stancil Road  
Angier, NC 27501  
E-mailed to flstancil@embarqmail.com (Attn. : Mr. Freddie L. Stancil)

Re.: Engineering Analysis – Framing  
Lot 141 Patton Point Subdivision, Broadway, Harnett County, NC  
Job No.: 14DDM-0423G

To whom it may concern/ Inspections Dept.:

The undersigned arrived on-site 4-23-14 to observe, measure and analyze the framed conditions for the following:

- 1) The portal wall at the garage was observed, measured and analyzed for lateral loading conditions. Specifically the 1/2" diameter bolts used in lue of the 5/8" planned. Based on the drag beam element of the garage door header and the perpendicular wall sections at the ends the 1/2" diameter bolts are adequate to transfer and support the loading conditions (uplift and lateral).

Sincerely,

David Miller, PE

DEM/14DDM-0423G

