

HTE# 13-5-32408

Harnett County Department of Public Health Improvement Permit

27599

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Phillip L + Susan G Williams PROPERTY LOCATION: 521467 WADE STEPHANSON
 NEW REPAIR EXPANSION SUBDIVISION: Fieldstone Farms LOT # 15
 Type of Structure: SFD + Garage Site Improvements required prior to Construction Authorization Issuance: _____
 Proposed Wastewater System Type: 25% REDUCTION
 Projected Daily Flow: 3600 GPD
 Number of bedrooms: 3 Number of Occupants: 6 max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well _____ feet Permit valid for: Five years
 Permit conditions: _____ No expiration
Contractor to meet onsite prior to INSTALL

Authorized State Agent: James E. Monahan Date: 11-15-13 SEE ATTACHED SITE SKETCH
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Phillip L + Susan G Williams PROPERTY LOCATION: 521467 WADE STEPHANSON
 SUBDIVISION: Fieldstone Farms LOT # 15
 Facility Type: SFD + Garage New Expansion Repair
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** 25% REDUCTION SYSTEM (Initial) Wastewater Flow: 3600 GPD
 (See note below, if applicable)
Pump to 25% REDUCTION (Repair)

Installation Requirements/Conditions

Septic Tank Size <u>1000</u> gallons	Number of trenches <u>3</u>	Exact length of each trench <u>100</u> feet	Trench Spacing: <u>9</u> Feet on Center
Pump Tank Size _____ gallons	Trenches shall be installed on contour at a	Maximum Trench Depth of: <u>22-7/8</u> inches	Soil Cover: <u>6</u> inches
	(Trench bottoms shall be level to +/- 1/4"	in all directions)	(Maximum soil cover shall not exceed 36" above the trench bottom)

Pump Requirements: _____ ft. TDH vs. _____ GPM
 Aggregate Depth: 6 inches below pipe
2 inches above pipe
12 inches total

Conditions: Contractor to meet onsite prior to INSTALL.

**WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.**

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____
 This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: James E. Monahan Date: 11-15-13
 Construction Authorization Expiration Date: 11-15-18

HTE# 13-5-32408

Permit # 27599

Harnett County Department of Public Health Site Sketch

PROPERTY LOCATION: 2021407 WADE STEPHANSON

ISSUED TO: Phillip Lt Susan G Williams SUBDIVISION Fieldstone Estates LOT # 15

Authorized State Agent: James E Mashant Date: 11-15-13

