

HTE# 14-5-34522R

Har...t County Department of Public Health

28036

### Improvement Permit

GARY ROBINSON HOMES LLC A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Trace Homes Inc PROPERTY LOCATION: DAY TRADING CT  
 NEW  REPAIR  EXPANSION  SUBDIVISION: MARKET PLACE LOT # 87  
 Type of Structure: SFD (43'x46.5') Site Improvements required prior to Construction Authorization Issuance:  
 Proposed Wastewater System Type: 25% REDUCTION SYSTEM  
 Projected Daily Flow: 480 GPD  
 Number of bedrooms: 4 Number of Occupants: 8 max  
 Basement  Yes  No  
 Pump Required:  Yes  No  May be required based on final location and elevations of facilities  
 Type of Water Supply:  Community  Public  Well Distance from well 100 feet Permit valid for:  Five years  
 Permit conditions:  No expiration

Authorized State Agent: [Signature] Date: 9/15/14 SEE ATTACHED SITE SKETCH  
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.  
REVISED 12/3/15 [Signature]

### Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

GARY ROBINSON HOMES LLC  
 ISSUED TO: Trace Homes Inc PROPERTY LOCATION: DAY TRADING CT  
 SUBDIVISION: MARKET PLACE LOT # 87  
 Facility Type: SFD (43'x46.5')  New  Expansion  Repair  
 Basement?  Yes  No Basement Fixtures?  Yes  No  
 Type of Wastewater System\*\* 25% REDUCTION SYSTEM (Initial) Wastewater Flow: 480 GPD  
 (See note below, if applicable)  Pump To 25% REDUCTION (Repair)

**Installation Requirements/Conditions**  
 Septic Tank Size 1000 gallons  
 Pump Tank Size \_\_\_\_\_ gallons  
 Number of trenches 4  
 Exact length of each trench 60 feet  
 Trenches shall be installed on contour at a  
 Maximum Trench Depth of: 18-30 inches  
 (Trench bottoms shall be level to +/-1/4" in all directions)  
 Trench Spacing: 9 Feet on Center  
 Soil Cover: 6-18 inches  
 (Maximum soil cover shall not exceed 36" above the trench bottom)  
 Pump Requirements: \_\_\_\_\_ ft. TDH vs. \_\_\_\_\_ GPM \_\_\_\_\_ inches below pipe  
 Aggregate Depth: \_\_\_\_\_ inches above pipe  
 \_\_\_\_\_ inches total  
 Conditions: MEET ON SITE TO VERIFY FIELD LOCATION AND NECESSITY OF A PUMP.

**WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.**

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: \_\_\_\_\_ Date: \_\_\_\_\_

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 9/15/14  
REVISED 12/3/15 Construction Authorization Expiration Date: 9/15/19

HTE# 14-5-34522R

Permit # 28036

# Harnett County Department of Public Health Site Sketch

GARY ROBINSON HOMES LLC

PROPERTY LOCATOR: DAY TRADING CT  
ISSUED TO: TRACE HOMES INC SUBDIVISION MARKET PLACE LOT # 87

Authorized State Agent:

~~RENS (OLIVER TOLKSDORF)~~ Date: 9/15/14  
RG 1560 12/3/15

