## HTE# 14-5-3473212 Harl.... County Department of Public ...alth

28126

Improvement Permit

A building permit cannot be issued with only an Improvement Permit PROPERTY LOCATION: W: 11 Lucas Rd ISSUED TO: JSJ Boilders SUBDIVISION Sweetwater Site Improvements required prior to Construction Authorization Issuance: , EXPANSION REPAIR Type of Structure: SFD JEX34 Proposed Wastewater System Type: 25% Reduction System Projected Daily Flow: 480 Number of Occupants: 8 max Number of bedrooms: Basement TYes ☐ May be required based on final location and elevations of facilities Pump Required: Yes Five years Type of Water Supply: 

Community Public Well Distance from well feet Permit valid for: ☐ No expiration Permit conditions: The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.. Construction Authorization (Required for Building Permit) The construction and installation requirements of Rules .1950, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout. ISSUED TO: JSJ Builders PROPERTY LOCATION: W: 11 Lucar Rd SUBDIVISION Juce + water Facility Type: SFD New Expansion Repair Basement Fixtures? 

Yes 25 % Reduction System (Initial) Wastewater Flow: 480 GPD Type of Wastewater System\*\* (See note below, if applicable ) 25% Reduction System (Repair) Number of trenches / Installation Requirements/Conditions Exact length of each trench \_\_\_\_\_\_\_\_ feet \_\_\_\_ Trench Spacing: \_\_\_\_\_\_\_ Feet on Center Septic Tank Size / OOO gallons Trenches shall be installed on contour at a Pump Tank Size gallons Maximum Trench Depth of: 44-62 inches (Maximum soil cover shall not exceed (Trench bottoms shall be level to +/-1/4" 36" above the trench bottom) in all directions) Pump Requirements: \_\_\_\_\_ft. TDH vs. \_\_\_\_ GPM inches below pipe Conditions: If septic system can not be installed as shown inches above pipe on site sketch ponot install & call office WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA. \*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit. Owner/Legal Representative Signature: This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH Authorized State Agent. Construction Authorization Expiration Date: 12/17/2019

## Harnett County Department of Public Health Site Sketch

		PROPERTY LOCATON: Will Lucas Rd	
ISSUED TO:	J5JBuilder	SUBDIVISION Sweetwater	LOT # /6
	1	1	/
Authorized Sta	te Agent: Sugar Mysicin,	RE145 Date: 12/13	7/2014

