

Harnett County
Inspection Inquiry - Results Comments

7/06/16
11:50:54

PARCEL NUMBER	:	12-0546- - -0063- - -	
Property address	:	4071 MCLEAN CHAPEL CHURCH RD	
Appl, structure nbr	:	15 50035284 000 000	12
Permit type, seq nbr	:	CPSF 00 CP * SFD	
Inspection type, seq nbr	:	R425 0004 FOUR TRADE ROUGH IN	
Inspection status, date	:	INSPECTION COMPLETED	6/30/16

Inspection Results Comments

1)Items #3,5,11,13 &14 still not corrected from first inspection.
 2)Items # 2,3,& 4 not corrected from last inspection.

OK TO SIDE DO NOT INSULATE

Press Enter to continue.
F3=Exit F12=Cancel

Bottom

Harnett County
Inspection Inquiry - Results Comments

7/06/16
11:51:04

PARCEL NUMBER	:	12-0546- - -0063- - -	
Property address	:	4071 MCLEAN CHAPEL CHURCH RD	
Appl. structure nbr	:	15 50035284 000 000	12
Permit type, seq nbr	:	CPSF 00 CP * SFD	
Inspection type, seq nbr	:	R425 0003 FOUR TRADE ROUGH IN	
Inspection status, date	:	INSPECTION COMPLETED	6/23/16

Inspection Results Comments

1)Items #3,5,11,13 &14 were not corrected.2)Need truss repair letter for damaged roof truss in middle bedroom upstairs 1 @ window & 3 @ door.3)Missing hurricane straps on 3ply roof truss in middle bedroom per truss documents.4)3' head of water on drain line test.5)Fire caulk hole in top plate @ end of tub in bonus room.6)Straps missing on end of lvls in bonus room.7)Missing nails in roof truss hangers in bonus room.8)Seal all cracks in air barriers in bonus room.9)Nail osb on end wall between

Press Enter to continue.
F3=Exit F12=Cancel

More...

Harnett County
Inspection Inquiry - Results Comments

PARCEL NUMBER : 12-0546- - -0063- - -
 Property address : 4071 MCLEAN CHAPEL CHURCH RD
 Appl, structure nbr : 15 50035284 000 000
 Permit type, seq nbr : CPSF 00 CP * SFD
 Inspection type, seq nbr : R425 0003 FOUR TRADE ROUGH IN
 Inspection status, date : INSPECTION COMPLETED 6/23/16

12

Inspection Results Comments

windows in back right bedroom.10)Add stud on end wall & to
 left of window in front left bedroom over 16".11)Replace 2
 cut floor joist under master bathroom.
 OK TO SIDE DO NOT INSULATE

Press Enter to continue.
F3=Exit F12=Cancel

Bottom

HARRETT COUNTY CASH RECEIPTS

*** CUSTOMER RECEIPT ***

Oper: DJOHNSON Type: CP Drawer: 1
Date: 7/06/16 54 Receipt no: 6990

Year	Number	Amount
2015	50035204	
4071 MCLEAN CHAPEL CHURCH RD		
KUNNLEVEL, NC 28323		
B1	Bp - PERMIT FEES	\$50.00

REINSPECTION FEE

AARON GARNER

Tender detail	
CP CREDIT CARD	\$50.00
Total tendered	\$50.00
Total payment	\$50.00

Trans date: 7/06/16 Time: 11:51:40

** THANK YOU FOR YOUR PAYMENT **