

HTE# 15-5-35547

# Harnett County Department of Public Health Improvement Permit

28256

A building permit cannot be issued with only an Improvement Permit

PROPERTY LOCATION: McLean Chapel Church Rd

ISSUED TO: David Smith

SUBDIVISION \_\_\_\_\_ LOT # 14A

NEW  REPAIR  EXPANSION

Site Improvements required prior to Construction Authorization Issuance: \_\_\_\_\_

Type of Structure: SFD 22x28'

Proposed Wastewater System Type: 25% Reduction System

Projected Daily Flow: 240 GPD

Number of bedrooms: 2 Number of Occupants: 4 max

Basement  Yes  No

Pump Required:  Yes  No  May be required based on final location and elevations of facilities

Type of Water Supply:  Community  Public  Well Distance from well \_\_\_\_\_ feet

Permit valid for:  Five years  
 No expiration

Permit conditions: \_\_\_\_\_

Authorized State Agent: Bryan McJoin RCHS

Date: 3/12/2015

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

## Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: David Smith

PROPERTY LOCATION: McLean Chapel Church Rd

SUBDIVISION \_\_\_\_\_ LOT # 14A

Facility Type: SFD  New  Expansion  Repair

Basement?  Yes  No Basement Fixtures?  Yes  No

Type of Wastewater System\*\* 25% Reduction System (Initial) Wastewater Flow: 240 GPD

(See note below, if applicable)

Pump to 25% Reduction System (Repair)

### Installation Requirements/Conditions

Septic Tank Size 1000 gallons

Number of trenches 1

Exact length of each trench 150 feet

Trench Spacing: 9 Feet on Center

Pump Tank Size \_\_\_\_\_ gallons

Trenches shall be installed on contour at a

Soil Cover: 6 inches

Maximum Trench Depth of: 12-18 inches

(Maximum soil cover shall not exceed

(Trench bottoms shall be level to +/-1/4"

36" above the trench bottom)

in all directions)

Pump Requirements: \_\_\_\_\_ ft. TDH vs. \_\_\_\_\_ GPM

Aggregate Depth: \_\_\_\_\_ inches below pipe

Conditions: French Drain to be installed 30 inches deep

\_\_\_\_\_ inches above pipe  
\_\_\_\_\_ inches total

**WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.  
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.**

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: \_\_\_\_\_

Date: \_\_\_\_\_

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This

Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: Bryan McJoin RCHS

Date: 3/12/2015

Construction Authorization Expiration Date: 3/12/2020

HTE# 15-5-35547

Permit # 28256

# Harnett County Department of Public Health Site Sketch

ISSUED TO: David Smith

PROPERTY LOCATOR: McLean Chapel Church rd.  
SUBDIVISION \_\_\_\_\_ LOT # 14A

Authorized State Agent: Bryan McSwain, RCHS

Date: 3/12/2015

\* The French Drain  
can go in either  
direction

① or ②

Solid PVC  
can be used  
to daylight  
the French  
Drain

