

COUNTY OF HARNETT
Building Inspections Department
Planning Services

Certificate of Compliance: _____ **Occupancy:**

Certificate issued pursuant to the requirements of North Carolina General Statute 153A-363 and Harnett County Zoning Ordinances. This certifies at the time of issuance, this structure was in compliance with the various ordinances of the County of Harnett and the North Carolina State Building Codes. For the following:

Use Classification: Residential

Permit Numbers

Name: H + H Onsite Home

Building: _____

Electrical: _____

Address: 51 Blount Rd

Insulation: _____

Plumbing: _____

Mechanical: _____

MFG Home: _____

Date: 10/20/15

Building Official: [Signature]

ADDRESS . : 51 BLANCHARD RD SUBDIV:
CONTRACTOR : H & H ONSITE HOMES LLC PHONE : (910) 486-4864
OWNER . . : KIGER CHARLES R & CYNTHIA R PHONE :
PARCEL . . : 03-9587- - -0020- -39-
APPL NUMBER: 15-50035999 CP NEW RESIDENTIAL (SFD)
DIRECTIONS : T/S: 04/27/2015 01:54 PM JBROCK ----
L ONTO 27W L BLANCHARD RD

STRUCTURE: 000 000 46.10X48 3BDR CRAWL W/ GARAGE

FLOOD ZONE : FLOOD ZONE X
BEDROOMS : 3000000.00 PROPOSED USE : SFD
SEPTIC - EXISTING? : NEW TANK WATER SUPPLY : COUNTY

PERMIT: CPSF 00 CP * SFD

TYP/SQ	REQUESTED COMPLETED	INSP RESULT	DESCRIPTION RESULTS/COMMENTS
A814 01	6/10/15 6/10/15	SB AP	ADDRESS CONFIRMATION TIME: 17:00 VRU #: 002670842 51 BLANCHARD RD SANFORD 27332 T/S: 06/10/2015 11:10 AM SBENNETT -----
B101 01	6/10/15 6/10/15	MR AP	R*BLDG FOOTING / TEMP SVC POLE TIME: 17:00 VRU #: 002670859 T/S: 06/10/2015 12:58 PM MREARIC -----
B103 01	6/23/15 6/23/15	TSG DA	R*BLDG FOUND & TEMP SVC POLE TIME: 17:00 VRU #: 002677300 1-NO PLANS ON SITE 2- FOUNDATION BACKFILLED CAN NOT VERIFY FOOTING PROJECTION.
B103 02	6/24/15 6/24/15	MR DA	R*BLDG FOUND & TEMP SVC POLE TIME: 17:00 VRU #: 002678670 T/S: 06/24/2015 02:37 PM MREARIC ----- still no plans or foundation exposed
B103 03	6/25/15 6/25/15	TSG AP	R*BLDG FOUND & TEMP SVC POLE TIME: 17:00 VRU #: 002679454
B105 01	6/29/15 6/29/15	TSG AP	R*OPEN FLOOR TIME: 17:00 VRU #: 002680189
B101 02	7/23/15 7/23/15	MR AP	R*BLDG FOOTING / TEMP SVC POLE TIME: 17:00 VRU #: 002692523 ext footing needed T/S: 07/23/2015 01:30 PM MREARIC -----
R425 01	7/29/15 7/29/15	TSG DP	FOUR TRADE ROUGH IN VRU #: 002694461 1- NO TRUSS PLANS ON SITE. 2- WINDOWS AND DOORS NOT COMPLETE . JOB NOT READY.
B103 04	8/10/15 8/10/15	JH AP	R*BLDG FOUND & TEMP SVC POLE TIME: 17:00 VRU #: 002701118 EXT FOUNDATION NEEDED -----
R425 02	8/10/15 8/10/15	JH DP	FOUR TRADE ROUGH IN TIME: 17:00 VRU #: 002700490 1)Strap each side of garage door header from top plate to 1' below header per portal framing detail.2)Fire caulk cables & termite pipes @ top plate in back left corner of garage.3)Seal all holes in air barrier @ water heater in garage.4)Post on front & back porch need to be installed per plans.5)Block joints on osb 4' from corners.6)Nail 2ply truss in front right bedroom per truss documents.7)Fire caulk 2 holes in top plate on back wall in laundry room.8)Missing carbon/smoke outside of upstairs bed door.9)Missing baffels throughout house.10)Missing bracing on roof trusses.11)Missing hurricaine straps on A1 truss over front door & A4,A5,A6 & A7 in master bedroom on front wall.12)Need receptacle on front of house accessibled from grade.

----- CONTINUED ONTO NEXT PAGE -----

ADDRESS . : 51 BLANCHARD RD SUBDIV:
CONTRACTOR : H & H ONSITE HOMES LLC PHONE : (910) 486-4864
OWNER . . : KIGER CHARLES R & CYNTHIA R PHONE :
PARCEL . . : 03-9587- - -0020- -39-
APPL NUMBER: 15-50035999 CP NEW RESIDENTIAL (SFD)

TYP/SQ	REQUESTED COMPLETED	INSP RESULT	DESCRIPTION RESULTS/COMMENTS
			OK TO SIDE DO NOT INSULATE
R425 03	8/12/15 8/12/15	MR AP	FOUR TRADE ROUGH IN TIME: 17:00 VRU #: 002702090 T/S: 08/12/2015 02:03 PM MREARIC ----- posts to be installed per code at final
I129 01	8/14/15 8/14/15	TSG AP	R*INSULATION INSPECTION TIME: 17:00 VRU #: 002703270
H824 01	8/26/15 8/26/15	JM AP	ENVIR. OPERATIONS PERMIT TIME: 17:00 VRU #: 002710168 T/S: 08/27/2015 10:31 AM SSTEWARD ----- T/S: 08/27/2015 10:31 AM SSTEWARD -----
R125 01	9/17/15 9/17/15	MR AP	ONE TRADE ROUGH IN TIME: 17:00 VRU #: 002718948 STONE INSPECTION T/S: 09/17/2015 01:48 PM MREARIC -----
E209 01	9/24/15 9/24/15	MR AP	R*ELEC TEMP POWER CERT TIME: 17:00 VRU #: 002722130 T/S: 09/24/2015 02:49 PM MREARIC ----- need premise #
R429 01	10/20/15	TI	FOUR TRADE FINAL TIME: 17:00 VRU #: 002731883 WOULD LIKE INSPECTION AFTER LUNCH PLEASE

----- COMMENTS AND NOTES -----