

**COUNTY OF HARNETT**  
**Building Inspections Department**  
**Planning Services**

**Certificate of Compliance:** \_\_\_\_\_ **Occupancy:** ✓

Certificate issued pursuant to the requirements of North Carolina General Statute 153A-363 and Harnett County Zoning Ordinances. This certifies at the time of issuance, this structure was in compliance with the various ordinances of the County of Harnett and the North Carolina State Building Codes. For the following:

Use Classification: SFD

Name: ADH Onsite Homes LLC

Address: 11 Winged Foot Dr

Date: 12-12-16

Building Official: James T Hall

**Permit Numbers**

Building: \_\_\_\_\_

Electrical: 15

Insulation: 5003761

Plumbing: \_\_\_\_\_

Mechanical: \_\_\_\_\_

MFG Home: \_\_\_\_\_

ADDRESS : 11 WINGED FOOT DR SUBDIV: WALNUT GROVE 37LOTS  
 CONTRACTOR : H & H ONSITE HOMES LLC PHONE : (910) 486-4864  
 OWNER : EVEN PAR DEVELOPMENT LLC PHONE :  
 PARCEL : 01-0525- - -0062- -27-  
 APPL NUMBER: 15-50037641 CP NEW RESIDENTIAL (SFD)  
 DIRECTIONS : T/S: 12/03/2015 01:36 PM JBROCK ----  
 11 WINGED FOOT LOT 18

**STRUCTURE: 000 000 36X42 4BDR CRAWL W/ GARAGE**

FLOOD ZONE : FLOOD ZONE X  
 # BEDROOMS : 4000000.00 PROPOSED USE : SFD  
 SEPTIC - EXISTING? : NEW TANK WATER SUPPLY : COUNTY

**PERMIT: CPSF 00 CP \* SFD**

| TYP/SQ  | REQUESTED COMPLETED | INSP RESULT | DESCRIPTION RESULTS/COMMENTS  |
|---------|---------------------|-------------|---|
| B101 01 | 3/03/16             | JH          | R*BLDG FOOTING / TEMP SVC POLE TIME: 17:00 VRU #: 002783884   |
|         | 3/03/16             | AP          |   |
| A814 01 | 3/09/16             | SB          | ADDRESS CONFIRMATION TIME: 17:00 VRU #: 002786622   |
|         | 3/09/16             | AP          | 11 WINGED FOOT DR BUNNLEVEL 28323<br>T/S: 03/09/2016 09:30 AM SBENNETT -----  |
| B103 01 | 3/09/16             | JH          | R*BLDG FOUND & TEMP SVC POLE TIME: 17:00 VRU #: 002786614   |
|         | 3/09/16             | AP          |   |
| B105 01 | 3/23/16             | BS          | R*OPEN FLOOR TIME: 17:00 VRU #: 002791994   |
|         | 3/23/16             | AP          | T/S: March 23, 2016 08:18 AM BSUTTON -----  |
| R425 01 | 4/20/16             | JH          | FOUR TRADE ROUGH IN TIME: 17:00 VRU #: 002804391  |
|         | 4/20/16             | DA          | NO plans in box or truss documents & layout-----  |
| R425 02 | 4/21/16             | JH          | FOUR TRADE ROUGH IN TIME: 17:00 VRU #: 002805976  |
|         | 4/21/16             | DP          | 1)Install front & back porch post per plans.2)Strap each side of garage header from top plate to 1' below header.3)Add stud on end wall in master bed closet over 16".4)No bundling of wires at switches or etc. throughout house.5)Need block under back porch beam over back door.6)Need 2-2x6 @ stairs end of lvl inliving room.7)Missing nails in hurricane straps on front porch.8)Missing nails in roof truss hangers at top of stairs & loft.9)Add stud on end wall in back right bed over 16".10)3' head of water on drain line test.11)Nail osb on end wall in back left bedroom.12)Missing hurricane straps on 2ply truss in chase @ top of stairs.13)Missing Tbracing on gable trusses.14)Missing truss bracing on M1 & M2 truss.15)Nail 2ply truss per truss documnets.16)Repair hole inside of foundation wall in crawl @ drain line<br>T/S: 04/21/2016 10:12 AM JHALL ----- |
| R425 03 | 4/27/16             | JH          | FOUR TRADE ROUGH IN TIME: 17:00 VRU #: 002807584  |
|         | 4/27/16             | DP          | T/S: 04/25/2016 03:36 PM LBENNETT -----<br>Items # 5,6 & 10 were not corrected-----   |
| R425 04 | 4/29/16             | JH          | FOUR TRADE ROUGH IN TIME: 17:00 VRU #: 002809598  |
|         | 4/29/16             | AP          | T/S: 04/28/2016 02:08 PM JBROCK -----   |
| I129 01 | 5/03/16             | JH          | R*INSULATION INSPECTION VRU #: 002810349  |
|         | 5/03/16             | AP          |   |
| R125 01 | 6/08/16             | JH          | ONE TRADE ROUGH IN TIME: 17:00 VRU #: 002827418   |
|         | 6/08/16             | AP          | T/S: 06/07/2016 01:03 PM JBROCK -----<br>stone inspection   |

ADDRESS : 11 WINGED FOOT DR  
CONTRACTOR : H & H ONSITE HOMES LLC  
OWNER : EVEN PAR DEVELOPMENT LLC  
PARCEL : 01-0525- - -0062- -27-  
APPL NUMBER: 15-50037641 CP NEW RESIDENTIAL (SFD)

SUBDIV: WALNUT GROVE 37LOTS  
PHONE : (910) 486-4864  
PHONE :

| TYP/SQ  | REQUESTED COMPLETED         | INSP RESULT       | DESCRIPTION RESULTS/COMMENTS  |
|---------|-----------------------------|-------------------|---|
| H824 01 | 6/22/16<br>6/23/16          | OT<br>AP          | ENVIR. OPERATIONS PERMIT TIME: 17:00 VRU #: 002835676<br>T/S: 06/23/2016 10:43 AM SSTEWARD<br>T/S: 06/23/2016 10:43 AM SSTEWARD   |
| E209 01 | 7/13/16<br>7/13/16          | JH<br>AP          | R*ELEC TEMP POWER CERT TIME: 17:00 VRU #: 002842854<br>T/S: 07/12/2016 10:13 AM JBROCK  |
| R429 01 | 11/18/16<br>11/18/16        | JH<br>DA          | FOUR TRADE FINAL TIME: 17:00 VRU #: 002899854<br>T/S: 11/16/2016 04:05 PM JBROCK<br><del>1</del> Top step at front & back porches is over 8 1/4". <del>2</del> Need energy certificate. <del>3</del> Remove wood from under house. <del>4</del> Need 3x3 landing at bottom of steps for back porch. |
| R429 02 | 12/12/16<br><u>12-12-16</u> | TI<br><i>APJY</i> | FOUR TRADE FINAL TIME: 17:00 VRU #: 002908713<br>T/S: 12/09/2016 08:43 AM JBROCK  |

COMMENTS AND NOTES