

COUNTY OF HARNETT
Building Inspections Department
Planning Services

Certificate of Compliance: _____ **Occupancy:** X

Certificate issued pursuant to the requirements of North Carolina General Statute 153A-363 and Harnett County Zoning Ordinances. This certifies at the time of issuance, this structure was in compliance with the various ordinances of the County of Harnett and the North Carolina State Building Codes. For the following:

Use Classification: SFD

Name: Chadwick & Mallory Goodnight

Address: 548 Rollins Mill Road

Holly Springs NC 27540

Date: 07/29/2016

Permit Numbers

Building: 16-50037971

Electrical: _____

Insulation: _____

Plumbing: _____

Mechanical: _____

MFC No: XXXXXXXXXXXXXXXXXXXX

Building Official: Brad Sutton

ADDRESS . . : 548 ROLLINS MILL RD SUBDIV:
CONTRACTOR : PHONE :
OWNER . . : GOODNIGHT CHADWICK & MALLORY PHONE : (919) 669-8586
PARCEL . . : 05-0626- - -0052- -09-
APPL NUMBER: 16-50037971 CP NEW RESIDENTIAL (SFD)
DIRECTIONS : T/S: 02/05/2016 12:58 PM JBROCK ----
CHRISTIAN LIGHT RD L ON 42 W R ON
ROLLINS MILL RD DRIVEWAY ON R ABOUT 1/2
MILE DOWN ROLLINS MILL
premise #77005751

STRUCTURE: 000 000 80X66 3BDR CRAWL W/ GARAGE & DECK

FLOOD ZONE : FLOOD ZONE X
BEDROOMS : 3000000.00 PROPOSED USE : SFD
SEPTIC - EXISTING? : NEW TANK WATER SUPPLY : COUNTY

PERMIT: CPSF 00 CP * SFD

TYP/SQ	REQUESTED COMPLETED	INSP RESULT	DESCRIPTION RESULTS/COMMENTS
B101 01	3/11/16 3/11/16	BS DA	R*BLDG FOOTING / TEMP SVC POLE TIME: 17:00 VRU #: 002787919 T/S: March 11, 2016 11:09 AM BSUTTON ----- Footing contractor has opted to get engineers letter on footing. Once letter is approved, footing will be approved T/S: March 14, 2016 09:47 AM BSUTTON ----- T/S: March 14, 2016 09:47 AM BSUTTON -----
B101 02	3/14/16 3/14/16	BS AP	R*BLDG FOOTING / TEMP SVC POLE TIME: 17:00 VRU #: 002788727 T/S: March 14, 2016 09:49 AM BSUTTON ----- T/S: March 14, 2016 09:52 AM BSUTTON ----- Footing inspection was done thrid party by John A. McRae. Letter is attached
A814 01	3/24/16 3/24/16	SB AP	ADDRESS CONFIRMATION TIME: 17:00 VRU #: 002793917 548 ROLLINS MILL RD HOLLY SPRINGS 27540 T/S: 03/24/2016 09:32 AM SBENNETT -----
B103 01	3/24/16 3/24/16	KS AP	R*BLDG FOUND & TEMP SVC POLE TIME: 17:00 VRU #: 002793909 would like after lunch T/S: 03/24/2016 03:40 PM KSLATTUM -----
E207 01	3/29/16 3/29/16	KS AP	R*ELEC TEMP SERVICE POLE TIME: 17:00 VRU #: 002795342 T/S: 03/28/2016 11:57 AM LBENNETT ----- T/S: 03/29/2016 02:53 PM KSLATTUM ----- Need premise number.
B105 01	4/01/16 4/01/16	DT AP	R*OPEN FLOOR VRU #: 002797744 T/S: 04/01/2016 10:14 AM DETAYLOR -----
R425 01	5/06/16 5/06/16	BS DA	FOUR TRADE ROUGH IN TIME: 13:00 VRU #: 002812964 T/S: 05/05/2016 01:50 PM JFORBES ----- WOULD LIKE AFTERNOON T/S: May 06, 2016 03:21 PM BSUTTON ----- 1.INstall bolt/flash/ lintel over garage door. 2. Insulation and air barrier behind fireplace. 3. Build chase around HVAC duct and firestop.
I129 01	5/12/16 5/12/16	BS DA	R*INSULATION INSPECTION TIME: 08:00 VRU #: 002814986 T/S: 05/11/2016 10:46 AM JFORBES ----- CUSTOMER WOULD LIKE AM INSPECTION PLEASE T/S: May 12, 2016 10:30 AM BSUTTON ----- Firestop top of hvac chase with minimum 3/4 inch OSB or plywood, cut tight to fit around duct, and firefoam between

ADDRESS : 548 ROLLINS MILL RD
CONTRACTOR :
OWNER : GOODNIGHT CHADWICK & MALLORY
PARCEL : 05-0626- - -0052- -09-
APPL NUMBER: 16-50037971 CP NEW RESIDENTIAL (SFD)

SUBDIV:
PHONE :
PHONE : (919) 669-8586

TYP/SQ	REQUESTED COMPLETED	INSP RESULT	DESCRIPTION RESULTS/COMMENTS
I129 02	6/07/16 6/07/16	BS AP	duct and plywood (it needs to look just like the floor penetration below. 2. Lintel must have flashing that extends up behind housewrap, and out and over lintel. R*INSULATION INSPECTION TIME: 17:00 VRU #: 002826428 T/S: 06/06/2016 09:20 AM LBENNETT T/S: June 07, 2016 11:50 AM BSUTTON
R425 02	6/07/16 6/07/16	BS AP	FOUR TRADE ROUGH IN TIME: 17:00 VRU #: 002826436 T/S: 06/06/2016 09:20 AM LBENNETT T/S: June 07, 2016 11:50 AM BSUTTON
H824 01	7/11/16 7/11/16	JM AP	ENVIR. OPERATIONS PERMIT TIME: 17:00 VRU #: 002843001 T/S: 07/12/2016 12:51 PM SSTEWARD T/S: 07/12/2016 12:52 PM SSTEWARD
R429 01	7/21/16 7/21/16	BS DA	FOUR TRADE FINAL TIME: 17:00 VRU #: 002847283 Morning inspection if possible. Please call with status. -- Trying to get meter pulled from temp pole and set on the house. 919-669-8586 Thanks Chad T/S: July 21, 2016 08:26 AM BSUTTON
R429 02	7/29/16 <u>7-29-16</u>	TI <u>APBS</u>	1. Need address posted on house. 2. Need handrail at front porch (4 stair risers) 3. Install dishwasher. 4. Label panel cover. 5. Need energy certificate. 6. Up and down hall detectors/must be CO/smoke. 7. Rear porch posts not installed. 8. Lights at porch not installed. 9. Garage door not installed. 10. Sealed crawlspace incomplete. Crawl door also missing. 11. Complete final grade around house. Minimum 6 inches of fall for 10 feet out. 12. Caulk all exterior light fixtures on top and sides (where installed on brick/exposed to weather) FOUR TRADE FINAL VRU #: 002850576 Please do inspection tomorrow afternoon. Please call if you have any questions. Thanks, Chad. 9196698586

COMMENTS AND NOTES