

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: GATEWEST

LOT 40/41 COMBINED

INITIAL SYSTEM: APPROVED 25% REDUCTION

REPAIR APPROVED 25% REDUCTION

DISTRIBUTION: SERIAL  
~~R BOX~~

DISTRIBUTION SERIAL  
~~R BOX~~

BENCHMARK: 100.0

LOCATION MON FRONT LOT 40

NO. BEDROOMS: 4

LTAR 0.3 GPD/FT<sup>2</sup>

LINE	FLAG COLOR	ELEVATION	LENGTH	
In. final system {	1	R	102.42	130'
	2	B	101.67	130'
	3	Y	101.08	130'
	4A	R	100.53	20'
			<u>410'</u>	
4B	R	100.58	110'	
5	O	100.00	130'	
6	B	99.42	130'	
7	P	99.08	40'	
			<u>410'</u>	

BY M FAIGER

DATE 08/2016

TYPICAL PROFILE

0-14 LI (Vf, wgs)

14-34 + SCL (Fr, shk)

PM @ 34" OR GREATER

INSTALL AT 18"

THERE SHALL BE NO GRADING,  
CUTTING, LOGGING OR OTHER SOIL  
DISTURBANCE IN SEPTIC AREA