

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: CLASSIC Homes of N.C.

PROPERTY LOCATION: SR-1581 Baileys XROADS RD
SUBDIVISION _____ LOT # _____

NEW REPAIR EXPANSION
Type of Structure: SFD

Site Improvements required prior to Construction Authorization Issuance: _____

Proposed Wastewater System Type: 25% Red

Projected Daily Flow: 360 GPD

Number of bedrooms: 3 Number of Occupants: 6 max

Basement Yes No

Pump Required: Yes No May be required based on final location and elevations of facilities

Type of Water Supply: Community Public Well Distance from well _____ feet

Permit valid for: Five years
 No expiration

Authorized State Agent: James E. Markon Date: 8-26-16 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: CLASSIC Homes of N.C.

PROPERTY LOCATION: SR1581 Baileys XROADS RD
SUBDIVISION _____ LOT # _____

Facility Type: SFD New Expansion Repair

Basement? Yes No Basement Fixtures? Yes No

Type of Wastewater System** Pumps to 25% Reductors (Initial) Wastewater Flow: 360 GPD

(See note below, if applicable)
Pumps to 25% Reductors (Repair)

Installation Requirements/Conditions	Number of trenches <u>1</u>	
Septic Tank Size <u>1600</u> gallons	Exact length of each trench <u>300</u> feet	Trench Spacing: <u>9</u> Feet on Center
Pump Tank Size <u>1000</u> gallons	Trenches shall be installed on contour at a	Soil Cover: <u>6</u> inches
	Maximum Trench Depth of: <u>14-12</u> inches	(Maximum soil cover shall not exceed
	(Trench bottoms shall be level to +/-1/4"	36" above the trench bottom)
	in all directions)	

Pump Requirements: _____ ft. TDH vs. _____ GPM
Aggregate Depth: 6 inches below pipe
2 inches above pipe

Conditions: Contractor to meet ONSETTE prior to install 12 inches total

**WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.**

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: James E. Markon Date: 8-26-16
Construction Authorization Expiration Date: 8-26-21

HTE# 16-5-39300R

Permit # 28982

Harnett County Department of Public Health Site Sketch

ISSUED TO: Classic Homes of N.C. PROPERTY LOCATION: 221581 Bailey KIRDS RD SUBDIVISION _____ LOT # _____

Authorized State Agent: James E. Markant Date: 8-26-16

* Contractor to meet ON SITE prior to install of Septic

