

HTE# 165-39830

# Harnett County Department of Public Health

29087

## Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Raynor Builders Inc PROPERTY LOCATION: 511429 Calybeate RD  
 SUBDIVISION: DEXTERFIELD LOT # 27  
 NEW  REPAIR  EXPANSION   
 Type of Structure: SFD  
 Proposed Wastewater System Type: 25% Reducer  
 Projected Daily Flow: 360 GPD  
 Number of bedrooms: 3 Number of Occupants: 6 max  
 Basement  Yes  No  
 Pump Required:  Yes  No  May be required based on final location and elevations of facilities  
 Type of Water Supply:  Community  Public  Well Distance from well \_\_\_\_\_ feet  
 Permit valid for:  Five years  No expiration  
 Permit conditions: \_\_\_\_\_

Authorized State Agent: [Signature] Date: 10-26-16 SEE ATTACHED SITE SKETCH  
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

## Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Raynor Builders INC PROPERTY LOCATION: 511429 Calybeate RD  
 SUBDIVISION: DEXTERFIELD LOT # 27  
 Facility Type: SFD  New  Expansion  Repair  
 Basement?  Yes  No Basement Fixtures?  Yes  No  
 Type of Wastewater System\*\* 25% REDUCED system (Initial) Wastewater Flow: 360 GPD  
 (See note below, if applicable )  
Accepted (Repair)  
 Installation Requirements/Conditions  
 Septic Tank Size 1000 gallons Exact length of each trench 230 feet Trench Spacing: 9 Feet on Center  
 Pump Tank Size \_\_\_\_\_ gallons Trenches shall be installed on contour at a Maximum Trench Depth of: 24-19 inches Soil Cover: 6 inches  
 (Trench bottoms shall be level to +/-1/4" in all directions) (Maximum soil cover shall not exceed 36" above the trench bottom)  
 Pump Requirements: \_\_\_\_\_ ft. TDH vs. \_\_\_\_\_ GPM Aggregate Depth: 6 inches below pipe  
2 inches above pipe  
12 inches total  
 Conditions: \_\_\_\_\_

**WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.  
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.**

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: \_\_\_\_\_ Date: \_\_\_\_\_

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 10-26-16  
 Construction Authorization Expiration Date: 10-26-21

HTE# 16-5-39830

Permit # 29087

# Harnett County Department of Public Health Site Sketch

ISSUED TO: RAYNOR BIDS INC PROPERTY LOCATOR: EX 1429 CLAYBANK RD  
SUBDIVISION: DBXTRALCISID LOT # 27

Authorized State Agent: James E. Markham Date: 10-26-16

\* NO WATER OR POWER LINES IN SYSTEM OF  
Repair AREA.

