

HTE# 17-5-40672

Harnett County Department of Public Health

29504

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: THOMAS & RYE GALLOWAY PROPERTY LOCATION: TIRZAH DRIVE
NEW ☒ REPAIR ☐ EXPANSION ☐ SUBDIVISION: THOMAS LASTER LOT # 5
Type of Structure: SFD (85'x76') Site Improvements required prior to Construction Authorization Issuance:
Proposed Wastewater System Type: PUMP TO 25% REDUCTION SYSTEM
Projected Daily Flow: 360 GPD
Number of bedrooms: 3 Number of Occupants: 6 max
Basement ☐ Yes ☒ No
Pump Required: ☒ Yes ☐ No ☐ May be required based on final location and elevations of facilities
Type of Water Supply: ☐ Community ☒ Public ☐ Well Distance from well 100' feet Permit valid for: ☒ Five years
Permit conditions: ☐ No expiration

Authorized State Agent: [Signature] Date: 4/26/17 SEE ATTACHED SITE SKETCH
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: THOMAS & RYE GALLOWAY PROPERTY LOCATION: TIRZAH DRIVE
SUBDIVISION: THOMAS LASTER LOT # 5
Facility Type: SFD (85'x76') ☒ New ☐ Expansion ☐ Repair
Basement? ☐ Yes ☒ No Basement Fixtures? ☐ Yes ☒ No
Type of Wastewater System: PUMP TO 25% REDUCTION SYSTEM (Initial) Wastewater Flow: 360 GPD
(See note below, if applicable ☐) PUMP TO 25% RED. (Repair) on 1/16/17

Installation Requirements/ConditionsSeptic Tank Size 1000 gallonsPump Tank Size 1000 gallonsNumber of trenches 4Exact length of each trench 60 feetTrenches shall be installed on contour at a 2Maximum Trench Depth of: 18-23 inches

(Trench bottoms shall be level to +/-1/4"

in all directions)

Trench Spacing: 9 Feet on CenterSoil Cover: 6-12 inches

(Maximum soil cover shall not exceed 36" above the trench bottom)

Pump Requirements: _____ ft. TDH vs. _____ GPM

_____ inches below pipe

Aggregate Depth: _____ inches above pipe

Conditions: _____ inches total

WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.

****If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.**

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 4/26/17
Construction Authorization Expiration Date: 4/26/22

HTE# 17-5-40672

Permit # 29504

Harnett County Department of Public Health Site Sketch

ISSUED TO: Galloway, Thomas Rye PROPERTY LOCATION: TIRZAH DRIVE
SUBDIVISION THOMAS LADARER LOT # 5

Authorized State Agent: ~~MISS GINGER TOLKSON~~ Date: 1/16/18

* HOUSE ALREADY BUILT

* SYSTEM FLAGGED

* ALL WATER INCLUDING
FOUNDATION DRAIN
MUST BE DIRECTED
AROUND
DRAINFIELD

