

HTE# 17-540907R

Harnett County Department of Public Health

29525

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: WINTERS, ANDREW & ERICA PROPERTY LOCATION: POPE RD SUBDIVISION _____ LOT # _____

NEW [X] REPAIR [] EXPANSION [] Site Improvements required prior to Construction Authorization Issuance: _____

Type of Structure: 560 (76'x35')

Proposed Wastewater System Type: Pump To 25% REDUCTION SYSTEM

Projected Daily Flow: 360 GPD

Number of bedrooms: 2 Number of Occupants: 6 max

Basement [] Yes [X] No

Pump Required: [X] Yes [] No [] May be required based on final location and elevations of facilities

Type of Water Supply: [] Community [X] Public [] Well Distance from well _____ feet Permit valid for: [X] Five years [] No expiration

Permit conditions: _____

Authorized State Agent: [Signature] RENS Date: 5/23/17 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: WINTERS, ANDREW & ERICA PROPERTY LOCATION: POPE RD SUBDIVISION _____ LOT # _____

Facility Type: 560 (76'x35') [X] New [] Expansion [] Repair

Basement? [] Yes [X] No Basement Fixtures? [] Yes [X] No

Type of Wastewater System** Pump To 25% REDUCTION SYSTEM (Initial) Wastewater Flow: 360 GPD

(See note below, if applicable []) Pump To 25% Red. (Repair)

Installation Requirements/Conditions: Number of trenches 1 Septic Tank Size 1000 gallons Exact length of each trench 300 feet Trench Spacing: 9 Feet on Center Pump Tank Size 1000 gallons Trenches shall be installed on contour at a max! Maximum Trench Depth of: 18.24 inches (Maximum soil cover shall not exceed 36" above the trench bottom) (Trench bottoms shall be level to +/-1/4" in all directions)

Pump Requirements: _____ ft. TDH vs. _____ GPM Aggregate Depth: _____ inches below pipe _____ inches above pipe _____ inches total

WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] RENS Date: 5/23/17 Construction Authorization Expiration Date: 5/23/22

HTE# 17-5-4090712

Permit # 29525

Harnett County Department of Public Health Site Sketch

ISSUED TO: WINTERS ANDREW & ERICA PROPERTY LOCATOR: POPE RD
SUBDIVISION _____ LOT # _____

Authorized State Agent: ~~RENS (OLIVER TOLSON)~~ Date: 5/23/17
RENS 9/20/17

REVISION ADDO BARN

