HTE# 17-5-41529 R

## Harnett County Department of Public Health

Improvement Permit

PROPERTY LOCATION: HEATHERWOOD DO
ISSUED TO: MCKEE HOMES LLC SUBDIVISION DAXMONT LOT # 186
NEW REPAIR FXPANSION Site Improvements required prior to Construction Authorization Issuance:
Type of Structure: SEO (3) > 57)
Proposed Wastewater System Type: Punk To 25% Rob. 375 Projected Daily Flow: 480 GPD
Projected Daily Flow: 460 GPD
Number of bedrooms: Number of Occupants: max
Basement
Pump Required: Yes No May be required based on final location and elevations of facilities
Type of Water Supply:   Community Public Well Distance from well feet Permit valid for: Five years Permit conditions:
Permit conditions: No expiration
Authorized State Agent:: SEE ATTACHED SITE SKETCH
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This
site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit in the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.
the Laws and Rules for sewage freatment and disposal and to conditions of this permit.
Construction Authorization
Construction Authorization
(Required for Building Permit)
The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958. and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.
ISSUED TO: McKEE HOMES LLC PROPERTY LOCATION: HGATHGOMOOD De.
Facility Type: SGO(3)257)  SUBDIVISION Openion Repair  SUBDIVISION Property LOT # 186
Basement?  Yes No Basement Fixtures? Yes No
Type of Wastewater System** Pume To 25% REDUCTION SYSTEM (Initial) Wastewater Flow: 480 GPD
(See note below, if applicable ) Pune To 25% RED, Sys (Repair)
Installation Requirements/Conditions Number of trenches
Septic Tank Size 1000 gallons Exact length of each trench 500 feet Trench Spacing: 9 Feet on Center
Pump Tank Size \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \
Maximum Trench Depth of: inches (Maximum soil cover shall not exceed
(Trench bottoms shall be level to $\pm 1/4$ " 36" above the trench bottom)
in all directions)
Pump Requirements: ft. TDH vs GPM inches below pip
Aggregate Depth: inches above pig
Conditions: inches total
WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.
The Total Control (Section Control Con
**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.
Owner/Legal Representative Signature:
This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.  SEE ATTACHED SITE SKETCH
SEE ATTACHED SHE SACTOR
Authorized State Agent: Date: C 30 17
Construction Authorization Expiration Date: 6/30/22

## Harnett County Department of Public Health Site Sketch

