













SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: OAKMONT  
 INITIAL SYSTEM: APPROVED 25% REDUCTION <sup>pump to</sup>

LOT 186  
 REPAIR APPROVED 25% REDUCTION <sup>pump to</sup>

DISTRIBUTION: D-Box

DISTRIBUTION D-Box

BENCHMARK: 100.0

LOCATION PT ON LINE 186/187

NO. BEDROOMS: 4

LTAR 0.8 GPD/FT<sup>2</sup>

<u>LINE</u>	<u>FLAG COLOR</u>	<u>ELEVATION</u>	<u>LENGTH</u>
1	O	99.75	50'
2	B	99.17	50'
3	O	98.58	50'
			<u>150'</u>
4	B	97.84	50'
5	O	97.25	50'
6	B	96.92	50'
			<u>150'</u>

Facial system

BY M. EAKER

DATE 03/2015

TYPICAL PROFILE  
0-40 s/w (VFr wgs)  
or 2 /m > 48"  
INSTALL AT 18-22"

THERE SHALL BE NO GRADING,  
 CUTTING, LOGGING OR OTHER SOIL  
 DISTURBANCE IN SEPTIC AREA