

HTE# 17-542117

Harnett County Department of Public Health

29221

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

PROPERTY LOCATION: 339 River rd. (sn 1418)

ISSUED TO: Moss Home builders SUBDIVISION _____ LOT # _____

NEW REPAIR EXPANSION

Site Improvements required prior to Construction Authorization Issuance: _____

Type of Structure: 432 76'x69' SFD

Proposed Wastewater System Type: 25% reduction Sys.

Projected Daily Flow: 480 GPD

Number of bedrooms: 4 Number of Occupants: 8 max

Basement Yes No

Pump Required: Yes No May be required based on final location and elevations of facilities

Type of Water Supply: Community Public Well Distance from well 100+ feet

Permit valid for: Five years

Permit conditions: _____ No expiration

Authorized State Agent: [Signature] Date: 09/19/2017

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Moss Home builders

PROPERTY LOCATION: 339 River rd. (sn 1418)

SUBDIVISION _____ LOT # _____

Facility Type: 432 76'x69' SFD New Expansion Repair

Basement? Yes No Basement Fixtures? Yes No

Type of Wastewater System** 25% Reduction Sys. (Initial) Wastewater Flow: 480 GPD

(See note below, if applicable)

25% Reduction Sys. (Repair)

Installation Requirements/Conditions

Septic Tank Size 1250 gallons

Pump Tank Size _____ gallons

Number of trenches 3

Exact length of each trench 120 feet

Trenches shall be installed on contour at a

Maximum Trench Depth of: 26 inches

(Trench bottoms shall be level to +1-1/4"

in all directions)

Trench Spacing: 9 Feet on Center

Soil Cover: 14 inches

(Maximum soil cover shall not exceed

36" above the trench bottom)

Pump Requirements: _____ ft. TDH vs. _____ GPM

Aggregate Depth: _____ inches below pipe

_____ inches above pipe

_____ inches total

Conditions: _____

WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.

NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 09/19/2017

Construction Authorization Expiration Date: 09/19/2022

HTE# 17-5-42117

Permit # 29221

Harnett County Department of Public Health Site Sketch

PROPERTY LOCATION: 339 River Rd. (SR 1418)

ISSUED TO: Moss Homebuilders

SUBDIVISION _____

LOT # _____

Authorized State Agent: _____

Date: 09/19/2017

