

COUNTY OF HARNETT
Building Inspections Department
Planning Services

Certificate of Compliance: _____ **Occupancy:** X

Certificate issued pursuant to the requirements of North Carolina General Statute 153A-363 and Harnett County Zoning Ordinances. This certifies at the time of issuance, this structure was in compliance with the various ordinances of the County of Harnett and the North Carolina State Building Codes. For the following:

Use Classification: Residential

Name: WJH LLC

Address: 385 Cottle Lake Dr
Coats, NC 27521

Permit Numbers

Building: _____

Electrical: _____

Insulation: _____

Plumbing: _____

Mechanical: IT 50042300

MFG Home: _____

Date: 4-12-18

Building Official: [Signature]

ADDRESS : 385 COTTLE LAKE DR SUBDIV: J L STONE
 CONTRACTOR : WJH LLC PHONE : (336) 282-3606
 OWNER : MASTIN BAKER INVESTMENTS LLC PHONE :
 PARCEL : 07-0589- - -0102- -39-
 APPL NUMBER: 17-50042300 CP NEW RESIDENTIAL (SFD)
 DIRECTIONS : T/S: 09/19/2017 09:02 AM JBROCK ----
 COTTLESTONE #35
 210 S TAKE L ONTO S MAIN ST THEN R ONTO
 E FRONT ST
 APPL NOTES : BPMN 12/07/17 T/S: 12/07/2017 01:40 PM BPETRICH --
 PREMISE 88830000

STRUCTURE: 000 000 38X46 4BDR 2.5BA MONO W/ GARAGE

FLOOD ZONE : FLOOD ZONE X
 # BEDROOMS : 4000000.00 PROPOSED USE : SFD
 SEPTIC - EXISTING? : NEW TANK WATER SUPPLY : COUNTY

PERMIT: CPSF 00 CP * SFD

TYP/SQ	REQUESTED COMPLETED	INSP RESULT	DESCRIPTION RESULTS/COMMENTS
A814 01	11/27/17	SB	ADDRESS CONFIRMATION TIME: 17:00 VRU #: 003057502
	11/27/17	AP	385 COTTLE LAKE DR COATS 27521 T/S: 11/27/2017 11:21 AM SBENNETT -----
P309 01	11/28/17	DT	R*PLUMB UNDER SLAB TIME: 17:00 VRU #: 003057510
	11/28/17	AP	T/S: 11/27/2017 09:06 AM JBROCK ----- T/S: 11/28/2017 12:08 PM DETAYLOR -----
B114 01	11/30/17	DT	R*BLDG MONO SLAB/TEMP SVC POLE TIME: 17:00 VRU #: 003059235
	11/30/17	AP	T/S: 11/29/2017 09:51 AM JBROCK ----- T/S: 11/30/2017 12:10 PM DETAYLOR -----
R425 01	1/16/18	DT	FOUR TRADE ROUGH IN TIME: 17:00 VRU #: 003076304
	1/16/18	DA	T/S: 01/12/2018 01:49 PM BPETRICH ----- T/S: 01/16/2018 04:02 PM DETAYLOR -----
B104 01	1/22/18	JB	R*FOUND & SETBACK VERIF SURVEY TIME: 17:00 VRU #: 003078045
	1/22/18	AP	T/S: 01/22/2018 08:34 AM JBROCK -----
R425 02	1/25/18	BS	FOUR TRADE ROUGH IN TIME: 17:00 VRU #: 003080181
	1/25/18	DA	T/S: 01/24/2018 01:14 PM BPETRICH ----- T/S: January 25, 2018 03:05 PM BSUTTON ----- 1. Need engineering on anchoring. There are 23 wedge anchors installed in lieu of embedded anchors. 2. Need structural nail plate above washer box for dryer vent/3 inch drain. 3. Structural plate and firecaulk at dining room top plate for water heater pan drain. 4. Draft stop shower drain above master closet. 5. Truss documents call for 16D nails in hangers at D02L girder. 6. A05L and A08L girders missing nails in uplift into truss. 7. Brace trusses A02. Must use "T" brace as there are only 2 trusses. Ok to side/do not insulate
R425 03	2/01/18	DT	FOUR TRADE ROUGH IN TIME: 17:00 VRU #: 003083722
	2/01/18	DA	T/S: 01/31/2018 11:41 AM LLUCAS ----- T/S: 02/01/2018 11:27 AM DETAYLOR ----- Fire caulk plumbing vent at top plate in master bath Okay to insulate
I129 01	2/06/18	KS	R*INSULATION INSPECTION TIME: 17:00 VRU #: 003085255
	2/06/18	AP	T/S: 02/05/2018 08:52 AM JBROCK ----- T/S: 02/06/2018 12:13 PM KSLATTUM -----

CONTINUED ONTO NEXT PAGE