

HTE# 18-5-43039

Harnett County Department of Public Health

29855

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Robin Cooper Karen Wood
PROPERTY LOCATION: Millwood Ln. (Hwy 210 N.)
SUBDIVISION: Adams Farm S/S LOT # 3B
Type of Structure: 432 60'x62.8' SFD
Proposed Wastewater System Type: 25% Reduction Sys.
Projected Daily Flow: 480 GPD
Number of bedrooms: 4 Number of Occupants: 8 max
Basement: No
Pump Required: May be required based on final location and elevations of facilities
Type of Water Supply: Public
Permit conditions: Permit valid for: Five years

Authorized State Agent: [Signature] Date: 01/25/2018 SEE ATTACHED SITE SKETCH
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Robin Cooper Karen Wood
PROPERTY LOCATION: Millwood Ln. (Hwy 210 N.)
SUBDIVISION: Adams Farm S/S LOT # 3B
Facility Type: 432 60'x62.8' SFD New
Basement? No Basement Fixtures? No
Type of Wastewater System: 25% Reduction System (Initial) Wastewater Flow: 480 GPD
(See note below, if applicable) 25% Reduction Sys. (Repair)
Installation Requirements/Conditions:
Septic Tank Size 1250 gallons Exact length of each trench 70 feet Trench Spacing: 9 Feet on Center
Pump Tank Size gallons Trenches shall be installed on contour at a Soil Cover: 12 inches
Maximum Trench Depth of: 24 inches (Maximum soil cover shall not exceed 36" above the trench bottom)
in all directions)
Pump Requirements: ft. TDH vs. GPM Aggregate Depth: NA inches below pipe NA inches above pipe NA inches total
Conditions: D-Box On Contour Equal Distribution Required
Future Pool shall be 15ft min from final septic location

WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: Date:

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 01/25/2018
ANDREW CURQU Construction Authorization Expiration Date: 01/25/2023

HTE# 18-5-43039

Permit # 29855

Harnett County Department of Public Health Site Sketch

ISSUED TO: Robin Cooper + Karen Wood PROPERTY LOCATOR: Millwood Ln. (Hwy 210 N.)
SUBDIVISION Adams Farm S/D LOT # 3B

Authorized State Agent: Andrew Curran, PHS Date: 01/25/2018
ANDREW CURRAN

- * D-Box On Contour Equal Distribution
- * Future Pool shall be 15ft min from final septic location
- * Millwood Ln. Easement shall be marked at install including cul de sac.

