

Harnett County Department of Public Health

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Lanco Custom Bldg

PROPERTY LOCATION: 15 Southern Place (Clark Road) SA1230
 SUBDIVISION Currin Plantation LOT # 40

NEW REPAIR EXPANSION
 Type of Structure: 3BR 39'x58.5' SFD
 Proposed Wastewater System Type: 25% reduction Sys.
 Projected Daily Flow: 366 GPD
 Number of bedrooms: 3 Number of Occupants: 6 max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well NA feet
 Permit conditions: _____

Site Improvements required prior to Construction Authorization Issuance: _____
 Permit valid for: Five years No expiration

Authorized State Agent: Andrew Warren, EHS Date: 06/14/2019 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Lanco Custom Bldg

PROPERTY LOCATION: 15 Southern Pl (Clark Rd. SA1230)
 SUBDIVISION Currin Plantation LOT # 40

Facility Type: 3BR 39'x58.5' SFD New Expansion Repair
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** 25% Reduction System (Initial) Wastewater Flow: 360 GPD
 (See note below, if applicable
50% Reduction Sys. PPBPS (Repair)

Installation Requirements/Conditions

Septic Tank Size 1000 gallons
 Pump Tank Size _____ gallons
 Number of trenches 1
 Exact length of each trench 225 feet
 Trenches shall be installed on contour at a
 Maximum Trench Depth of: 18-12 inches (Trench bottoms shall be level to +1/4" in all directions)
 Trench Spacing: 9 Feet on Center
 Soil Cover: 6 inches (Maximum soil cover shall not exceed 36" above the trench bottom)
 Pump Requirements: _____ ft. TDH vs. _____ GPM
 Aggregate Depth: NA inches below pipe, NA inches above pipe, NA inches total
 Conditions: Imported soil may be required on shallow end (6" cover min)

**WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
 NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.**

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.
 Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: Andrew Warren, EHS Date: 06/14/2019
ANDREW WARREN Construction Authorization Expiration Date: 06/14/2024

HTE# 18-5-432762

Permit # NA

Harnett County Department of Public Health Site Sketch

SR 1230

ISSUED TO: Lanco Custom Bldg PROPERTY LOCATOR: 15 Southern Pl. (Clark Road)
SUBDIVISION: Curra Plantation LOT # 40

Authorized State Agent: *[Signature]* Date: 06/14/2019
ANDREW CURRIN



- * DEEP (18IN) TO SHALLOW (12IN) REQUIRED
- * IMPORTED SOIL REQUIRED ON SHALLOW END (6IN COVER REQUIRED)
- * INSTAL SYS AS TIGHT AS SETBACKS ALLOW TO MAXIMIZE REPAIR
- * CALL PRIOR TO INSTALL W/ ANY QUESTIONS, COMMENTS, OR CONCERNS
- * CHAMBER SYSTEM LIKELY REQ.