

HTE# R-5-43364

Harnett County Department of Public Health

30012

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Precision Custom Homes PROPERTY LOCATION: Summerville Ga
SUBDIVISION Summerville LOT # 34

NEW REPAIR EXPANSION Type of Structure: SPD (50x50')
Site Improvements required prior to Construction Authorization Issuance:

Proposed Wastewater System Type: 25% Recovery System (Pump)
Projected Daily Flow: 450 GPD

Number of bedrooms: 4 Number of Occupants: 8 max
Basement Yes No

Pump Required: Yes No May be required based on final location and elevations of facilities
Type of Water Supply: Community Public Well Distance from well _____ feet Permit valid for: Five years No expiration

Permit conditions: _____

Authorized State Agent: [Signature] Date: 3/20/18 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Precision Custom Homes PROPERTY LOCATION: Summerville Ga
SUBDIVISION Summerville LOT # 34

Facility Type: SPD (50x50') New Expansion Repair
Basement? Yes No Basement Fixtures? Yes No

Type of Wastewater System** Pump To 25% Recovery System Q4 (Initial) Wastewater Flow: 450 GPD
(See note below, if applicable)

Pump To 25% Rec. Sys. (Repair)

Installation Requirements/Conditions
Septic Tank Size 1000 gallons
Pump Tank Size 1000 gallons
Number of trenches 1
Exact length of each trench 180 feet
Trench Spacing: 9 Feet on Center
Soil Cover: 6 inches
Trenches shall be installed on contour at a Maximum Trench Depth of: 18 inches
(Trench bottoms shall be level to $\pm 1/4$ " in all directions)
(Maximum soil cover shall not exceed 36" above the trench bottom)

Pump Requirements: _____ ft. TDH vs. _____ GPM
Aggregate Depth: _____ inches below pipe
_____ inches above pipe
_____ inches total

Conditions: _____

**WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.**

****If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.**

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 3/20/18
Construction Authorization Expiration Date: 3/20/23


HTE# 18-5-43384

Permit # 30012

Harnett County Department of Public Health Site Sketch

ISSUED TO: Precision Custom Homes PROPERTY LOCATOR: Summellin Dr.
SUBDIVISION: Summellin LOT # 34

Authorized State Agent: [Signature] Date: 3/20/18



SUMMELLIN DRIVE