

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: TINGEN POINT

LOT 152

INITIAL SYSTEM: APPROVED 25% REDUCTION

REPAIR APPROVED 25% REDUCTION

DISTRIBUTION: D-Box

DISTRIBUTION D-Box

BENCHMARK: 100.0

LOCATION PC 152/153

NO. BEDROOMS: 4

LTAR 0.4 GPD/FR²

LINE	FLAG COLOR	ELEVATION	LENGTH
1-4 Initial system	W	108.17	75'
	R	107.75	75'
	Y	107.08	75'
	W	106.08	75'
			<u>300'</u>
5	P	105.08	75'
6	Y	103.92	75'
7	W	102.84	75'
8	P	102.25	75'
			<u>300'</u>

BY M FAIGEN

DATE 03/2015

TYPICAL PROFILE (MOST LIMITING)

0-18 CS (VF, wgr)

18-36 SCL (F, 16M)

cr 2 / PA > 36"

1A STALL AT 13"

THERE SHALL BE NO GRADING,
CUTTING, LOGGING OR OTHER SOIL
DISTURBANCE IN SEPTIC AREA