


| | | | | | |
|-------------------------|---------------------|---------------------------|------------------|-----------------|---|
| JOB T10-10026 | TRUSS T01 | Truss Type FINK | Qty 11 | Ply 1 | CUMMINGS Job Reference (optional) |
|-------------------------|---------------------|---------------------------|------------------|-----------------|---|

Longleaf Truss Company, West End, N.C. Run: 8/31/08 Jun 11 2018 Pmt: 8/31/08 Jun 11 2019 MiTek Industries, Inc. Mon Oct 7 11:38:31 2019 Page 1
 ID: Uj07gEhpjH4qReVMMVM7TeGyVqZV-BN1o1Psgt513aYR7hEED3jBdO8kpyvNP0cOdyVqY_



| | | | | | |
|----------------------|----------------------|-------------|-----------------------------|----------------|-------------|
| LOADING (psf) | SPACING- | CSI. | DEFL. | PLATES | GRIP |
| TCLL 20.0 | 2-0-0 | TC 0.38 | in (loc) l/defl L/d | MT20 | 244/190 |
| TCDL 10.0 | Plate Grip DOL 1.15 | BC 0.54 | Vert(LL) -0.11 6-8 >999 240 | | |
| BCLL 0.0 | Lumber DOL 1.15 | WB 0.24 | Vert(CT) -0.26 6-8 >999 180 | | |
| BCDL 10.0 | Rep Stress Incr YES | Matrix-S | Horz(CT) 0.05 6 n/a n/a | | |
| | Code IRC2018/TPI2014 | | | Weight: 105 lb | FT = 20% |

LUMBER-
 TOP CHORD 2x4 SP No.1
 BOT CHORD 2x4 SP No.1
 WEBS 2x4 SP No.3

BRACING-
 TOP CHORD Sheathed or 4-1-4 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (size) 2=0-3-8 (min. 0-1-10), 6=0-3-8 (min. 0-1-10)
 Max Horz 2=-82(LC 10)
 Max Uplift 2=-28(LC 12), 6=-28(LC 12)
 Max Grav 2=1017(LC 2), 6=1017(LC 2)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD 2-3=-1894/33, 3-4=-1661/37, 4-5=-1661/37, 5-6=-1994/33
 BOT CHORD 2-10=0/1682, 8-10=0/1119, 6-8=0/1682
 WEBS 3-10=-374/96, 4-10=0/587, 4-8=0/587, 5-8=-374/96

JOINT STRESS INDEX
 2 = -nan(ind), 3 = -nan(ind), 4 = -nan(ind), 5 = -nan(ind), 6 = -nan(ind), 8 = -nan(ind), 9 = -nan(ind) and 10 = -nan(ind)


- NOTES-**
- 1) Unbalanced roof live loads have been considered for this design.
 - 2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=12ft; B=45ft; L=24ft; eave=4ft; Cal. II; Exp B; Enclosed; MWFRS (directional); cantilever left and right exposed; and vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - 3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL); Lum DOL=1.15 Plate DOL=1.15; Pg=10.0 psf; Pf=7.7 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10
 - 4) Unbalanced snow loads have been considered for this design.
 - 5) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 7.7 psf on overhangs non-concurrent with other live loads.
 - 6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - 7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - 8) All bearings are assumed to be User Defined crushing capacity of 425 psi.
 - 9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 28 lb uplift at joint 2 and 28 lb uplift at joint 6.
 - 10) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

| | | | | | |
|------------------|---------------|---------------------|----------|----------|--------------------------------------|
| Job T10-10026 | Truss T01G | Truss Type GABLE | Qty 2 | Ply 1 | CUMMINGS Job Reference (optional) |
|------------------|---------------|---------------------|----------|----------|--------------------------------------|

Longleaf Truss Company, West End, N C

Run: 83.310 6 1 Jun 11 2010 Print: 8.310 6 Jun 11 2010 MiTek Industries, Inc. Mon Oct 7 11:36:32 2019 Page 1
ID:Ujg7gEhpjH4qReWMVM?TeGyVqZV-cabAFIlePQwCl0BFxlSowAYx1rVTJCw73z0w3yVqXc



| LOADING (psf) | | SPACING- | CSI. | DEFL. | in (loc) | l/defl | L/d | PLATES | GRIP |
|---------------|-------|----------------------|----------|----------|----------|--------|-----|----------------|----------|
| TCLL | 20.0 | Plate Grip DOL | TC | Vert(LL) | 0.00 | 13 | n/r | MT20 | 244/190 |
| TCDL | 10.0 | Lumber DOL | BC | Vert(CT) | 0.01 | 13 | n/r | | |
| BCLL | 0.0 * | Rep Stress Incr | WB | Horz(CT) | 0.00 | 12 | n/a | | |
| BCDL | 10.0 | Code IRC2018/TPI2014 | Matrix-S | | | | | | |
| | | | | | | | | Weight: 117 lb | FT = 20% |

LUMBER-
 TOP CHORD 2x4 SP No.1
 BOT CHORD 2x4 SP No.1
 OTHERS 2x4 SP No.3

BRACING-
 TOP CHORD Sheathed or 6-0-0 oc purlins.
 BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. All bearings 24-0-0.
 (lb) - Max Horz 2=-82(LC 10)
 Max Uplift All uplift 100 lb or less at joint(s) 2, 12, 19, 20, 21, 22, 17, 16, 15, 14
 Max Grav All reactions 250 lb or less at joint(s) 2, 12, 18, 19, 20, 21, 17, 16, 15 except
 22=310(LC 30), 14=310(LC 31)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.

JOINT STRESS INDEX
 2 = -nan(ind), 3 = -nan(ind), 4 = -nan(ind), 5 = -nan(ind), 6 = -nan(ind), 7 = -nan(ind), 8 = -nan(ind), 9 = -nan(ind), 10 = -nan(ind), 11 = -nan(ind), 12 = -nan(ind), 14 = -nan(ind), 15 = -nan(ind), 16 = -nan(ind), 17 = -nan(ind), 18 = -nan(ind), 19 = -nan(ind), 20 = -nan(ind), 21 = -nan(ind) and 22 = -nan(ind)

- NOTES-**
- Unbalanced roof live loads have been considered for this design.
 - Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TC DL=6.0psf; BCDL=6.0psf; h=12ft; B=45ft; L=24ft; eave=2ft; Cat. II; Exp B; Enclosed; MWFRS (directional); cantilever left and right exposed; end vertical left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
 - Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
 - TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pg=10.0 psf; Pf=7.7 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Partially Exp.; Ce=1.0; Cs=1.00; Ct=1.10
 - Unbalanced snow loads have been considered for this design.
 - This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 7.7 psf on overhangs non-concurrent with other live loads.
 - All plates are 1.5x4 MT20 unless otherwise indicated.
 - Gable requires continuous bottom chord bearing.
 - Gable studs spaced at 2-0-0 oc.
 - This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
 - * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
 - All bearings are assumed to be User Defined crushing capacity of 425 psi.
 - Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 100 lb uplift at joint(s) 2, 12, 19, 20, 21, 22, 17, 16, 15, 14.

| | | | | | |
|------------------|---------------|---------------------|----------|----------|--------------------------------------|
| Job T10-10026 | Truss T01G | Truss Type GABLE | Qty 2 | Ply 1 | Comments Job Reference (optional) |
|------------------|---------------|---------------------|----------|----------|--------------------------------------|

Longleaf Truss Company, West End, N.C

Run: B3 310 a 1 Jun 11 2019 Print: B 310 a Jun 11 2019 MITek industries, Inc. Mon Oct 7 11:30:33 2019 Page 2
ID:Ujg7gEhpjH4qReWVMVM7T6GyVqZV-4m8YSSuwQIYnpabNpfHhB8jgRBICmS4MjijSWyVqXy

NOTES-

14) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard