

HTE# 07-5-17033R

Harnell County Department of Public Health

24058

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

PROPERTY LOCATION: Hwy 401

ISSUED TO: JARRELL COMPANY, LLC

SUBDIVISION _____ LOT # _____

NEW REPAIR EXPANSION

Site Improvements required prior to Construction Authorization Issuance: _____

Type of Structure: 15000 SF SHOWROOM & WAREHOUSE

Proposed Wastewater System Type: PUMP TO CONVENTIONAL

Projected Daily Flow: 150 GPD

Number of bedrooms: 0 Number of Occupants: 6 EMPLOYEES max

Basement Yes No

Pump Required: Yes No May be required based on final location and elevations of facilities

Type of Water Supply: Community Public Well Distance from well 100 feet

Permit valid for: Five years No expiration

Permit conditions: _____

Authorized State Agent: [Signature] RS

Date: 6/5/07

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: JARRELL COMPANY LLC

PROPERTY LOCATION: Hwy 401

SUBDIVISION _____ LOT # _____

Facility Type: 15000 SF SHOWROOM & WAREHOUSE New Expansion Repair

Basement? Yes No Basement Fixtures? Yes No

Type of Wastewater System** PUMP TO CONVENTIONAL (Initial)

Wastewater Flow: 150 GPD

(See note below, if applicable)

PUMP TO CONVENTIONAL (Repair)

Installation Requirements/Conditions

2 TRENCHES

Septic Tank Size 1000 gallons

Exact length of each trench 50 feet

Trench Spacing: 9 Feet on Center

Pump Tank Size 1000 gallons

Trenches shall be installed on contour at a

Soil Cover: 24 inches

Maximum Trench Depth of: 36 inches

(Maximum soil cover shall not exceed

(Trench bottoms shall be level to +/- 1/4"

36" above the trench bottom)

in all directions)

Pump Requirements: _____ ft. TDH vs. _____ GPM

Aggregate Depth: 6 inches below pipe

2 inches above pipe

Conditions: _____

12 inches total

**If applicable: *I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.*

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] RS

Date: 6/5/07

Construction Authorization Expiration Date: 6/5/12

HTE# 07-5-17033R

Permit # 24058

Harnett County Department of Public Health Site Sketch

PROPERTY LOCATOR: Hwy 401

ISSUED TO: JARRELL COMPANY SUBDIVISION _____ LOT # _____

Authorized State Agent: [Signature] Date: 6/5/07

