

HTE# 07-5-18359

# Harrison County Department of Public Health

24522

## Improvement Permit

A building permit cannot be issued with only an Improvement Permit

PROPERTY LOCATION: McLEAN CHAPEL CHURCH RD SR2020

ISSUED TO: KENNETH S. MURCHISON

SUBDIVISION \_\_\_\_\_ LOT # \_\_\_\_\_

NEW  REPAIR  EXPANSION

Site Improvements required prior to Construction Authorization Issuance: \_\_\_\_\_

Type of Structure: 30'x40' OFFICE BUILDING (2 EMPLOYEES)

Proposed Wastewater System Type: CONVENTIONAL

Projected Daily Flow: 100 GPD

Number of bedrooms: \_\_\_\_\_ Number of Occupants: 4 max


Basement  Yes  No

Pump Required:  Yes  No  May be required based on final location and elevations of facilities

Type of Water Supply:  Community  Public  Well Distance from well 100 feet

Permit valid for:  Five years  
 No expiration

Permit conditions: \_\_\_\_\_

Authorized State Agent:  RS

Date: 2/7/08

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

## Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: KENNETH S. MURCHISON

PROPERTY LOCATION: McLEAN CHAPEL CHURCH RD SR2020

SUBDIVISION \_\_\_\_\_ LOT # \_\_\_\_\_

Facility Type: 30'x40' OFFICE BUILDING  New  Expansion  Repair

Basement?  Yes  No Basement Fixtures?  Yes  No

Type of Wastewater System\*\* CONVENTIONAL (Initial) Wastewater Flow: 100 GPD

(See note below, if applicable )

CONVENTIONAL (Repair)

### Installation Requirements/Conditions

2 TRENCHES

Septic Tank Size 1000 gallons

Exact length of each trench 50 feet

Trench Spacing: 9 Feet on Center

Pump Tank Size \_\_\_\_\_ gallons

Trenches shall be installed on contour at a

Soil Cover: 24 inches

Maximum Trench Depth of: 36 inches

(Maximum soil cover shall not exceed

(Trench bottoms shall be level to  $\pm 1/4"$  in all directions)

36" above the trench bottom)

Pump Requirements: \_\_\_\_\_ ft. TDH vs. \_\_\_\_\_ GPM

6 inches below pipe

Aggregate Depth: 2 inches above pipe

Conditions: \_\_\_\_\_

12 inches total

\*\*If applicable: *I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.*

Owner/Legal Representative Signature: \_\_\_\_\_ Date: \_\_\_\_\_

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent:  RS

Date: 2/7/08

Construction Authorization Expiration Date: 2/7/13

HTE# 07-5-18359

Permit # 24522

# Harnett County Department of Public Health Site Sketch

ISSUED TO: KENNETH S. MURKISON PROPERTY LOCATOR: McLEAN CHAPEL CHURCH RD  
SUBDIVISION \_\_\_\_\_ LOT # \_\_\_\_\_

Authorized State Agent: ~~\_\_\_\_\_~~ RS (OLIVER TOLKSPORF) Date: 2/7/09

