

13

Fire Marshal/Emergency Management

Mailing: P. O. Box 370 Lillington, NC 27546
Physical: 200 North 13th Street, Suite 19
Erwin, NC 28339

910-893-7580
910-893-5025

APPLICATION FOR PLAN REVIEW

APPLICATION NUMBER: 10-50022319

TODAY'S DATE: 5.3.10 RECEIVED BY: ALICIA SOK

SUBMITTED BY: ADKINS & DENNIS

NAME OF PROJECT: ALMIGHT HOME SELF STORAGE

PHYSICAL ADDRESS: 6050 LCIW BRIGGS VACINA

PHONE NUMBER: 919-567-0483 EXT.: _____

CONTACT PERSON: _____

MAILING ADDRESS: _____

PHONE NUMBER: _____

CONTRACTOR'S NAME: _____

MAILING ADDRESS: _____

PHONE NUMBER: _____

NOTICE

PLANS THAT ARE SUBMITTED WILL BE REVIEWED AS QUICKLY AS POSSIBLE, WITH AN AVERAGE TIME OF REVIEW BETWEEN 7 - 10 WORKING DAYS.

(4) sets of plans
customer did not complete approval.
ALICIA SOK



Plan Review, Inspection and Permit Fees

Application Number 09-50022319

\$150.00	<input type="checkbox"/>	Explosive Mat. (90 Days)
\$ 75.00	<input type="checkbox"/>	Explosive Mat. (72 Hrs)
\$ 25.00	<input type="checkbox"/>	Fireworks Public Display
\$ 35.00	<input checked="" type="checkbox"/>	Final Inspection
\$ 35.00 + 2.00 per device	<input type="checkbox"/>	Fire Alarm Testing
\$ 35.00 + 2.00 per nozzle	<input type="checkbox"/>	Fixed Fire Suppression
\$ 25.00	<input type="checkbox"/>	Insecticide Fog/Fumigation
\$ 50.00	<input type="checkbox"/>	Pipe Test/UST/AGST
\$ 50.00	<input type="checkbox"/>	Plans up to 5000 ft ²
\$100.00	<input type="checkbox"/>	Plans 5001 ft ² to 10,000 ft ²
\$150.00	<input type="checkbox"/>	Plans 10,001 ft ² to 25,000 ft ²
\$250.00	<input checked="" type="checkbox"/>	Plans 25,001 ft ² and over
\$ 35.00 + 2.00 per Head	<input type="checkbox"/>	Sprinkler Certification Test
\$ 35.00	<input type="checkbox"/>	Standpipe Testing
\$ 25.00	<input type="checkbox"/>	Special Assembly
\$ 25.00	<input type="checkbox"/>	Temporary Kiosks/Displays
\$ 25.00	<input type="checkbox"/>	Tents, Canopies, Air Supported
\$ 50.00	<input type="checkbox"/>	Tank Installation (charge for each tank)
\$ 50.00	<input type="checkbox"/>	Tank Removal (charge for each tank)

\$ 285.00 Total

Total device/heads

Teddy Joe Mclamb
Code Enforcement Official

05/17/10
Date



Harnett
COUNTY
NORTH CAROLINA



Emergency Services Department

www.harnett.org

200 N. 13th Street
Suite 19
Erwin, NC 28339

Mailing Address:
PO Box 370
Lillington, NC 27546

ph: 910-893-7580
fax: 910-893-5025

May 17, 2010

Adkins & Denton, LLC
6050 US 401 N
Fuquay-Varina, NC 27526

Almost Home Self Storage
6050 US 401 N
Fuquay-Varina, NC 28526

Application Number 09-50022319

Mr. Denton,

Thank you for submitting the plans for Almost Home Self Storage. The plans have been carefully reviewed by a qualified code enforcement official to examine for full compliance with the North Carolina Fire Prevention Code and all other fire protection regulatory documents. There are some items that were found during the plan review process that need to be addressed before a final inspection of the new facility can be given. These items are outlined and described below.

- **906.1 Fire Extinguishers**
 - Fire extinguishers shall be placed in approved locations as drawn by the code enforcement official on the approved plans.
 - The fire extinguishers provided shall have a minimum rating of 2A 10B:C and shall not be installed higher than 5 feet above the finished floor
 - Fire extinguishers locations may be changed but with coordination with our office

- **503.1.1 Fire Department Access**
 - The fire department access shall extend to within 150 feet of all portions of the facility.
 - The fire department access road shall be of an unobstructed width of not less than 20 feet and shall have an unobstructed vertical clearance of not less than 13 feet 6 inches.

- **505.1 Physical Address**
 - The physical address of the building shall be posted in a conspicuous place so that it can be seen on approach from the road, access road, and/or parking lot.
 - The numbers used to make up the physical address shall be at least 5 inches in height.

- **506.1 Knox Box**
 - Knox Box or Knox switch shall be installed on the building or the fence surrounding the building
 - Order Form is provided
 - If key pad with gate is used for entrance, a Knox key switch may suit better for this application

- **508.5.1 Where required.**
 - Where a portion of the facility or building hereafter constructed or moved into or within the jurisdiction is more than 400 feet (122 m) from a hydrant on a fire apparatus access road, as measured by an approved route around the exterior of the facility or building, on-site fire hydrants and mains shall be provided where required by the fire code official.
 - As we discussed on the site plan review

Thank you again for submitting the plans for the Almost Home Self Storage. Please review the plans and adhere to any notes and alterations that were made in addition to the original drawings. If you have any questions, please do not hesitate to call this office.

Again, thank you and we look forward to working with you during the construction period!

Sincerely,



T.J. McLamb, CFI
Chief Deputy Fire Marshal