

3

<b>Fire Marshal/Emergency Management</b>	
Mailing: P. O. Box 370 Lillington, NC 27546 Physical: 200 North 13th Street, Suite 19 Erwin, NC 28339	910-893-7580 910-893-5025

**APPLICATION FOR PLAN REVIEW .**

APPLICATION NUMBER: 10 50024840

TODAY'S DATE: 10-21-10 RECEIVED BY: JWB

SUBMITTED BY: James W. Walker Jr.

NAME OF PROJECT: Jimmy Walker Automotive

PHYSICAL ADDRESS: 1129 Sheriff Johnson Rd Lillington, NC 27546

PHONE NUMBER: 910-893-5296 EXT.:           

CONTACT PERSON: James W. Walker Jr.

MAILING ADDRESS: 384 Mitchell Rd Lillington NC 27546

PHONE NUMBER: 910-893-5296

CONTRACTOR'S NAME: Sanford Metal Building LLC

MAILING ADDRESS: P.O. Box 5231 Sanford NC 27331

PHONE NUMBER: 919-776-2623

**NOTICE**

**PLANS THAT ARE SUBMITTED WILL BE REVIEWED AS QUICKLY AS POSSIBLE, WITH AN AVERAGE TIME OF REVIEW BETWEEN 7 - 10 WORKING DAYS.**

*2 sets of Plans*



## Plan Review, Inspection and Permit Fees

Application Number <sup>2</sup> 10-50004840

SCANNED  
10-29-10  
DATE

\$150.00	<input type="checkbox"/>	Explosive Mat. (90 Days)
\$ 75.00	<input type="checkbox"/>	Explosive Mat. (72 Hrs)
\$ 25.00	<input type="checkbox"/>	Fireworks Public Display
\$ 35.00	<input checked="" type="checkbox"/>	Final Inspection
\$ 35.00 +2.00 per device	<input type="checkbox"/>	Fire Alarm Testing
\$ 35.00 + 2.00 per nozzle	<input type="checkbox"/>	Fixed Fire Suppression
\$ 25.00	<input type="checkbox"/>	Insecticide Fog/Fumigation
\$ 50.00	<input type="checkbox"/>	Pipe Test/UST/AGST
\$ 50.00	<input type="checkbox"/>	Plans up to 5000 ft <sup>2</sup>
\$100.00	<input checked="" type="checkbox"/>	Plans 5001 ft <sup>2</sup> to 10,000 ft <sup>2</sup>
\$150.00	<input type="checkbox"/>	Plans 10,001 ft <sup>2</sup> to 25,000 ft <sup>2</sup>
\$250.00	<input type="checkbox"/>	Plans 25,001 ft <sup>2</sup> and over
\$ 35.00 + 2.00 per Head	<input type="checkbox"/>	Sprinkler Certification Test
\$ 35.00	<input type="checkbox"/>	Standpipe Testing
\$ 25.00	<input type="checkbox"/>	Special Assembly
\$ 25.00	<input type="checkbox"/>	Temporary Kiosks/Displays
\$ 25.00	<input type="checkbox"/>	Tents, Canopies, Air Supported
\$ 50.00	<input type="checkbox"/>	Tank Installation (charge for each tank)
\$ 50.00	<input type="checkbox"/>	Tank Removal (charge for each tank)

\$ 135.00 Total

Total device/heads

Teddy Joe McLamb  
Code Enforcement Official

10/27/10  
Date



## Fire Marshal Division

September 7, 2010

Jimmy Walker  
384 Mitchell Rd  
Lillington, NC 27546

Jimmy Walker Automotive  
1129 Sheriff Johnson Rd  
Lillington, NC 27546

Application Number 10-50024840

Mr. Walker,

Thank you for submitting the plans for the shop. The plans have been carefully reviewed by a qualified code enforcement official to examine for full compliance with the North Carolina Fire Prevention Code and all other fire protection regulatory documents. There are some items that were found during the plan review process that need to be addressed before a final inspection of the new facility can be given. These items are outlined and described below.

- **906.1 Fire Extinguishers**
  - Fire extinguishers shall be placed in approved locations as drawn by the code enforcement official on the approved plans.
  - The fire extinguishers provided shall have a minimum rating of 2A 40B:C and shall not be installed higher than 5 feet above the finished floor in the shop area and 2A-10 B:C shall be posted in the office area
  
- **503.1.1 Fire Department Access**
  - The fire department access shall extend to within 150 feet of all portions of the facility.



- The fire department access road shall be of an unobstructed width of not less than 20 feet and shall have an unobstructed vertical clearance of not less than 13 feet 6 inches.
- **505.1 Physical Address**
  - The physical address of the building shall be posted in a conspicuous place so that it can be seen on approach from the road, access road, and/or parking lot.
  - The numbers used to make up the physical address shall be at least 5 inches in height.
- **506.1 Knox Box**
  - A secure key box shall be installed on the new building that houses all keys to all the doors within the building in which the fire department would need access to in the event of an emergency
  - Authorization form will be delivered to the site or can pick up from office
- **1006.1 Illumination required.**
  - The means of egress, **including the exit discharge**, shall be illuminated at all times the building space served by the means of egress is occupied.
  - Exit discharge to be illuminated to the public way
- **2211.2.2 Waste oil, motor oil and other Class IIIB liquids.**
  - Waste oil, motor oil and other Class IIIB liquids shall be stored in approved tanks or containers, which are allowed to be stored and dispensed from inside repair garages
- **2211.2.3.1 Disposal of liquids.**
  - Crankcase drainings and liquids shall not be dumped into sewers, streams or on the ground, but shall be stored in approved tanks or containers in accordance with Chapter 34 until removed from the premises
- **2211.2.3.2 Disposal of oily waste.**
  - Self-closing metal cans shall be used for oily waste
- **2211.3 Sources of ignition.**
  - Sources of ignition shall not be located within 18 inches (457 mm) of the floor and shall comply with Chapters 3 and 26
- **2211.3.2 Smoking.**



- Smoking shall not be allowed in repair garages except in approved locations
  
- **2211.2.1 Cleaning of parts.**
  - Cleaning of parts shall be conducted in listed and approved parts-cleaning machines in accordance with Chapter 34

Thank you again for submitting the plans for the new shop. Please review the plans and adhere to any notes and alterations that were made in addition to the original drawings. These remarks are for the plans that were submitted and its original intent. These remarks do not apply if the original intent changes or what was submitted on the above date changes. If you have any questions, please do not hesitate to call this office.

Again, thank you and we look forward to working with you during the construction period!

Sincerely,

*Teddy Joe McLamb*

T. J McLamb, CFI  
Chief Deputy Fire Marshal

3

REVISED PLANS SUBMITTED  
10/28/10 (RD)

SCANNED  
~~10-21-10~~  
DATE  
10/28/10

**Fire Marshal/Emergency Management**  
Mailing: P. O. Box 370 Lillington, NC 27546  
Physical: 200 North 13th Street, Suite 19  
Erwin, NC 28339  
910-893-7580  
910-893-5025

**APPLICATION FOR PLAN REVIEW .**

APPLICATION NUMBER: 10 50024840R  
TODAY'S DATE: 10-21-10<sup>28</sup> RECEIVED BY: JWB (RD 10/28/10)  
SUBMITTED BY: James W. Walker Jr.  
NAME OF PROJECT: Jimmy Walker Automotive  
PHYSICAL ADDRESS: 1129 Sheriff Johnson Rd Lillington, NC 27546  
PHONE NUMBER: 910-893-5296 EXT.: \_\_\_\_\_  
CONTACT PERSON: James W. Walker Jr.  
MAILING ADDRESS: 384 Mitchell Rd Lillington NC 27546  
PHONE NUMBER: 910-893-5296  
CONTRACTOR'S NAME: Sanford Metal Building LLC  
MAILING ADDRESS: P.O. Box 5231 Sanford NC 27331  
PHONE NUMBER: 919-776-2623

**NOTICE**

**PLANS THAT ARE SUBMITTED WILL BE REVIEWED AS QUICKLY AS POSSIBLE, WITH AN AVERAGE TIME OF REVIEW BETWEEN 7 - 10 WORKING DAYS.**

2 sets of Plans