



## Plan Review, Inspection, and Permit Fees

Application Number

: 15-50037445 & 15-50037446

*Added  
fees to  
37445  
only*

\$75.00	<input type="checkbox"/>	DRB Major Sub Division Prelim Site Plans	\$	-
\$150.00	<input type="checkbox"/>	Explosive Material (90 Days)	\$	-
\$75.00	<input type="checkbox"/>	Explosive Materials (72 Hours)	\$	-
\$50.00	<input type="checkbox"/>	Fireworks Public Display	\$	-
\$50.00	<input checked="" type="checkbox"/>	Final Inspection	\$	50.00
\$35.00 + \$2.00 per device	<input type="checkbox"/>	Fire Alarm Testing	\$	-
\$35.00 + \$2.00 per nozzle	<input type="checkbox"/>	Fixed Fire Suppression	\$	-
\$25.00	<input type="checkbox"/>	Insecticide Fog/Fumigation	\$	-
\$50.00	<input type="checkbox"/>	Pipe Test/UST/AGST	\$	-
\$50.00	<input type="checkbox"/>	Plans up to 5000 sq ft	\$	-
\$100.00	<input type="checkbox"/>	Plans 5001 sq ft to 10,000 sq ft	\$	-
\$150.00	<input checked="" type="checkbox"/>	Plans 10,001 sq ft to 25,000 sq ft	\$	150.00
\$250.00	<input type="checkbox"/>	Plans 25,001 sq ft and over	\$	-
\$35.00 + 2.00 per head	<input type="checkbox"/>	Sprinkler Certification Test	\$	-
\$35.00	<input type="checkbox"/>	Standpipe Testing	\$	-
\$25.00	<input type="checkbox"/>	Special Assembly	\$	-
\$25.00	<input type="checkbox"/>	Temporary Kiosks/Displays	\$	-
\$25.00	<input type="checkbox"/>	Tents/Canopies/Air Supported	\$	-
\$50.00	<input type="checkbox"/>	Tank Installation (charge for each tank)	\$	-
\$50.00	<input type="checkbox"/>	Tank Removal (charge for each tank)	\$	-
		Total Devices/Heads	\$	-
		<b>Total Cost</b>	\$	<b>200.00</b>

Code Enforcement Official

Bill Lamm

11/16/2015



November 16, 2015

C. David Holleman  
204 Scholl Street  
Fuquay Varina, NC 27526

**Re: Almost Home Self Storage Ph2  
6050 US 401 North  
Fuquay Varina, NC 27526**

**Application Number 15-50037445 Climate Control  
15-50037446 Non Climate Control**

Mr. Holleman,

Thank you for submitting the plans for the storage facility. The plans have been carefully reviewed by a qualified code enforcement official to examine for full compliance with the North Carolina Fire Prevention Code and all other fire protection regulatory documents. There are some items that were found during the plan review process that need to be addressed before a final inspection of the new facility can be given. These items are outlined and described below.

- **906.1 Fire Extinguishers**
  - Fire extinguishers shall be placed in approved locations as drawn by the code enforcement official on the approved plans.
  - The fire extinguishers provided shall have a minimum rating of 2A 10B:C and shall not be installed higher than 5 feet above the finished floor or ground.
  - Fire extinguishers shall be installed in such a manner that no distance to an extinguisher is greater than 75', this distance can be measured from existing extinguishers on existing buildings.
  - Fire Extinguishers being placed on exterior of the building shall be placed in weather proof closures.
  - One 2A 10BC extinguisher shall be placed in the interior corridor of the climate controlled building.



- **1011.1 Exit / Emergency lights**
  - Exit lights shall be installed at both entrance doors of Climate Controlled building
  - Remote Exit lights shall be installed in corridor of Climate Control building with arrows indicating direction to Exit
  - One emergency light needs to be install in the center of the corridor of the Climate Control building
  
- **505.1 Physical Address ( If Phase 2 Buildings have a different address )**
  - The physical address of the building shall be posted in a conspicuous place so that it can be seen on approach from the road, access road, and/or parking lot.
  - The numbers used to make up the physical address shall be at least 5 inches in height.
  - The address shall be posted on the interior of the building indicating the suite location in a conspicuous manner.
  
- **Notes**
  - **If HVAC duct detectors are installed, and acceptance test will be required**
  - Please schedule all fire inspections through the Fire marshal's Office.
  - Contact Number **910-893-0741**.

Thank you again for submitting the plans for the storage facility. Please review the plans and adhere to any notes and alterations that were made in addition to the original drawings. These remarks are for the plans that were submitted and its original intent. These remarks do not apply if the original intent changes or what was submitted on the above date changes. If you have any questions, please do not hesitate to call this office.

Again, thank you and we look forward to working with you during the construction period!

Thank You,



Bill Lamm

Chief Deputy Fire Marshal

HARNETT COUNTY EMERGENCY SERVICES  
 REVIEWED FOR CODE COMPLIANCE

FABRINO STRONG  
 NTS

*[Signature]*  
 CODE COMPLIANCE OFFICER DATE

12-2-15

