



FM plans are in
middle of set.

Application for Plan Review

Detailed
Plans

45

Application # 17-50041710

Date Received: 9.22.17 Received By: djanism

Name of Project: Carolina Diesel Trucks

Physical Address of Project: 4206 Progress Dr

Anguay Varina NC 27526

Plans Submitted By: Jimmons Group

Project Phone: (919) 866-4507

Contact Person/Address: _____

Contact Email: _____

Contact Phone: (____) - ____ - ____ (____) - ____ - ____

Contractor's Name/Info: _____

Contractor's Phone: (____) - ____ - ____

- Plans that are submitted will be reviewed as quickly as possible with an average time of review between 7-10 working days.
- Status checks may be conducted on plan reviews by visiting the website <http://hteweb.harnett.org/Click2GovBP/Index.jsp> or by calling the Harnett County Central Permitting Office (910-893-7525, Option #2), or the Harnett County Fire Marshal's Office (910-893-7580).
- Approved plans must be picked up from the Central Permitting Office and all fees paid before any required inspections can be conducted.



Plan Review, Inspection, and Permit Fees


Application Number : 17-50041710

\$200.00	<input type="checkbox"/>	Explosive Material (90 Days)	\$	-
\$100.00	<input type="checkbox"/>	Explosive Materials (72 Hours)	\$	-
\$100.00	<input type="checkbox"/>	Fireworks Public Display	\$	-
\$50.00	<input checked="" type="checkbox"/>	Final Inspection	\$	50.00
\$35.00 + \$2.00 per device	<input type="checkbox"/>	Fire Alarm Testing	\$	-
\$35.00 + \$2.00 per nozzle	<input type="checkbox"/>	Fixed Fire Suppression	\$	-
\$75.00	<input type="checkbox"/>	Insecticide Fog/Fumigation	\$	-
\$100.00	<input type="checkbox"/>	Pipe Test/UST/AGST	\$	-
\$50.00	<input type="checkbox"/>	Plans up to 5000 sq ft	\$	-
\$100.00	<input checked="" type="checkbox"/>	Plans 5001 sq ft to 10,000 sq ft	\$	100.00
\$150.00	<input type="checkbox"/>	Plans 10,001 sq ft to 25,000 sq ft	\$	-
\$250.00	<input type="checkbox"/>	Plans 25,001 sq ft and over	\$	-
\$35.00 + 2.00 per head	<input type="checkbox"/>	Sprinkler Certification Test	\$	-
\$50.00	<input type="checkbox"/>	Standpipe Testing	\$	-
\$50.00	<input type="checkbox"/>	Special Assembly (ie. amusement buildings, carnivals, fairs)	\$	-
\$75.00	<input type="checkbox"/>	Tents/Canopies/Air Supported Structure	\$	-
\$100.00	<input type="checkbox"/>	Tank Installation (charge for each tank)	\$	-
\$100.00	<input type="checkbox"/>	Tank Removal (charge for each tank)	\$	-
		Total Devices/Heads	\$	-
		Total Cost	\$	150.00

Code Enforcement Official

Rodney Daniels

9/29/2017



September 29, 2017

Timmons Group

Re: Carolina Diesel Trucks
6296 Progress Drive
Fuquay Varina, NC 27526

Application Number 17-50041710


To whom it may concern,

Thank you for submitting the plans for Carolina Diesel Trucks. The plans have been carefully reviewed by a qualified code enforcement official to examine for full compliance with the North Carolina Fire Prevention Code and all other fire protection regulatory documents. There are some items that were found during the plan review process that need to be addressed before a final inspection of the new facility can be given. These items are outlined and described below.

- **505.1 Physical Address**
 - The physical address of the building shall be posted in a conspicuous place so that it can be seen on approach from the road, access road, and/or parking lot.
 - The numbers used to make up the physical address shall be at least 6 inches in height.

- **506.1 Knox Box**
 - A secure key box shall be installed on the new building that houses all keys to all the doors within the building in which the fire department would need access to in the event of an emergency.
 - Knox Box ID stickers shall be placed on all exterior doors in which entry to the building may be gained.
 - The box shall be mounted not to exceed 48 – 60 inches in height.
 - The basic model for the buildings should be at least a selection from the 3200 Series listed on the order form.
 - <https://www.knoxbox.com/store/departmentSearch.cfm>

- **Fire Extinguishers**
 - Fire Extinguishers shall be 2A:20BC and shall be placed with a travel distance to not exceed 75'



- Fire extinguishers are to be mounted no higher than 5' above the finished floor.

- **1006.1 Illumination Required**
 - The exit discharge shall be illuminated at all times the building spaces served by the means of egress is occupied
 - Illumination level in all areas of the means of egress shall not be less than 1 foot-candle at the walking surface and shall have emergency power supply.

- **903.2.9.1 Repair Garages**
 - A sprinkler system will be required if this building is used for the repair of commercial trucks or buses.

Thank you again for submitting the plans for Carolina Diesel Trucks. Please review the plans and adhere to any notes and alterations that were made in addition to the original drawings. These remarks are for the plans that were submitted and its original intent. These remarks do not apply if the original intent changes or what was submitted on the above date changes. If you have any questions, please do not hesitate to call this office

Again, thank you and we look forward to working with you during the construction period!

Sincerely,

Rodney Daniels
Chief Deputy Fire Marshal