

A17B0157A  
CAROLINA DIESEL TRUCKS



AMERICAN BUILDINGS

A NUCOR COMPANY

**BUILDING ERECTION NOTES**

1. THE METAL BUILDING SUPPLIER ASSUMES NO RESPONSIBILITY OR LIABILITY FOR FOUNDATION, FLOOR OR SLAB DESIGN OR CONSTRUCTION.
2. THE FOUNDATION DESIGN SHOULD BE DONE WITH DUE REGARD TO THE SPECIFIC SOIL CONDITIONS PRESENT AT THE ACTUAL JOBSITE.
3. FOUNDATION MUST BE DESIGNED FOR THE APPLICABLE REACTIONS AS THEY APPLY TO A PARTICULAR BUILDING AND MUST BE ADEQUATE TO RESIST ALL OF THE CRITICAL COMBINATIONS FOR EACH OF THE VARIOUS LOADING CONDITIONS. THESE REACTIONS AND LOAD COMBINATIONS MUST BE USED TO DETERMINE THE DESIGN LOADS TO BE RESISTED BY THE FOUNDATIONS.
4. REINFORCING BARS, WIRE MESH, ANCHOR ROD SHEAR ANGLES, TIE RODS AND / OR HAIRPINS (HOOK BARS) SHOULD BE INCORPORATED AS REQUIRED INTO THE FOUNDATION DESIGN. THE HORIZONTAL THRUST AT THE COLUMN BASE ACTING IN CONJUNCTION WITH APPLICABLE VERTICAL REACTIONS, MUST BE SUSTAINED BY HAIRPINS, TIE RODS, BUTTRESSES, OR OTHER DEPENDABLE MEANS.
5. COLUMN FOOTING SHOULD EXTEND A MINIMUM OF 12 INCHES INTO NATURAL SOIL, OR WHERE FILL IS USED, THE FILL MUST BE PROPERLY COMPACTED OR THE FOOTING SHALL EXTEND TO THE NATURAL GRADE. IN ALL CASES THE FOOTING SHALL EXTEND AT LEAST 6 INCHES BELOW THE LOCAL FROST LINE.
6. EXPANSION OR CONSTRUCTION JOINTS SHALL BE LOCATED AS REQUIRED IN FOUNDATION WALLS AND SLAB, AS SPECIFIED BY THE FOUNDATION DESIGNER.
7. THE TOP OF THE FOUNDATION OR FLOOR SHALL BE SQUARE, LEVEL AND SMOOTH. ANCHOR RODS SHALL BE ACCURATELY SET TO A TOLERANCE +/- 1/16 INCH ON DIMENSIONS WITHIN THE GROUP SPACING FOR AN INDIVIDUAL COLUMN. ALL OTHER DIMENSIONS SHALL HAVE A +/- 1/8 INCH TOLERANCE.
8. COLUMN BASE PLATES ARE DESIGNED NOT TO EXCEED THE ALLOWABLE BEARING STRESS OF CONCRETE THAT HAS A MINIMUM COMPRESSIVE STRENGTH OF 2500 P.S.I. AT 28 DAYS.
9. UNLESS EXPLICITLY NOTED OTHERWISE, ALL EMBEDDED STRUCTURAL STEEL (INCLUDING ANCHOR RODS), OTHER MATERIALS, AND LABOR SHALL BE SUPPLIED BY THE FOUNDATION CONTRACTOR.
10. ANCHOR RODS SHOULD BE AS SHOWN AND CALLED FOR, INCLUDING PROJECTION FROM CONCRETE, DIAMETER AND QUANTITY.
11. THE EMBEDMENT OF THE ANCHOR RODS IN THE CONCRETE AND CONFIRMING ADEQUACY OF ANCHOR ROD EDGE DISTANCE IS THE RESPONSIBILITY OF THE FOUNDATION DESIGNER. THE FRAME REACTIONS ARE CONSIDERED THE MINIMUM LOADS TO BE DEVELOPED.
12. ALL ANCHOR RODS SHALL BE ASTM F1554 GRADE 36 OR EQUAL IN ORDER TO CONFORM TO THE METAL BUILDING SUPPLIER'S DESIGN ASSUMPTIONS BASED ON THE ALLOWABLE STRESSES GIVEN IN THE AISC MANUAL OF STEEL CONSTRUCTION.
13. ANCHOR ROD DIAMETERS FOR THE PRIMARY FRAMING AND ENDWALL FRAMING ARE DENOTED AT RESPECTIVE BASE PLATE DETAILS OR ON THE ANCHOR BOLT PLAN. ANCHOR RODS FOR FRAMED OPENINGS SHALL BE 1/2 INCH DIAMETER UNLESS OTHERWISE NOTED.

**BASIC MATERIAL SPECIFICATIONS**

PRIMARY FRAMING STEEL

STEEL FOR MILL-ROLLED STRUCTURAL SECTIONS SHALL CONFORM TO THE REQUIREMENTS OF ASTM A 36, ASTM A 572 GRADE 50 OR 55, OR ASTM A 992.

STEEL FOR ALL BUILT-UP SECTIONS SHALL CONFORM TO ONE OR MORE OF THE FOLLOWING:

- A. ASTM A 1011 SS, GRADE 55
- B. ASTM A 1011 HSLAS, GRADE 55, CLASS 1
- C. ASTM A 572 GRADE 55
- D. ASTM A 529 GRADE 55

STEEL FOR ENDWALL "C" SECTIONS SHALL CONFORM TO ASTM A 1011 SS, GRADE 55, OR HSLAS, GRADE 55, CLASS 1.

STEEL FOR ROUND PIPE SECTIONS SHALL CONFORM TO ASTM A 500 GRADE B, 42 KSI.

SECONDARY FRAMING STEEL

STEEL USED TO FORM PURLINS, GIRTS, EAVE STRUTS AND "C" SECTIONS SHALL CONFORM TO ASTM A1011 SS, GRADE 55, OR HSLAS GRADE 55, CLASS 1, OR IF

GALVANIZED SHALL CONFORM TO ASTM A653 SS, GRADE 55, G90 OR HSLAS, GRADE 55, CLASS 1, G90.

ROOF AND WALL PANEL MATERIAL

EXTERIOR PANELS SHALL CONFORM TO ONE OF THE FOLLOWING:

PANEL MATERIAL SHALL BE ALUMINUM-ZINC ALLOY-COATED STEEL CONFORMING TO THE REQUIREMENTS OF ASTM A 792 SS, GRADE 80. MATERIAL MAY BE EITHER 26 OR 24 GAGE.

PANEL MATERIAL SHALL BE ALUMINUM-ZINC ALLOY-COATED STEEL CONFORMING TO THE REQUIREMENTS OF ASTM A 792 SS, GRADE 50, CLASS 1.

PANEL MATERIAL SHALL BE ZINC-COATED (GALVANIZED) STEEL, COATING DESIGNATION G90, CONFORMING TO THE REQUIREMENTS OF ASTM A 653 SS, GRADE 80, CLASS 1 OR CLASS 2, OR HSLAS, GRADE 80. MATERIAL MAY BE EITHER 26 OR 24 GAGE.

PANEL MATERIAL SHALL BE ZINC-COATED (GALVANIZED) STEEL, COATING DESIGNATION G90, CONFORMING TO THE REQUIREMENTS OF ASTM A 653 SS, GRADE 50, CLASS 1 OR CLASS 3, MATERIAL MAY BE EITHER 24 OR 22 GAGE.

BRACE MATERIALS:

BRACE CABLES: ASTM A 475, 7-STRAND EHS WIRE CABLE	BC4 = 1/4" DIA.(7mm)	BC5 = 5/16" DIA.(8mm)	BC6 = 3/8" DIA.(10mm)	BC8 = 1/2" DIA.(13mm)
BRACE RODS: ASTM A 572, 50 KSI (UPSET THREADS)	BR5 = 5/8" DIA.(16mm)	BR6 = 3/4" DIA.(20mm)	BR7 = 7/8" DIA.(23mm)	BR8 = 1" DIA.(26mm)
OR ASTM A 529, 50 KSI (CUT THREADS)	BR9 = 1 1/8" DIA.(29mm)	BR10 = 1 1/4" DIA.(32mm)	BR11 = 1 3/8" DIA.(35mm)	BR12 = 1 1/2" DIA.(39mm)

STRUCTURAL PRIMER NOTE:

"SHOP COAT PRIMER IS INTENDED TO PROTECT THE STEEL FRAMING DURING TRANSPORTATION TO THE JOBSITE.

STORAGE IN EXTREME COLD TEMPERATURES OR WINTER SNOW CONDITIONS, INCLUDING TRANSPORTATION ON SALTED OR CHEMICALLY TREATED ROADS WILL ADVERSELY AFFECT THE DURABILITY AND LONGEVITY OF THE PRIMER. THE COAT OF SHOP PRIMER DOES NOT PROVIDE THE UNIFORMITY OF APPEARANCE, OR THE DURABILITY AND CORROSION RESISTANCE OF A FIELD APPLIED FINISH COAT OF PAINT OVER A SHOP PRIMER. MINOR ABRASIONS TO THE SHOP COAT PRIMER CAUSED BY HANDLING, LOADING, SHIPPING, UNLOADING AND ERECTION ARE UNAVOIDABLE AND ARE NOT THE RESPONSIBILITY OF THE METAL BUILDING SUPPLIER. ABC IS NOT RESPONSIBLE FOR THE DETERIORATION OF THE PRIMER OR CORROSION THAT MAY RESULT FROM NEITHER ATMOSPHERIC AND ENVIRONMENTAL CONDITIONS NOR THE COMPATIBILITY OF THE PRIMER TO ANY FIELD APPLIED COATING."

"AS A MINIMUM AND SECONDARY TO MORE STRENUOUS JOB SPECIFIC REQUIREMENTS, PROJECTS LOCATED IN CANADA MUST BE ERECTED WITHIN TOLERANCES AS DEFINED IN SECTION 29.7 OF SPECIFICATION S16.01 AND PROJECTS IN OTHER LOCATIONS MUST BE ERECTED WITHIN TOLERANCES AS DEFINED IN THE LATEST EDITION OF THE METAL BUILDING SYSTEMS MANUAL, PUBLISHED BY THE MBMA."

CONSTRUCTION BRACING NOTE:

TEMPORARY SUPPORTS, SUCH AS TEMPORARY GUYS, BRACES, FALSEWORK, CRIBBING OR OTHER ELEMENTS REQUIRED FOR THE ERECTION OPERATION IS TO BE DETERMINED, FURNISHED AND INSTALLED BY THE ERECTOR. THESE SUPPORTS MUST SECURE THE STEEL FRAMING, OR ANY PARTLY ASSEMBLED STEEL FRAMING, AGAINST LOADS COMPARABLE IN INTENSITY TO THOSE FOR WHICH THE STRUCTURE WAS DESIGNED RESULTING FROM WIND AND OR SEISMIC ACTIVITY AND AGAINST THE LOADS RESULTING FROM THE ERECTION OPERATION.

ERECTOR NOTE

FIELD WORK (TRIMMING, DRILLING, WELDING, ETC.) MAY BE REQ'D FOR CERTAIN CONDITIONS. ABC WILL NOT BE LIABLE FOR ADDITIONAL ERECTION COSTS DUE TO THIS WORK. CONDITIONS EFFECTED MAY INCLUDE (BUT ARE NOT LIMITED TO): ALL SHEETING PANELS LESS THAN 3'0 IN LENGTH WILL HAVE TO BE FIELD CUT FROM PANELS PROVIDED AS NOTED ON ERECTION DWGS, SOME PORTAL FRAME KNEE BRACES REQUIRE FIELD WELDING OR DRILLING FOR CONNECTION AT RAFTER, FLUSH GIRT/PURLIN CONDITIONS MAY NEED TO BE SLOTTED TO ACCOMMODATE X-BRACING, "KICKER" BRACES AT OPEN ENDWALLS MAY REQUIRE FIELD DRILLED HOLES AT CONNECTION TO PURLINS, ANGLE X-BRACING MAY REQUIRE FIELD WELDING AT THE COLUMN BASE, ALL JOBS WITH JOISTS WILL LIKELY REQUIRE SOME FIELD WELDING (REGARDLESS OF BOLTED CONNECTIONS)

CANOPY BY OTHERS  
VERTICAL SUPPORT FOR CANOPY BY OTHERS AT COLUMNS FRAME LINE 1, H-K, 1-2  
PROVIDE EXTRA CEE SECTIONS PER CUSTOMER REQUEST. SEE E-09 AND E-23 FOR SIZES  
LOCATIONS.  
MEZZANNINE DECKING BY OTHERS.

NOTE FOR CUSTOMER: DECK AT EACH SIDEWALL MUST BE CAPABLE OF TRANSFERRING 6.4 KIPS UNFACTORED SEISMIC LONGITUDINAL FORCE INTO JOISTS.  
BUILDER ADVISE TO HAVE DECK WITHSTAND 2'-8" SPANS

**ABC - ATLANTIC DIVISION**  
6115 COCA COLA BLVD.  
COLUMBUS, GA 31909  
PHONE: (706) 562-8020  
FAX: (706)562-8017

**ABC - MIDWEST DIVISION**  
2101 EAST MAIN STREET  
EL PASO, IL 61738  
PHONE: (309) 527-1500  
FAX: (309) 527-1522

**ABC - SOUTH DIVISION**  
1150 STATE DOCKS RD.  
EUFAULA, AL 36027  
PHONE: (334) 687-2032  
FAX: (334) 688-2200

**ABC - WEST DIVISION**  
2260 TENAYA DRIVE  
MODESTO, CA 95354  
PHONE: (209) 236-0580  
FAX: (209) 236-0588

THIS IS TO CERTIFY THAT THE METAL BUILDING COMPONENTS FURNISHED BY AMERICAN BUILDINGS COMPANY FOR THE REFERENCED BUILDING HAVE BEEN DESIGNED IN OUR COLUMBUS, GA OFFICE FOR FABRICATION IN OUR LA CROSSE, VA PLANT.

IN ADDITION TO THE DEAD LOAD (D) OF THE BUILDING COMPONENTS, THE MEMBERS ARE DESIGNED ON THE FOLLOWING DESIGN BASIS:

COLLATERAL LOAD (C)  
3 psf On Roof Members  
3 psf On Supporting Frames

ROOF LIVE LOAD (Lr)  
20 psf on Roof Members With Reduction On Supporting Frames As Permitted By Code

SNOW LOAD (S)  
10.5 psf Roof Snow Load  
Roof Exposure Condition = Partially Exposed  
Thermal Condition = All structures that do not otherwise qualify as either "Structures kept just above freezing and others" or "Unheated structures and structures intentionally kept below freezing  
15 psf Ground Snow Load  
Thermal Factor = 1.0  
Snow Exposure Factor = 1.0  
Snow Importance Factor = 1.0

WIND LOAD (W)  
Exposure (Surface Roughness) Category = B  
95 mph Basic Wind Speed (3-second gust)  
Enclosure Classification = Enclosed Buildings  
Internal Pressure Coefficients = +0.18 and -0.18  
Wind Importance Factor = 1.0  
Design Pressure for Wall Components and Cladding = +14.86 psf and -19.81 psf

SEISMIC LOAD (E)  
Equivalent Lateral Force Procedure  
22.9 %g Seismic Mapped Short Period Acceleration  
8.6 %g Seismic Mapped 1 Sec Period Acceleration  
Site Classification = D  
Seismic Importance Factor = 1.0  
Seismic Design Category = C  
Seismic Design Short Period Acceleration, Sds = 0.244g  
Seismic Design 1 Sec Period Acceleration, Sd1 = 0.138g  
Transverse Direction OCBF (X-Bracing)  
Base Shear, V = pCsW p=1.00 Cs=Sds/ (R/I)=0.0814 R=3<3.25  
Transverse Direction OMF (Rigid Frames)  
Base Shear, V = pCsW p=1.00 Cs=Sds/ (R/I)=0.0814 R=3<3.5  
Longitudinal Direction OCBF (X-Bracing)  
Base Shear, V = pCsW p=1.00 Cs=Sds/ (R/I)=0.0814 R=3<3.25

Classification of Building = II. All buildings and other structures except those listed in Categories I, III, and IV

NOTES:

1. ROOF DESIGN IS BASED ON THE LARGER OF LIVE LOAD OR ROOF SNOW LOAD.
2. ALL WELDING MUST BE PERFORMED BY AWS QUALIFIED WELDERS FOR THE WELDING PROCESSES AND POSITIONS TO BE USED. ALL WELDING AND WELD PREP MUST BE COMPLETED AND VISUALLY INSPECTED TO AWS ACCEPTANCE CRITERIA (TABLE 6.1) IN ACCORDANCE WITH THE APPLICABLE AWS STANDARD. WELD ELECTRODES USED FOR ALL FIELD WELD PROCESSES MUST BE SELECTED FROM TABLE 3.1 IN AWS D1.1 FOR GROUP II MATERIAL GREATER THAN OR EQUAL 0.125" THICK OR TABLE 1.2 IN AWS D1.3 FOR MATERIAL LESS THAN 0.125" THICK AND ALL FILLER MATERIAL MUST HAVE A Fu OF 70 KSI.

AMERICAN BUILDINGS COMPANY SERVICEABILITY STANDARDS (2006 MBMA MANUAL CRITERIA) WILL BE USED FOR DESIGN AND FABRICATION OF YOUR ORDER.

THE ABOVE DESIGN LOADS ARE APPLIED IN ACCORDANCE WITH THE 2012 NORTH CAROLINA STATE BUILDING CODE. THE DESIGN IS IN GENERAL ACCORDANCE WITH 2005 AISC 360-05 SPECIFICATION FOR STRUCTURAL STEEL BUILDINGS AND 2007 AISI NASPEC NORTH AMERICAN COLD-FORMED STEEL SPECIFICATION.

THIS CERTIFICATION IS LIMITED TO THE STRUCTURAL DESIGN OF THE FRAMING AND COVERING PARTS MANUFACTURED BY AMERICAN BUILDINGS COMPANY. ACCESSORY ITEMS SUCH AS DOORS, WINDOWS, LOUVERS, TRANSLUCENT PANELS AND VENTILATORS ARE NOT INCLUDED. ALSO EXCLUDED. ARE OTHER PARTS OF THE PROJECT NOT PROVIDED BY AMERICAN BUILDINGS COMPANY SUCH AS FOUNDATIONS, MASONRY WALLS, MECHANICAL EQUIPMENT AND THE ERECTION AND INSPECTION OF THE BUILDING. THE BUILDING SHALL BE ERECTED ON A PROPERLY DESIGNED FOUNDATION IN ACCORDANCE WITH AMERICAN BUILDINGS COMPANY'S "GENERAL ERECTION GUIDE" AND THE JOB ERECTION DRAWINGS. THE DRAWINGS LISTED ON THIS SHEET SHALL REMAIN WITH AND BECOME PART OF THIS CERTIFICATION.

MEZZANNINE DESIGN LOADS:

ASSUMED DEAD LOAD : 20 PSF  
LIVE LOAD : 135 PSF (10 PSF PARTITION LOADS)  
COLLATERAL LOAD: 3 PSF

USER REQUESTED DEFLECTION CRITERIA  
RIGID FRAME - H/100 (HORIZONTAL)


SHEET NUMBER	STATUS	DATE	REV. NO.
C-1 ~ C-2	FOR APPROVAL ONLY	08/03/17	2
AB-1 ~ AB-3	FOR APPROVAL ONLY	08/03/17	2
E-01 ~ E-15	FOR APPROVAL ONLY	08/03/17	2
SED-000 ~ SED-020	FOR APPROVAL ONLY	08/03/17	2

THE REGISTERED PROFESSIONAL ENGINEER WHOSE SEAL APPEARS ON THESE DRAWINGS IS EMPLOYED BY THE MANUFACTURER AND DOES NOT SERVE AS OR REPRESENT THE PROJECT ENGINEER OF RECORD AND SHALL NOT BE CONSIDERED AS SUCH.

THIS PROJECT IS DESIGNED AS AN ENCLOSED BUILDING. ACCESSORIES (DOORS, WINDOWS, ETC.) BY OTHERS MUST BE DESIGNED AS "COMPONENTS AND CLADDING" IN ACCORDANCE WITH THE SPECIFIC WIND PROVISIONS OF THE REFERENCED BUILDING CODE.

THE METAL BUILDING MANUFACTURER DOES NOT CONSIDER VIBRATION ANALYSIS OF MEZZANINE SYSTEMS UNLESS EXPLICITLY REQUESTED AND SPECIFIED IN THE METAL BUILDING MANUFACTURER QUOTE AND ORDER DOCUMENTS. ANY NEED FOR VIBRATION ANALYSIS SHOULD BE CONSIDERED AND SPECIFIED BY THE ENGINEER OF RECORD FOR THE PROJECT.

**\*\*NOT FOR CONSTRUCTION\*\***

CAROLINA DIESEL TRUCKS 62 PROGRESS DRIVE FUQUAY VARINA, NC 27526 THOMAS ANDREWS	 AMERICAN BUILDINGS <small>A HUCOR COMPANY</small>  	DRAWING STATUS: <b>FOR APPROVAL ONLY</b>	
		SOFTWARE VERSIONS	DESIGN: MSA 47.3 BIM: v20.6
		JOB NUMBER: <b>A17B0157A</b>	SHEET: <b>C-1</b>

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					

ROOF PANELS

TYPE: S3 GAGE: 24 COLOR: ALCT  
 PAINT WARRANTY: NO  
 WEATHERTIGHTNESS WARRANTY: NO  
 UL 90 CERTIFICATION: NO  
 FACTORY MUTUAL CERTIFICATION: NO

WALL PANELS

TYPE: A3P GAGE: 26 COLOR: FXGYSMF BASE: ANGLE W/  
 PAINT WARRANTY: YES

EAVE TREATMENT

STANDARD GUTTER WITH DOWNSPOUTS 46.33 FT O.C. (MAX)

TRIM COLORS

RAKE TRIM: POWHSMP GUTTER OR EAVE: POWHSMP  
 DOWNSPOUTS: POWHSMP FRAMED OPENINGS: POWHSMP  
 CORNER: FXGYSMF BASE TRIM: BRSLMFP  
 MISCELLANEOUS:

PRIMER COLORS

PRIMARY: RED SECONDARY: RED

ROOF FASTENERS

STANDING SEAM III  
 STRUCTURAL:  
 #14X1 SDRF  
 STITCH:  
 #14X1 SDRF

WALL FASTENERS

ARCHITECTUAL III  
 STRUCTURAL:  
 #12X1 1/4 SDHH  
 STITCH:  
 #14X3/4 SDHH

TRIM FASTENERS

#14X3/4 SDHH

INSULATION

ROOF: BY OTHERS  
 THICK: 4.0 WIDTH: NA FACE: NA COLOR: NA  
 WALLS: BY OTHERS  
 THICK: 4.0 WIDTH: NA FACE: NA COLOR: NA  
 THERMAL BLOCKS INCLUDED BY METAL BUILDING SUPPLIER (1" THICK ONLY)

WALK DOORS

QTY	SIZE	TYPE	SWING	LOCKSET	CLOSER	COLOR	LINER TRIM	LINER TRIM COLOR
1	6070	S	RHO	SRP	NO	WHITE	NO	
2	3070	S	RHO	SRP	NO	WHITE	NO	

FRAMED OPENINGS

QTY	WIDTH	HEIGHT	SILL HEIGHT	FR WRAP TRIM	LINER TRIM	LINER TRIM COLOR
4	16'	8'		YES	NO	
1	20'	18'		YES	NO	
1	12'	9'		YES	NO	

RECENT PRODUCT REVISIONS

THE FOLLOWING NOTES MAY OR MAY NOT PERTAIN TO THIS SPECIFIC JOB BUT ARE NOTEWORTHY PRODUCT CHANGES.  
 1. THINK SAFETY!


**\*\*NOT FOR CONSTRUCTION\*\***

CAROLINA DIESEL TRUCKS  
 62 PROGRESS DRIVE  
 FUQUAY VARINA, NC 27526  
 THOMAS ANDREWS



DRAWING STATUS:  
**FOR APPROVAL ONLY**  
 SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6  
 JOB NUMBER: **A17B0157A** SHEET: **C-2**

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					



ANCHOR BOLT TABLE	
SIZE	QTY
3/4	108

- ERECTION NOTE!!!
1. FINISHED FLOOR ELEVATION = 100'-0"
  2. BOTTOM OF BASE PLATE (B.O.B.P.) = 100'-0" EXCEPT AS NOTED.



















ANCHOR BOLT PLAN

CAROLINA DIESEL TRUCKS  
 62 PROGRESS DRIVE  
 FUQUAY VARINA, NC 27526  
 THOMAS ANDREWS



DRAWING STATUS:  
**FOR APPROVAL ONLY**  
 SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6  
 JOB NUMBER: **A17B0157A**  
 SHEET: **AB-1**

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					



**ERECTION NOTE!!!**  
1. FINISHED FLOOR ELEVATION = 100'-0"  
2. BOTTOM OF BASE PLATE (B.O.B.P.) = 100'-0" EXCEPT AS NOTED.

**ERECTION NOTE!!!**  
ALL ANCHOR RODS SHALL HAVE A 3 INCH PROJECTION (UNLESS NOTED) ABOVE THE BOTTOM OF THE COLUMN BASE PLATES, EXCEPT 1/2 INCH DIAMETER ANCHOR RODS LOCATED AT DOORS WHICH SHALL HAVE PROJECTION OF 1 INCH.  
  
ALL ANCHOR RODS SHALL HAVE A MINIMUM THREAD LENGTH OF 1/4 INCH LESS THAN THE PROJECTION. THE PROJECTIONS SPECIFIED PROVIDE FOR A SINGLE BASE PLATE THICKNESS, AND APPLICATION OF ONE 3/16 INCH WASHER, AND ONE HEAVY HEX NUT. IN THE INSTALLED POSITION, THE TOP OF THE ANCHOR BOLT MUST BE FLUSH WITH OR ABOVE THE TOP OF THE NUT.  
  
ADDITIONAL PROJECTION LENGTH MUST BE CONSIDERED AND PROVIDED FOR ITEMS SUCH AS GROUT, DOUBLE NUTS, PLATE WASHERS, LEVELING PLATES, ETC., THAT MAY BE SPECIFIED BY OTHERS.  
  
PROJECTING THREADS SHOULD BE GREASED OR OTHERWISE PROTECTED FROM CORROSION.


NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					

CAROLINA DIESEL TRUCKS  
62 PROGRESS DRIVE  
FUQUAY VARINA, NC 27526  
THOMAS ANDREWS



DRAWING STATUS:  
**FOR APPROVAL ONLY**  
SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6  
JOB NUMBER: A17B0157A SHEET: AB-2a

BP09-A  
 3/8 PLATE - 3/4 AB - 3" REQD. PROJECTION



ERECTION NOTE!!!  
 1. FINISHED FLOOR ELEVATION = 100'-0"  
 2. BOTTOM OF BASE PLATE (B.O.B.P.) = 100'-0" EXCEPT AS NOTED.

ERECTION NOTE!!!  
 ALL ANCHOR RODS SHALL HAVE A 3 INCH PROJECTION (UNLESS NOTED) ABOVE THE BOTTOM OF THE COLUMN BASE PLATES, EXCEPT 1/2 INCH DIAMETER ANCHOR RODS LOCATED AT DOORS WHICH SHALL HAVE PROJECTION OF 1 INCH.  
 ALL ANCHOR RODS SHALL HAVE A MINIMUM THREAD LENGTH OF 1/4 INCH LESS THAN THE PROJECTION. THE PROJECTIONS SPECIFIED PROVIDE FOR A SINGLE BASE PLATE THICKNESS, AND APPLICATION OF ONE 3/16 INCH WASHER, AND ONE HEAVY HEX NUT. IN THE INSTALLED POSITION, THE TOP OF THE ANCHOR BOLT MUST BE FLUSH WITH OR ABOVE THE TOP OF THE NUT.

ADDITIONAL PROJECTION LENGTH MUST BE CONSIDERED AND PROVIDED FOR ITEMS SUCH AS GROUT, DOUBLE NUTS, PLATE WASHERS, LEVELING PLATES, ETC., THAT MAY BE SPECIFIED BY OTHERS.

CAROLINA DIESEL TRUCKS  
 62 PROGRESS DRIVE  
 FUQUAY VARINA, NC 27526  
 THOMAS ANDREWS




DRAWING STATUS:  
**FOR APPROVAL ONLY**  
 SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6  
 JOB NUMBER: **A17B0157A** SHEET: **AB-2b**

PROJECTING RELEASE REVISION	BY	DATE	DESCRIPTION	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	HRH /	JV	08/03/2017	1	RCC / RCC	JV	06/14/2017
0	RCC / RCC	JV	06/12/2017				

# REACTION SCHEMATICS

LOADING CONDITION	FRAME LINE 1			
	K		A	
	V (kips)	H1 (kips)	V (kips)	H1 (kips)
D	+5.4	+2.4	+5.2	-2.4
C	+2.2	+1.6	+2.2	-1.6
L	+9.4	+6.4	+7.9	-6.4
MEZZ LL	+8.4	+0.2	+8.4	-0.2
S	+11.1	+5.5	+7.1	-5.5
W	-12.6	-8.7	-11.4	+8.8
E*	-1.6 to +1.6	-6.9 to +6.9	-1.6 to +1.6	-6.9 to +6.9

\*Earthquake reactions do not include any amplifications for overstrength which may or may not be required in the design of column anchorage and foundation by others.  
 H1 = horizontal force in the plane of frame  
 H2 = horizontal force perpendicular to the plane of frame




LOADING CONDITION	FRAME LINE 2								
	K			A			G,I	E	C
	V (kips)	H1 (kips)	H2 (kips)	V (kips)	H1 (kips)	H2 (kips)	V (kips)	V (kips)	V (kips)
D	+12.5	+3.8	NA	+6.1	-3.8	NA	+6.6	+6.9	+4.0
C	+4.4	+2.8	NA	+3.6	-2.8	NA	+0.8	+0.8	+0.4
L	+17.0	+11.1	NA	+14.4	-11.1	NA	NA	NA	NA
MEZZ LL	+33.6	+0.5	NA	+3.3	-0.5	NA	+33.8	+35.1	+18.2
S	+20.3	+9.4	NA	+12.9	-9.4	NA	NA	NA	NA
W	-16.5 to +0.5	-10.5 to +1.8	NA	-14.4 to +0.9	-1.9 to +10.7	NA	NA	NA	NA
W (at X braced bays)	NA	NA	NA	-20.0 to +0.9	-1.9 to +10.7	NA	NA	NA	NA
E*	-1.8 to +1.8	-7.4 to +7.4	NA	-1.8 to +1.8	-7.3 to +7.3	NA	NA	NA	NA
E* (at X braced bays)	NA	NA	NA	-5.8 to +5.8	-7.3 to +7.3	NA	NA	NA	NA

\*Earthquake reactions do not include any amplifications for overstrength which may or may not be required in the design of column anchorage and foundation by others.  
 H1 = horizontal force in the plane of frame  
 H2 = horizontal force perpendicular to the plane of frame

LOADING CONDITION	FRAME LINES 3-4					
	K			A		
	V (kips)	H1 (kips)	H2 (kips)	V (kips)	H1 (kips)	H2 (kips)
D	+5.8	+3.8	NA	+5.8	-3.8	NA
C	+3.7	+3.0	NA	+3.8	-3.0	NA
L	+15.0	+12.0	NA	+15.0	-12.0	NA
S	+13.5	+10.5	NA	+13.5	-10.5	NA
W	-15.0 to +0.9	-11.4 to +1.8	NA	-15.0 to +0.9	-1.8 to +11.4	NA
W (at X braced bays)	-20.5 to +0.9	-11.4 to +1.8	NA	-20.5 to +0.9	-1.8 to +11.4	NA
E*	-0.4 to +0.4	-0.9 to +0.9	NA	-0.4 to +0.4	-0.9 to +0.9	NA
E* (at X braced bays)	-5.8 to +5.8	-0.9 to +0.9	-10.0 to +10.0	-5.8 to +5.8	-0.9 to +0.9	-10.0 to +10.0

\*Earthquake reactions do not include any amplifications for overstrength which may or may not be required in the design of column anchorage and foundation by others.  
 H1 = horizontal force in the plane of frame  
 H2 = horizontal force perpendicular to the plane of frame




LOADING CONDITION	CURTAIN WALL AT FRAME LINE 1									
	J		H		F		D		B	
	V (kips)	H2 (kips)	V (kips)	H2 (kips)	V (kips)	H2 (kips)	V (kips)	H2 (kips)	V (kips)	H2 (kips)
D	+5.4	NA	+7.2	NA	+6.9	NA	+6.9	NA	+5.2	NA
W	-0.8 to +1.3	-2.2 to +2.0	-1.0 to +1.7	-3.2 to +2.9	+0.3	-3.2 to +2.9	+0.3	-3.0 to +2.7	+0.3	-2.1 to +1.9
L	+1.8	+0.2	+2.3	+0.3	+0.3	NA	+0.3	NA	+0.3	NA
S	+4.6	+0.5	+6.1	+0.6	+0.3	NA	+0.3	NA	+0.3	NA
C	+0.8	NA	+1.1	NA	+0.8	NA	+0.8	NA	+0.6	NA
MEZZ LL	+25.6	NA	+34.1	NA	+34.1	NA	+34.0	NA	+25.6	NA

\*Earthquake reactions do not include any amplifications for overstrength which may or may not be required in the design of column anchorage and foundation by others.  
 H1 = horizontal force in the plane of frame  
 H2 = horizontal force perpendicular to the plane of frame

LOADING CONDITION	FRAME LINE 5									
	K		I			G,E		C		A
	V (kips)	H1 (kips)	V (kips)	H1 (kips)	H2 (kips)	V (kips)	H2 (kips)	V (kips)	H2 (kips)	V (kips)
D	+0.5	NA	+0.9	NA	NA	+1.1	NA	+0.9	NA	+0.5
C	+0.3	NA	+0.8	NA	NA	+0.9	NA	+0.8	NA	+0.3
L	+2.0	NA	-0.3 to +3.6	NA	NA	+6.5	NA	-0.3 to +5.6	NA	+2.0
S	+1.2	NA	+2.9	NA	NA	+5.0	NA	+2.9	NA	+1.2
W	-3.3 to +3.3	-2.3 to +2.3	-4.5 to +3.3	-2.3 to +2.3	-2.3 to +2.6	-4.8 to +0.2	-2.9 to +3.3	-4.5 to +0.1	-2.3 to +2.6	-1.4 to +0.2
E*	-1.8 to +1.8	-1.3 to +1.3	-1.8 to +1.8	-1.3 to +1.3	NA	+0.2	NA	+0.1	NA	+0.2

\*Earthquake reactions do not include any amplifications for overstrength which may or may not be required in the design of column anchorage and foundation by others.  
 H1 = horizontal force in the plane of frame  
 H2 = horizontal force perpendicular to the plane of frame



LOADING CONDITION	FRAME LINE 1.8	
	C	A
	V (kips)	V (kips)
D	+2.9	+2.9
C	+0.3	+0.3
MEZZ LL	+12.5	+12.5

\*Earthquake reactions do not include any amplifications for overstrength which may or may not be required in the design of column anchorage and foundation by others.  
 H1 = horizontal force in the plane of frame  
 H2 = horizontal force perpendicular to the plane of frame


\*\*NOT FOR CONSTRUCTION\*\*

CAROLINA DIESEL TRUCKS  
 62 PROGRESS DRIVE  
 FUQUAY VARINA, NC 27526  
 THOMAS ANDREWS



DRAWING STATUS:  
**FOR APPROVAL ONLY**  
 SOFTWARE VERSIONS: DESIGN: MSA 47.3 BIM: v20.6  
 JOB NUMBER: **A17B0157A** SHEET: **AB-3**

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					



PRIMARY FRAMING SHAKEOUT PLAN

**\*\*NOT FOR CONSTRUCTION\*\***

CAROLINA DIESEL TRUCKS  
 62 PROGRESS DRIVE  
 FUQUAY VARINA, NC 27526  
 THOMAS ANDREWS



DRAWING STATUS:  
**FOR APPROVAL ONLY**  
 SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6  
 JOB NUMBER: **A17B0157A** SHEET: **E-01**

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					




MEMBER SIZE TABLE						
ASSEMBLY NAME	OUTSIDE FLANGE	WEB THICK	WEB LENGTH	STARTING WEB DEPTH	ENDING WEB DEPTH	INSIDE FLANGE
RC1	8" X 1/4 X 21'-2 13/16	8GA	18'-1 9/16	1'-0 1/16	2'-10 1/8	8" X 5/16 X 18'-7 13/16
		8GA	3'-1 5/16	2'-10 1/8	2'-10 11/16	
RR1	6" X 1/4 X 49'-11 1/4	8GA	9'-11 5/8	2'-10 3/4	2'-8 1/8	6" X 5/16 X 7'-3 7/16
		8GA	20'-0	2'-8 1/8	2'-0 7/8	6" X 1/4 X 39'-10 5/16
		10GA	19'-11 5/8	2'-0 7/8	1'-5 3/4	
RC2	8" X 1/4 X 21'-2 13/16	8GA	18'-1 9/16	1'-0 1/16	2'-10 1/8	8" X 5/16 X 18'-7 13/16
		8GA	3'-1 5/16	2'-10 1/8	2'-10 11/16	

NOTE: MEMBERS LIST FOR EACH ASSEMBLY ARE IN ORDER FROM LOWEST TO HIGHEST ELEVATION.

SPLICE BOLT TABLE				
SPLICE	BOLTS	CLEAR TO F.F.	PLATE SIZE	PLATE SIZE
A	(8) 3/4 X 2 3/4 A325T	18'-6 1/2	8" X 1/2	8" X 1/2
B	(2) 3/4 X 2 3/4 A325T (6) 3/4 X 2 A325T	23'-9 3/16	6" X 3/8	6" X 3/8
C	(8) 3/4 X 2 3/4 A325T	18'-6 1/2	8" X 1/2	8" X 1/2

Purlin and Girt depth and spacing are subject to change upon final design.  
 Flange braces from the girts and purlins to the columns and rafters are required for structural stability, but are not shown on this drawing for clarity. This drawing shall not be construed as allowing the structure to be erected without flange braces.



FRAME ID: A17B0157A.01A 06/03/17 12:43

RIGID FRAME CROSS SECTION AT FL. 1 BLDG 1

\*\*NOT FOR CONSTRUCTION\*\*

CAROLINA DIESEL TRUCKS  
 62 PROGRESS DRIVE  
 FUQUAY VARINA, NC 27526  
 THOMAS ANDREWS



DRAWING STATUS:  
**FOR APPROVAL ONLY**  
 SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6  
 JOB NUMBER: A17B0157A  
 SHEET: E-02

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					




MEMBER SIZE TABLE						
ASSEMBLY NAME	OUTSIDE FLANGE	WEB THICK	WEB LENGTH	STARTING WEB DEPTH	ENDING WEB DEPTH	INSIDE FLANGE
RR3	6" X 1/2 X 29'-4 11/16	7/32	9'-4 11/16	2'-10 11/16	2'-8 1/4	6" X 1/2 X 6'-8 3/8
	6" X 3/8 X 19'-11 1/2	3/16	19'-11 1/2	2'-8 1/4	2'-1	6" X 3/8 X 39'-10 3/16
		3/16	20'-0	2'-1	1'-5 3/4	
RC5	8" X 5/16 X 21'-3 1/8	8GA	14'-11 5/8	1'-0 1/16	2'-6 1/4	8" X 1/2 X 18'-7 15/16
		7/32	6'-3 1/2	2'-6 1/4	2'-10 11/16	

NOTE: MEMBERS LIST FOR EACH ASSEMBLY ARE IN ORDER FROM LOWEST TO HIGHEST ELEVATION.

SPLICE BOLT TABLE				
SPLICE	BOLTS	CLEAR TO F.F.	PLATE SIZE	PLATE SIZE
A	(10) 3/4 X 2 3/4 A325T	18'-6 9/16	8" X 5/8	8" X 5/8
B	(8) 3/4 X 2 3/4 A325T	23'-8 13/16	6" X 1/2	6" X 1/2
C	(10) 3/4 X 2 3/4 A325T	18'-6 9/16	8" X 5/8	8" X 5/8

Purlin and Girt depth and spacing are subject to change upon final design.  
 Flange braces from the girts and purlins to the columns and rafters are required for structural stability, but are not shown on this drawing for clarity. This drawing shall not be construed as allowing the structure to be erected without flange braces.



RIGID FRAME CROSS SECTION AT FL. 3-4 BLDG 1

**\*\*NOT FOR CONSTRUCTION\*\***

CAROLINA DIESEL TRUCKS  
 62 PROGRESS DRIVE  
 FUQUAY VARINA, NC 27526  
 THOMAS ANDREWS




DRAWING STATUS:  
**FOR APPROVAL ONLY**  
 SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6  
 JOB NUMBER: **A17B0157A**  
 SHEET: **E-04**

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					

SPLICE BOLT TABLE				
SPLICE	BOLTS	CLEAR TO F.F.	PLATE SIZE	PLATE SIZE
A	(4) 1/2 X 1 1/4 A325T	20'-6 13/16	5" X 1/4	N/A
B	(4) 1/2 X 1 1/4 A325T	22'-0 1/8	8" X 3/8	N/A
C	(8) 3/4 X 2 A325T	22'-3 11/16	6" X 3/8	6" X 3/8
D	(4) 1/2 X 2 A325T	23'-6 3/4	8" X 3/8	N/A
E	(8) 3/4 X 2 A325T	24'-5 9/16	6" X 3/8	6" X 3/8
F	(4) 1/2 X 2 A325T	23'-6 3/4	8" X 3/8	N/A
G	(8) 3/4 X 2 A325T	22'-3 11/16	6" X 3/8	6" X 3/8
H	(4) 1/2 X 1 1/4 A325T	22'-0 1/8	8" X 3/8	N/A
I	(4) 1/2 X 1 1/4 A325T	20'-6 13/16	5" X 1/4	N/A

THIS FRAME MUST NOT BE ERECTED WITHOUT THE PIPE AND/OR GIRT STRUT MEMBERS. REFER TO THE ENDWALL ELEVATION AT THIS FRAME LINE FOR ANY REQUIRED GIRTS.

Purlin and Girt depth and spacing are subject to change upon final design.  
 Flange braces from the girts and purlins to the columns and rafters are required for structural stability, but are not shown on this drawing for clarity. This drawing shall not be construed as allowing the structure to be erected without flange braces.




COLUMN & BEAM CROSS SECTION AT FL. 5 BLDG 1

\*\*NOT FOR CONSTRUCTION\*\*

CAROLINA DIESEL TRUCKS  
 62 PROGRESS DRIVE  
 FUQUAY VARINA, NC 27526  
 THOMAS ANDREWS

 AMERICAN BUILDINGS <small>A NUCOR COMPANY</small>  MEMBER	DRAWING STATUS: <b>FOR APPROVAL ONLY</b>
	SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6 JOB NUMBER: <b>A17B0157A</b>
SHEET: <b>E-05</b>	

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					



SHORTENED MARKS	
SHOWN	ACTUAL
S1	CLRB1

PLANE ID: 1004, 1005

**ROOF FRAMING PLAN BLDG 1**

**\*\*NOT FOR CONSTRUCTION\*\***


CAROLINA DIESEL TRUCKS  
62 PROGRESS DRIVE  
FUQUAY VARINA, NC 27526  
THOMAS ANDREWS



DRAWING STATUS: <b>FOR APPROVAL ONLY</b>	
SOFTWARE VERSIONS	DESIGN: MSA 47.3 BIM: v20.6
JOB NUMBER: <b>A17B0157A</b>	SHEET: <b>E-06</b>

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					

Purlin and Girt depth and spacing are subject to change upon final design.  
 Flange braces from the girts and purlins to the columns and rafters are required for structural stability, but are not shown on this drawing for clarity. This drawing shall not be construed as allowing the structure to be erected without flange braces.



PLANE ID: 1001, 1002

FRAMED OPENING TABLE				
MARK	WIDTH	HEIGHT	SILL HEIGHT	TYPE
1	16'-0	8'-0		

ENDWALL FRAMING ELEVATION AT LINE 1 BLDG 1

**\*\*NOT FOR CONSTRUCTION\*\***

CAROLINA DIESEL TRUCKS  
 62 PROGRESS DRIVE  
 FUQUAY VARINA, NC 27526  
 THOMAS ANDREWS




DRAWING STATUS:  
**FOR APPROVAL ONLY**  
 SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6  
 JOB NUMBER: **A17B0157A**  
 SHEET: **E-07**

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					

THIS ENDWALL FRAME MUST NOT BE ERECTED WITHOUT THE CROSS BRACING. REFER TO THE FRAME CROSS SECTION AT THIS FRAME LINE FOR THE REQUIRED CROSS BRACING.

Purlin and Girt depth and spacing are subject to change upon final design.  
 Flange braces from the girts and purlins to the columns and rafters are required for structural stability, but are not shown on this drawing for clarity. This drawing shall not be construed as allowing the structure to be erected without flange braces.



1 ADDED FIELD LOCATED WALKDOOR6-14-17RCC

PLANE ID: 1003

FRAMED OPENING TABLE				
MARK	WIDTH	HEIGHT	SILL HEIGHT	TYPE
1	20'-0"	18'-0"		OVERHEAD DOOR
2	6'-0"	7'-0"		PERSONNEL DOOR

ENDWALL FRAMING ELEVATION AT LINE 5 BLDG 1


\*\*NOT FOR CONSTRUCTION\*\*

CAROLINA DIESEL TRUCKS  
 62 PROGRESS DRIVE  
 FUQUAY VARINA, NC 27526  
 THOMAS ANDREWS



DRAWING STATUS:  
**FOR APPROVAL ONLY**  
 SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6  
 JOB NUMBER: A17B0157A  
 SHEET: E-08

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					




1 ADDED FIELD LOCATED WALKDOOR 6-14-17RCC

PLANE ID: 1001

FRAMED OPENING TABLE				
MARK	WIDTH	HEIGHT	SILL HEIGHT	TYPE
1	3'-0"	7'-0"		PERSONNEL DOOR
2	3'-4"	7'-2"		PERSONNEL DOOR

**SIDEWALL FRAMING ELEVATION AT LINE A BLDG 1**



**\*\*NOT FOR CONSTRUCTION\*\***


CAROLINA DIESEL TRUCKS  
62 PROGRESS DRIVE  
FUQUAY VARINA, NC 27526  
THOMAS ANDREWS



DRAWING STATUS:  
**FOR APPROVAL ONLY**  
SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6  
JOB NUMBER: **A17B0157A**  
SHEET: **E-09**

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					







1 ADDED FIELD LOCATED WALKDOOR6-14-17RCC

PLANE ID: 1000

FRAMED OPENING TABLE				
MARK	WIDTH	HEIGHT	SILL HEIGHT	TYPE
1	12'-0	9'-0		
2	3'-0	7'-0		PERSONNEL DOOR

SIDEWALL FRAMING ELEVATION AT LINE K BLDG 1



\*\*NOT FOR CONSTRUCTION\*\*

CAROLINA DIESEL TRUCKS  
62 PROGRESS DRIVE  
FUQUAY VARINA, NC 27526  
THOMAS ANDREWS



DRAWING STATUS:  
**FOR APPROVAL ONLY**  
SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6  
JOB NUMBER: A17B0157A  
SHEET: E-10

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					




ERECTION NOTE!!!  
ALL ROOF PANEL SIDELAP TO PURLIN INTERSECTIONS REQUIRE PANEL CLIPS.

REAR ROOF SHEETING PLAN BLDG 1

ROOF SHEETING @ 1005: (TBD)

PLANE ID: 1005

Aluminum-Coated panels are subject to staining due to residue from bare hands. Aluminum-Coated panels that include an acrylic finish do have additional protection, but it is limited and deteriorates in a relatively short time making that panel also subject to staining from bare hands. It is recommended that gloves be used for all handling of both products and that application of these products be limited to areas not exposed to touch.



PLANE ID: 1004

ROOF SHEETING @ 1004: (TBD)

FRONT ROOF SHEETING PLAN BLDG 1

\*\*NOT FOR CONSTRUCTION\*\*


CAROLINA DIESEL TRUCKS  
62 PROGRESS DRIVE  
FUQUAY VARINA, NC 27526  
THOMAS ANDREWS



DRAWING STATUS:  
**FOR APPROVAL ONLY**  
SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6  
JOB NUMBER:  
**A17B0157A**  
SHEET:  
**E-12**

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					

ERECTION NOTE!!!  
 ALL WALL PANELS MUST BE FASTENED TO ALL GIRTS (PARTIAL BAY OR FULL BAY) ACCORDING TO THE  
 REQUIRED FASTENER LAYOUT DETAILS.



PLANE ID: 1002

SHEETING PACKAGE: SP1014(FXGY)

**ENDWALL SHEETING ELEVATION AT LINE 1 BLDG 1**

FRAMED OPENING TABLE				
MARK	WIDTH	HEIGHT	TYPE	TRIM
1	16'-0	8'-0		


CAROLINA DIESEL TRUCKS  
 62 PROGRESS DRIVE  
 FUQUAY VARINA, NC 27526  
 THOMAS ANDREWS



DRAWING STATUS:  
**FOR APPROVAL ONLY**  
 SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6  
 JOB NUMBER: **A17B0157A**  
 SHEET: **E-13**

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					

ERECTION NOTE!!!  
 ALL WALL PANELS MUST BE FASTENED TO ALL GIRTS (PARTIAL BAY OR FULL BAY) ACCORDING TO THE  
 REQUIRED FASTENER LAYOUT DETAILS.



1 ADDED FIELD LOCATED WALKDOOR6-14-17RCC

PLANE ID: 1003

SHEETING PACKAGE: SP1015(FXGY)

ENDWALL SHEETING ELEVATION AT LINE 5 BLDG 1

FRAMED OPENING TABLE				
MARK	WIDTH	HEIGHT	TYPE	TRIM
1	20'-0"	18'-0"	OVERHEAD DOOR	
2	6'-0"	7'-0"	PERSONNEL DOOR	


CAROLINA DIESEL TRUCKS  
 62 PROGRESS DRIVE  
 FUQUAY VARINA, NC 27526  
 THOMAS ANDREWS



DRAWING STATUS:  
**FOR APPROVAL ONLY**  
 SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6  
 JOB NUMBER: A17B0157A  
 SHEET: E-14

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					

ERECTION NOTE!!!  
ALL WALL PANELS MUST BE FASTENED TO ALL GIRTS (PARTIAL BAY OR FULL BAY) ACCORDING TO THE REQUIRED FASTENER LAYOUT DETAILS.




1 ADDED FIELD LOCATED WALKDOOR6-14-17RCC

PLANE ID: 1001

SHEETING PACKAGE: SP1013(FXGY)

FRAMED OPENING TABLE				
MARK	WIDTH	HEIGHT	TYPE	TRIM
1	3'-0	7'-0	PERSONNEL DOOR	
2	3'-4	7'-2	PERSONNEL DOOR	

**SIDEWALL SHEETING ELEVATION AT LINE A BLDG 1**



1 ADDED FIELD LOCATED WALKDOOR6-14-17RCC

PLANE ID: 1000

SHEETING PACKAGE: SP1012(FXGY)

FRAMED OPENING TABLE				
MARK	WIDTH	HEIGHT	TYPE	TRIM
1	12'-0	9'-0		
2	3'-0	7'-0	PERSONNEL DOOR	

**SIDEWALL SHEETING ELEVATION AT LINE K BLDG 1**

CAROLINA DIESEL TRUCKS  
62 PROGRESS DRIVE  
FUQUAY VARINA, NC 27526  
THOMAS ANDREWS



DRAWING STATUS:  
**FOR APPROVAL ONLY**  
SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6  
JOB NUMBER: A17B0157A  
SHEET: E-15

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					

**STANDARD FLASHING PROFILES**

NOTE: DRAWINGS NOT TO SCALE, DRAWINGS TO REPRESENT PROFILE ONLY

**COLD FORMED ANGLES**  
20'2" LENGTH

GA-1: 6 3/8" width, 5 1/8" height  
 GA-2: 2 1/4" width, 3" height  
 GA-3: 4 9/16" width, 6 1/4" height  
 GA-4: 2 9/16" width, 8 1/4" height  
 GA-5: 3" width, 11 1/8" height  
 GA-6: 7 1/8" width, 7 7/8" height  
 GA-7: 2 1/8" width, 8" height

MARK # → BA-20 LENGTH → (20'2) DESCRIPTION → BASE TRIM	FC1V_-- (VARIES) C FLASHING	FCI (15'2) L3P IN. CORNER	FCIA2 (15'2) A3P IN. CORNER	FCP1 (15'2) PANEL CAP	FCR (15'2) L3P CORNER	FCRA2 (TCAV SIM.)(15'2) A3P/AVP CORNER	FDH2_-- (VARIES) DOOR HEADER/SPACER	FDH4-10.2 (10'2)	FFC (15'2) SHADOW PANEL TRIM	FFW (15'2) PANEL TRIM	FJ15_-- (VARIES) L3P J TRIM	FJ15B_-- (VARIES) A3P J TRIM
FJ2 (15'2) J FLASHING	FL2A_-- (15'2) SOFFIT TRIM	FL22A_--10.2 (10'2) SOFFIT SUPP.	FL2V_-- (15'2)	FL3A_-- (15'2)	FL3V_-- (15'2)	FL6 (15'2)	FL7 (15'2)	FL8 (15'2)	FL13 (15'2)	FL17 (15'2)	FL18 (15'2)	FPEC1-10.2 (10'2) PANEL END COVER
FOCF_-- & FOHF_-- (VARIES) F.O. COVER TRIM	THSRW_-- (15'2) ROOF TO WALL OH EAVE	FSF_-- (15'2)	FSJ1 (15'2) SILL/JAMB	LARF1 (15'2) AUX. RAKE	MEC2 (15'2)	PED_-- (15'2) DELUX EAVE	PF95_-- (VARIES) PARTITION TRIM	TRCP_-- (15'2) RIDGE FLASHING	RJF1 (15'2) RIDGE SUPPORT	RLF_-- (15'2) RIDGE LINER	RSF1 (15'2) TRIM RAKE SUPPORT	
SEF1 (15'2) EXPANSION TRIM	SEF2 (15'2)	TARF1 (15'2)	TFEC_-- (15'2) EAVE CLOSURE	TFSET	TFSE (15'2) EAVE SUPPORT	TGT1 (15'2) STANDARD GUTTER	THC_-- (15'2) HIGHSIDE EAVE	THL_-- (15'2) HIGHSIDE EAVE	THE_-- (15'2) HIGHSIDE EAVE	TICAV (15'2) AVP IN. CORNER	TL1 (15'2) RIDGE CLOSURE COVER TRIM	
TR1 & TRU1 (15'2) RAKE TRIM	TR1C (15'2) CUSTOM RAKE TRIM	TR1S (15'2)	TRCZ (15'2) RIDGE CLOSURE	TRW (15'2) Z ROOF TO WALL	TTEC (15'2) EXPANSION TRIM	TTES (15'2)	TVG1_--10.2 (10'2) PARAPET GUTTER	TVG2_--10.2 (10'2) VALLEY GUTTER	VFF1 (15'2) PARAPET/FACADE FLASHING	VFF7 (15'2) DRIP FLASHING		

NOTE: DUE TO MATERIALIZATION USAGE FLASHING LENGTHS MAY BE SUBSTITUTED WITH LONGER LENGTHS THAN WHAT IS CALLED OUT ON THE BILL OF LADING.

NOTE: GALVANIZED PIECES SUCH AS TFSE/RJF-1/TRCZ MAY BE PLACED UNDERNEATH THE PLASTIC ON THE BOTTOM SIDE OF THE FLASHING CRATE.

**STANDARD SCREWS & BOLTS**

1/8 RIVET, SRV-1, #10X1 SDPH, #10X1 STPH, #10X1 1/2 STHHW (WOODMATE), #12X1 1/4 SDHH, 1/2 X2 3/16 DE, 1/2 X1 1/4 BHB, #12X1 1/4 SDRF, #12X1 1/2 SDHHT5, #12X1 1/4 SDHHT4(SIM.), #14X3/4 SDHH, #14X3/4 SDRF, #14X1 SDRF(SIM.), #12X1 SDYC, NUTBLK, FAS 10-4 (FAB-LOK), 5/16 DRILL BOLT

**STANDARD CLIPS**

CPB-1 (5 3/4 X 10 GA X 5) (SAG CONNECTION), CL-2 (5 X 10 GA X 10 1/4) (CORNER CLIP), CL-3 (5 X 10 GA X 6 3/8) (JAMB/FO CLIP - COLD FORMED), CL-4 (5 X 10 GA X 7 7/8) (STR. CONNECTION OR INSET/FLUSH), CLFB (8 3/4 X 10 GA X 5) (FB WITH LINER), CL-15 (4 X 10 GA X 7 7/8) (CRIT/PURLIN REINFORCEMENT)

**FIXED EAVE & FIXED RAKE**

FR1 (15'2) FIXED RAKE, FEC\_ (15'2) FIXED EAVE

\*\*NOT FOR CONSTRUCTION\*\*


CAROLINA DIESEL TRUCKS  
62 PROGRESS DRIVE  
FUQUAY VARINA, NC 27526  
THOMAS ANDREWS

AMERICAN BUILDINGS  
A HUCOR COMPANY  
MEMBER

DRAWING STATUS:  
**FOR APPROVAL ONLY**

SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6  
JOB NUMBER: A17B0157A SHEET: SED-000

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					



THE FIRST STEP IN THE SUCCESSFUL INSTALLATION OF THE ROOF OR WALLS IS TO HAVE THE PRIMARY FRAMING PLUMB AND SQUARE. FOR BEST RESULTS, IT IS RECOMMENDED THAT A TRANSIT BE USED WHEN ERECTING THE STRUCTURAL STEEL. BE SURE TO READ THE GENERAL ERECTION GUIDE PRIOR TO COMMENCING ERECTION.

**BUILDING ALIGNMENT** GE01  
AA

**SAFETY NOTES:**

THE METAL BUILDING SUPPLIER STRONGLY RECOMMENDS THAT SAFE WORKING CONDITIONS AND ACCIDENT PREVENTION PRACTICES BE THE TOP PRIORITY ON ANY JOB SITE.

LOCAL, STATE AND FEDERAL SAFETY AND HEALTH STANDARDS SHOULD ALWAYS BE FOLLOWED TO HELP ENSURE WORKER SAFETY.

MAKE CERTAIN ALL EMPLOYEES KNOW THE SAFEST AND MOST PRODUCTIVE WAY OF ERECTING A BUILDING. EMERGENCY TELEPHONE NUMBERS, LOCATIONS OF FIRST AID STATIONS AND EMERGENCY PROCEDURES SHOULD BE KNOWN TO ALL EMPLOYEES.

DAILY MEETINGS HIGHLIGHTING SAFETY PROCEDURES, THE USE OF HARD HATS, RUBBER SOLE SHOES FOR ROOF WORK, PROPER EQUIPMENT FOR HANDLING MATERIAL AND SAFETY NETS WHERE POSSIBLE ARE RECOMMENDED ERECTION PRACTICES.

THE METAL BUILDING SUPPLIER INTENDS THAT THESE DRAWINGS BE INTERPRETED AND ADMINISTERED WITH SOUND JUDGMENT CONSISTENT WITH GOOD SAFETY PRACTICES.

ALL SAFETY PRECAUTIONS, OSHA SAFETY REQUIREMENTS, OR ANY OTHER APPROPRIATE SAFETY REQUIREMENTS, CUSTOMARY OR STATUTORY, MUST BE ADHERED TO, TO ENSURE MAXIMUM WORKER SAFETY.


IF OIL OR OTHER SLIPPERY SUBSTANCES ARE SPILLED ON THE ROOF/DECK PANELS, WIPE THEM OFF IMMEDIATELY TO PREVENT SLIPPING OR FALLING.

YOU SHOULD MAINTAIN A FIRM, SAFE POSITION WHEN USING ANY TOOL.

YOU SHOULD MAINTAIN A CONSTANT AWARENESS OF YOUR LOCATION IN RELATION TO THE ROOF EDGE WHEN USING TOOLS AND MACHINES OR PERFORMING ANY OTHER FUNCTION ON THE ROOF AREA.

DO NOT UNDER ANY CIRCUMSTANCES STEP OR WALK ON THE SURFACE OF ANY FIBERGLASS SKYLIGHT. IF FOOT TRAFFIC IS NECESSARY OVER SKYLIGHT, USE WALK BOARDS THAT ARE PROPERLY SUPPORTED BY THE BUILDING PURLINS.

**SAFETY COMMITMENT** GE70  
AA



**ASTM A325/A325T BOLT IDENTIFICATION** MF01  
AA

**BOLTED JOINTS**  
BOLTED JOINTS SHALL BE CONNECTED AND INSPECTED IN ACCORDANCE WITH THE 'SPECIFICATION FOR STRUCTURAL JOINTS USING HIGH-STRENGTH BOLTS', DECEMBER 31, 2009, APPROVED BY THE RESEARCH COUNCIL ON STRUCTURAL CONNECTIONS COMMITTEE.

**SNUG-TIGHT JOINTS**  
UNLESS NOTED OTHERWISE ON THE METAL BUILDING SUPPLIERS ERECTION DRAWINGS, ALL A325 BOLTS ARE USED IN CONNECTIONS DEFINED AS SNUG-TIGHT JOINTS (S7). FOR INSTALLATION IN SNUG-TIGHT JOINTS, ALL BOLT HOLES SHALL BE ALIGNED TO PERMIT BOLT INSERTION WITHOUT UNDUE DAMAGE TO THE THREADS. BOLTS SHALL BE PLACED IN ALL HOLES WITH NUTS THREADED TO COMPLETE THE ASSEMBLY BEFORE COMPACTING THE JOINT TO THE SNUG-TIGHT POSITION, PROGRESSING SYSTEMATICALLY FROM THE MOST RIGID PART OF THE JOINT. SNUG TIGHT IS THE CONDITION THAT EXISTS WHEN ALL HAVE BEEN PULLED INTO FIRM CONTACT BY THE BOLTS IN THE JOINT AND ALL BOLTS IN THE JOINT HAVE BEEN TIGHTENED SUFFICIENTLY TO PREVENT THE REMOVAL OF THE NUTS WITHOUT THE USE OF A WRENCH. MORE THAN ONE CYCLE THROUGH THE BOLT PATTERN MAY BE REQUIRED.

**PRETENSIONED AND SLIP-CRITICAL JOINTS**  
CONNECTIONS WHICH ARE DEFINED AS PRETENSIONED (PT) OR SLIP-CRITICAL (SC) JOINTS WILL BE AS NOTED ON THE ERECTION DRAWINGS BY THE METAL BUILDING MANUFACTURER OR BY THE ENGINEER OF RECORD. ALL CONNECTIONS WITH A490 BOLTS ARE EITHER PRETENSIONED (PT) OR SLIP-CRITICAL (SC) JOINTS. PRETENSIONED JOINTS ARE TYPICALLY REQUIRED WHEN THE JOINT IS SUBJECT TO SIGNIFICANT LOAD REVERSAL. THE JOINT IS SUBJECT TO FATIGUE LOAD WITH NO LOAD REVERSAL. THE BOLTS ARE SUBJECT TO TENSILE FATIGUE. THE BUILDING SUPPORTS A CRANE OF OVER 5-TON CAPACITY, OR THE CONNECTION IS PART OF THE SEISMIC LOAD RESISTING SYSTEM AND AISC SEISMIC PROVISIONS (AISC 341) ARE APPLICABLE. THE SEISMIC PROVISIONS ARE APPLICABLE WHEN THE SEISMIC RESPONSE MODIFICATION COEFFICIENT, R, IS TAKEN GREATER THAN 3. LOADINGS FROM WIND OR SNOW ARE NOT CONSIDERED SIGNIFICANT LOAD REVERSAL OR FATIGUE LOADINGS. SLIP CRITICAL JOINTS ARE REQUIRED WHEN SLIP IS DETERMINED TO BE DETRIMENTAL TO THE PERFORMANCE OF THE STRUCTURE. INSTALLATION METHODS PERMITTED FOR PRETENSIONED JOINTS INCLUDE TURN-OF-NUT PRETENSIONING, CALIBRATED WRENCH PRETENSIONING, TWIST-OFF-TYPE TENSION CONTROL BOLT PRETENSIONING, AND DIRECT-TENSION-INDICATOR PRETENSIONING. HOT DIP GALVANIZED CONNECTIONS MAY REQUIRE RE-PRETENSIONING AFTER 5 DAYS OF SETTLING.

**TURN-OF-NUT PRETENSIONING**  
FIRST TIGHTEN ALL BOLTS IN ACCORDANCE WITH THE ABOVE SNUG-TIGHT PROCEDURE. THEN ROTATE THE NUT OR HEAD BY THE AMOUNT SPECIFIED IN THE BOLT PRETENSION SCHEDULE. PROGRESSING SYSTEMATICALLY FROM THE MOST RIGID PART OF THE JOINT. THE PART NOT TURNED BY THE WRENCH SHALL BE PREVENTED FROM ROTATING DURING THIS OPERATION. IF THE NUT IS TURNED IN THE LOOSENING POSITION THE BOLT MUST BE REMOVED AND REPLACED. PRETENSION VALUES EQUAL TO OR GREATER THAN THE MINIMUM VALUES LISTED IN THE BOLT PRETENSION SCHEDULE ARE REQUIRED.

NOMINAL BOLT DIAMETER, d <sub>b</sub>	SPECIFIED MINIMUM BOLT PRETENSION, T <sub>m</sub> , KIPS		NUT OR HEAD ROTATION FROM SNUG-TIGHT CONDITION	
	ASTM A325 AND F1852	ASTM A490 AND F2280	L <sub>b</sub> ≤ 4d <sub>b</sub>	4d <sub>b</sub> < L <sub>b</sub> ≤ 8d <sub>b</sub>
1/2"	13 KIPS	16 KIPS	1/3 TURN	1/2 TURN
3/4"	29 KIPS	37 KIPS		
7/8"	41 KIPS	51 KIPS		
1"	54 KIPS	67 KIPS		
1 1/4"	75 KIPS	107 KIPS		

(L<sub>b</sub> = LENGTH OF BOLT)

**INSPECTION REQUIREMENTS PRIOR TO START OF WORK:**  
VERIFY ALL FASTENER COMPONENTS CONFORM TO REQUIREMENTS.

**INSPECTION REQUIREMENTS FOR SNUG-TIGHT JOINTS:**  
VERIFY THAT THE PROPER FASTENER COMPONENTS WERE USED AND THAT THE CONNECTED ELEMENTS WERE FABRICATED PROPERLY. AFTER ASSEMBLY, IT SHALL BE VISUALLY ENSURED THAT THE PLIES ARE SOLIDLY SEATED AGAINST EACH OTHER, BUT NOT NECESSARILY IN CONTINUOUS CONTACT. THAT WASHERS, IF REQUIRED, HAVE BEEN USED, AND THAT ALL BOLTS IN THE JOINT HAVE BEEN TIGHTENED SUFFICIENTLY TO PREVENT THE TURNING OF THE NUTS WITHOUT THE USE OF A WRENCH. NO FURTHER EVIDENCE OF CONFORMITY IS REQUIRED.

**INSPECTION REQUIREMENTS FOR TURN-OF-NUT PRETENSIONING:**  
FOR TURN-OF-NUT PRETENSIONING, IN ADDITION TO THE INSPECTION REQUIREMENTS FOR SNUG-TIGHT JOINTS, THE INSPECTOR SHALL OBSERVE THE PRE-INSTALLATION VERIFICATION TESTING AND MONITOR THE WORK IN PROGRESS TO ENSURE THAT THE BOLTING CREW PROPERLY ROTATES THE TURNED ELEMENT BY THE AMOUNT SPECIFIED IN THE SCHEDULE. ALTERNATIVELY, WHEN THE FASTENERS ARE MATCH-MARKED AFTER INITIAL FIT-UP (SNUG-TIGHT CONDITION), VISUAL INSPECTION IS PERMITTED. THE SIDE OF NUTS AND BOLTS THAT HAVE BEEN IMPACTED SUFFICIENTLY TO INDUCE THE MINIMUM PRETENSION LOADS WILL APPEAR SLIGHTLY PEENED. NO FURTHER EVIDENCE OF CONFORMITY IS REQUIRED.

**BOLT INSTALLATION & INSPECTION NOTES** MF91  
AA

1/2", 3/4", 7/8", 1" & 1 1/4" STRUCTURAL BOLTS (A325)

**\*\*NOT FOR CONSTRUCTION\*\***

CAROLINA DIESEL TRUCKS  
62 PROGRESS DRIVE  
FUQUAY VARINA, NC 27526  
THOMAS ANDREWS













DRAWING STATUS:  
**FOR APPROVAL ONLY**

SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6

JOB NUMBER: **A17B0157A** SHEET: **SED-001**

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					





**\*\*NOT FOR CONSTRUCTION\*\***


CAROLINA DIESEL TRUCKS  
62 PROGRESS DRIVE  
FUQUAY VARINA, NC 27526  
THOMAS ANDREWS

AMERICAN BUILDINGS  
A HUBCOR COMPANY  
MBMA  
ACCREDITED  
AC472


DRAWING STATUS:  
**FOR APPROVAL ONLY**  
SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6  
JOB NUMBER: A17B0157A  
SHEET: SED-002

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					

**SAFETY PRECAUTION:**  
STAY WELL IN THE CLEAR OF LOADS BEING MOVED BY ANY TYPE LIFTING DEVICE. BE SURE TO KEEP HANDS AND FEET CLEAR OF MOVING LOADS.




DIAGONAL HAUNCH CONNECTION AT BLDG. EAVE  
RIGID FRAME  
MF11  
AA




TYPICAL CONNECTION AT GAPS  
RIGID FRAME  
MF19  
AA

- SAFETY PRECAUTION:**  
WORKERS SHOULD BE TRAINED IN THE PROPER ERECTION PROCEDURES FOR ALL JOBS.
- SHIMS REQUIRED AT GAPS > 1/8".
  - PLACE NON-TAPERED SHIMS BETWEEN BOLT PAIRS AS REQUIRED IN GAPS IN COMPRESSION AREA GREATER THAN 1/8" AND TACK WELD.
  - TACK WELD NON-TAPERED SHIMS 1" MIN. x E x T BOTH SIDES BETWEEN 2" x T x W NON-TAPERED SHIMS TO MEET AISC "FINGER" STYLE.
  - ALL SHIMMING MATERIAL MILD STEEL.
  - RIDGE SHIMMING DETAILS SIMILAR.




RIDGE RAFTER CONNECTION DETAIL  
RIGID FRAME RAFTER  
MF22  
AA

**SAFETY PRECAUTION:**  
WORKER PERSONAL PROTECTION EQUIPMENT SHOULD ALWAYS MEET OSHA STANDARDS.




ANTI-ROLL DETAIL DOWNHILL  
RIGID FRAME RAFTER  
RF50A  
AA



**SAFETY PRECAUTION:**  
ALWAYS WEAR OSHA APPROVED EYE PROTECTION WHEN OPERATING DRILLS OR ELECTRIC SCREW GUNS.



CABLE/ROD BRACING TYPICAL END CONNECTIONS  
BR01  
AA



ROD BRACING ASSEMBLY  
BR01W  
AA



STIFFENER MOUNTED 6" OR 8" PIPE STRUT AT COLUMN  
BR15W  
AA

**\*\*NOT FOR CONSTRUCTION\*\***

CAROLINA DIESEL TRUCKS  
62 PROGRESS DRIVE  
FUQUAY VARINA, NC 27526  
THOMAS ANDREWS



DRAWING STATUS:  
**FOR APPROVAL ONLY**  
SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6  
JOB NUMBER: A17B0157A  
SHEET: SED-003


NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					

RAFTER/COLUMN FLANGE THICKNESS	SECONDARY MEMBER GAUGE	DOUBLE ENDED BOLT 1/2" X 2 3/16" A449 (NUTS INCLUDED) REQUIRED AT GIRTS OPTIONAL AT PURLINS	1/2" A325T BOLT REQUIRED FOR LAPPED MEMBERS (REQUIRES 1/2 HVHX NUT)	1/2" A325T BOLT REQUIRED FOR NON LAPPED MEMBERS (REQUIRES 1/2 HVHX NUT)
< 3/8"	11-16	1/2X2 3/16 A449 DE	1/2X1 1/4 A325T	1/2X1 1/4 A325T
	16	1/2X2 3/16 A449 DE	1/2X1 1/4 A325T	1/2X1 1/4 A325T
	15	1/2X2 3/16 A449 DE	1/2X1 1/4 A325T	1/2X1 1/4 A325T
	14	1/2X2 3/16 A449 DE	1/2X1 1/4 A325T	1/2X1 1/4 A325T
3/8"	13	1/2X2 3/16 A449 DE	1/2X1 1/4 A325T	1/2X1 1/4 A325T
	12	1/2X2 3/16 A449 DE	1/2X2 A325T	1/2X1 1/4 A325T
	11	1/2X2 3/16 A449 DE	1/2X2 A325T	1/2X1 1/4 A325T
	10	1/2X2 3/16 A449 DE	1/2X2 A325T	1/2X1 1/4 A325T
1/2"	15	1/2X2 3/16 A449 DE	1/2X2 A325T	1/2X2 A325T
	14	1/2X2 3/16 A449 DE	1/2X2 A325T	1/2X2 A325T
	13	1/2X2 3/16 A449 DE	1/2X2 A325T	1/2X2 A325T
	12	1/2X2 3/16 A449 DE	1/2X2 A325T	1/2X2 A325T


THE FOLLOWING FLANGE THICKNESS CONNECTIONS REQUIRE THE USE OF SHOP WELDED CLIPS. (SEE CONNECTION DETAILS.)

RAFTER/COLUMN FLANGE THICKNESS	SECONDARY MEMBER GAUGE	BUTTON HEAD BOLT AT WALL ZEE GIRTS ONLY 1/2" BUTTON HEAD BOLT (NUT INCLUDED) FIRST GIRT TO SHOP WELDED CLIP (UP THROUGH 1ST GIRT AND SHOP WELDED CLIP)	1/2" A325T BOLT REQUIRED FOR LAPPED AND NON LAPPED MEMBERS (REQUIRES 1/2 HVHX NUT)
1/2"	11	1/2 X 1 1/4 A307 BHB	1/2 X 1 1/4 A325
	16	1/2 X 1 1/4 A307 BHB	1/2 X 1 1/4 A325
	15	1/2 X 1 1/4 A307 BHB	1/2 X 1 1/4 A325
	14	1/2 X 1 1/4 A307 BHB	1/2 X 1 1/4 A325
> 1/2"	13	1/2 X 1 1/4 A307 BHB	1/2 X 1 1/4 A325
	12	1/2 X 1 1/4 A307 BHB	1/2 X 1 1/4 A325
	11	1/2 X 1 1/4 A307 BHB	1/2 X 1 1/4 A325
	10	1/2 X 1 1/4 A307 BHB	1/2 X 1 1/4 A325

BYPASS SECONDARY FRAMING CONNECTION, BOLT REQUIREMENTS **BS01 AA**




SAFETY PRECAUTION: DON'T ALLOW BLOCKING TO BE A FALLING HAZARD TO THOSE BENEATH THE ROOF. WORKERS SHOULD WEAR OSHA APPROVED HARD HATS.



Straight purlins are a necessity. Zee sections have a natural tendency to roll out of plane and deflect horizontally. This must be corrected by forcing the purlins into proper plane and spacing. Wood blocking is recommended as one method to accomplish this.

**Purlin Blocking**  
Before installing the roof panels and insulation, be certain that the purlins are straight and at 90° to the slope of the roof. Use wood blocking to assist with purlin alignment if adjustment is needed. Start with one row of temporary blocking in the center of the bay. Use additional rows of blocking if needed to maintain straight purlins. As sheeting progresses to within one panel width of the blocking it should hold the purlins in alignment allowing the blocking to be removed. Move blocking to next bay as the erection progresses.

PURLIN BLOCKING **GE02 AA**




SAFETY PRECAUTION: PUT WORKER SAFETY FIRST.

(2) 1/2X1 1/4 A325T/1/2 HVHX NUT OR AS AN OPTION (1) 1/2X1 1/4 A325T/1/2 HVHX NUT AND (1) 1/2X2 3/16 A449 DE - (TYP) MAY VARY SEE BS01AA


RAFTER FLANGE THICKNESS GREATER THAN 1/2" WITH SHOP WELDED CLIPS SEE DETAIL RF54AAA

STANDARD PURLIN LAP **RF01 AA**




SAFETY PRECAUTION: EACH WORKER SHOULD BE TRAINED TO USE THE SAFEST AND MOST PRODUCTIVE ERECTION TECHNIQUES.

PURLIN CONNECTION DETAIL AT ENDWALL FRAME **RF03R AA**




SAFETY PRECAUTION: WORKER PERSONAL PROTECTION EQUIPMENT SHOULD ALWAYS MEET OSHA STANDARDS.

RIDGE BRIDGING CLIP CONNECTION DETAIL **RF05 AA**




SAFETY PRECAUTION: WORKERS SHOULD ALWAYS WEAR GLOVES WHEN HANDLING METAL SURFACES WITH SHARP EDGES.

LOW/HIGH SIDE EAVE STRUT CONNECTION (INSET GIRTS) **RF31Q AA**




SAFETY PRECAUTION: WORKERS SHOULD ALWAYS WEAR GLOVES WHEN HANDLING METAL SURFACES WITH SHARP EDGES.

LOW/HIGH SIDE EAVE STRUT CONNECTION (BYPASS GIRTS) **RF31R AA**




SAFETY PRECAUTION: WORKERS SHOULD ALWAYS WEAR GLOVES WHEN HANDLING METAL SURFACES WITH SHARP EDGES.

LOW/HIGH SIDE EAVE STRUT CONNECTION (BYPASS GIRTS) **RF31RB AA**



SAFETY PRECAUTION: WORKERS SHOULD ALWAYS WEAR GLOVES WHEN HANDLING METAL SURFACES WITH SHARP EDGES.

LOW/HIGH SIDE EAVE STRUT CONNECTION (INSET GIRTS) **RF32Q AA**



SAFETY PRECAUTION: WORKERS SHOULD ALWAYS WEAR GLOVES WHEN HANDLING METAL SURFACES WITH SHARP EDGES.

LOW/HIGH SIDE EAVE STRUT CONNECTION (BYPASS GIRTS) **RF32R AA**


\*\*NOT FOR CONSTRUCTION\*\*

CAROLINA DIESEL TRUCKS  
62 PROGRESS DRIVE  
FUQUAY VARINA, NC 27526  
THOMAS ANDREWS




DRAWING STATUS: FOR APPROVAL ONLY  
SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6  
JOB NUMBER: A17B0157A  
SHEET: SED-004


NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					




**BRACING DETAIL-ROOF SLOPE LESS THAN OR EQUAL TO 1:12** BR51  
8" & 9 1/2" ZEE PURLINS w/CLIP-FASTENED ROOF - HIGH SIDE SIMILAR AA




**PURLIN BRACING KEY PLAN** BR90  
8" & 9 1/2" ZEE PURLINS w/CLIP-FASTENED ROOF AA




**BRACE ANGLE INSTALLATION** BR91  
CLIP-FASTENED ROOF AA



**BRACE CHANNEL INSTALLATION** BR92  
8" & 9 1/2" ZEE PURLIN AA



**PURLIN BRACING CROSS SECTION-ROOF SLOPES LESS THAN OR EQUAL TO 1:12** BR93  
8" OR 9 1/2" ZEE PURLIN w/CLIP-FASTENED ROOF - RIDGE BUILDING SHOWN, SINGLE SLOPE SIMILAR AA



**DETAIL AT RIDGE PURLIN** BR94  
8" OR 9 1/2" PURLIN BRACING AA

- PURLIN BRACING NOTES** BROA  
AA
1. APPLICABLE TO ROOFS WITH STANDING SEAM II, STANDING SEAM 360, LOC-SEAM, LOC-SEAM 360 AND SEAM-LOC PANELS.
  2. PURLINS ARE TO BE INSTALLED WITH PURLIN WEBS 90° TO RAFTERS.
  3. PURLIN BRACING IS NOT TO DISTORT OR ALTER PURLINS FROM THEIR INTENDED SHAPE AND LOCATION.
  4. SPACING AS REQUIRED BY DESIGN.
  5. FOR FACTORY MUTUAL REQUIREMENTS, PURLIN BRACING IS NOT TO EXCEED 80" O.C. AND IS REQUIRED ONLY IN THE END BAYS OF THE BUILDING.
- (BRACING NOT APPLICABLE WITH SCREW DOWN ROOF SYSTEMS)

**\*\*NOT FOR CONSTRUCTION\*\***



CAROLINA DIESEL TRUCKS  
62 PROGRESS DRIVE  
FUQUAY VARINA, NC 27526  
THOMAS ANDREWS



DRAWING STATUS:  
**FOR APPROVAL ONLY**  
SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6  
JOB NUMBER: A17B0157A SHEET: SED-005


NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					






NON-LAPPED BYPASS GIRT  
TYP. AT CORNER COLUMN OR ANY SINGLE BYPASS ZEE TO COLUMN

WF58R  
AA




BYPASS CHANNEL ENDWALL INTERIOR COLUMN

WF60R  
AA




BYPASS NON-LAPPED GIRT CONNECTION TO COLUMN  
AT COLUMN FLANGE THICKNESS LESS THAN OR EQUAL TO 1/2"

WF61R  
AA




FRAME BRACE  
FOR BYPASS PURLINS / GIRTS

BR17  
AA



FRAME BRACE  
INSET

BR17A  
AA



COLD-FORMED INTERIOR COLUMN FRAME BRACE  
FOR BYPASS GIRTS

BR17B  
AA

**\*\*NOT FOR CONSTRUCTION\*\***

CAROLINA DIESEL TRUCKS  
62 PROGRESS DRIVE  
FUQUAY VARINA, NC 27526  
THOMAS ANDREWS

AMERICAN BUILDINGS  
A NUCOR COMPANY  
MBMA  
ACCREDITED  
AC472

DRAWING STATUS:  
**FOR APPROVAL ONLY**

SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6


JOB NUMBER: **A17B0157A**

SHEET: **SED-007**

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					

USE WOOD BLOCKING TO ELEVATE AND SLOPE THE PANELS IN A MANNER THAT WILL ALLOW MOISTURE TO DRAIN. WOOD BLOCKING PLACED BETWEEN PANEL BUNDLES WILL PROVIDE ADDITIONAL AIR CIRCULATION. COVER THE STACKED BUNDLES WITH A TARP OR PLASTIC COVER LEAVING ENOUGH OPENING AT THE BOTTOM FOR AIR TO CIRCULATE.


SAFETY PRECAUTION:  
WORKERS SHOULD ALWAYS WEAR GLOVES WHEN HANDLING PANELS.



**PANEL STORAGE**  
LONG SPAN III, ARCHITECTURAL III, AND MULTI-RIB PANELS  
GE51  
AA

USE WOOD BLOCKING TO ELEVATE AND SLOPE THE PANELS IN A MANNER THAT WILL ALLOW MOISTURE TO DRAIN. WOOD BLOCKING PLACED BETWEEN PANEL BUNDLES WILL PROVIDE ADDITIONAL AIR CIRCULATION. COVER THE STACKED BUNDLES WITH A TARP OR PLASTIC COVER LEAVING ENOUGH OPENING AT THE BOTTOM FOR AIR TO CIRCULATE.


SAFETY PRECAUTION:  
WORKERS SHOULD ALWAYS WEAR GLOVES WHEN HANDLING PANELS.




**PANEL STORAGE**  
ARCHITECTURAL III  
WC51  
AC

USE WOOD BLOCKING TO ELEVATE AND SLOPE THE PANELS IN A MANNER THAT WILL ALLOW MOISTURE TO DRAIN. WOOD BLOCKING PLACED BETWEEN PANEL BUNDLES WILL PROVIDE ADDITIONAL AIR CIRCULATION. COVER THE AREA BENEATH PANELS WITH POLYETHYLENE OR A TARPAULIN TO PREVENT DIRT AND DEBRIS FROM ENTERING FEMALE SEAM.

SAFETY PRECAUTION  
MAINTAIN A CLEAN AND ORDERLY WORK AREA.



**PANEL STORAGE**  
STANDING SEAM  
RC51  
SA



TO FACILITATE THE HANDLING OF THE ROOF PANELS, PANEL BUNDLES CAN BE LIFTED AND PLACED ON THE ROOF IF LOCATED AT A RIGID FRAME AND WITH BLOCKING IN PLACE TO PREVENT THE PURLINS FROM ROLLING OVER. DO NOT SLIDE BUNDLED PANELS ALONG ROOF FRAMING. WHEN LIFTING BUNDLED SHEETS, MAKE CERTAIN THAT THE BUNDLE IS ADEQUATELY SUPPORTED. AS A RULE WHEN LIFTING, NO MORE THAN 1/3 OF THE LENGTH OF THE PANEL SHOULD BE LEFT UNSUPPORTED. REFER TO ERECTION DRAWINGS FOR THE ROOF PANEL MARKINGS AND STAGE BUNDLES ACCORDINGLY. THIS WILL MINIMIZE PANEL HANDLING AND SPEED THE ERECTION PROCEDURE.

**PANEL STORAGE ON ROOF**  
RC54  
AA

**ROOF AND WALL PANELS**

ROOF AND WALL PANELS INCLUDING COLOR COATED, ALUMINUM COATED AND GALVANIZED, PROVIDE EXCELLENT SERVICE UNDER WIDELY VARIED CONDITIONS. ALL UNLOADING AND ERECTION PERSONNEL SHOULD FULLY UNDERSTAND THAT THESE PANELS ARE QUALITY MERCHANDISE WHICH MERIT CAUTIOUS CARE IN HANDLING.

UNDER NO CIRCUMSTANCES SHOULD PANELS BE HANDLED ROUGHLY. PACKAGES OF SHEETS SHOULD BE LIFTED OFF THE TRUCK WITH EXTREME CARE TAKEN TO INSURE THAT NO DAMAGE OCCURS TO ENDS OF THE SHEETS OR TO SIDE RIBS. THE PACKAGES SHOULD BE STORED OFF THE GROUND SUFFICIENTLY HIGH ENOUGH TO ALLOW AIR CIRCULATION UNDERNEATH THE PACKAGES. THIS AVOIDS GROUND MOISTURE AND DETERS PEOPLE FROM WALKING ON THE PACKAGES. ONE END OF THE PACKAGE SHOULD ALWAYS BE ELEVATED ABOVE THE LOWER END TO ENCOURAGE DRAINAGE IN CASE OF RAIN.

ALL METAL PANELS ARE SUBJECT TO SOME DEGREE TO LOCALIZED DISCOLORATION OR STAIN WHEN WATER IS TRAPPED BETWEEN THEIR CLOSELY FITTED SURFACES. PANEL MANUFACTURER EXERCISES EXTREME CAUTION DURING FABRICATING AND SHIPPING OPERATIONS TO INSURE THAT ALL PANEL STOCK IS KEPT DRY. HOWEVER, DUE TO CLIMATIC CONDITIONS, WATER FORMED BY CONDENSATION OF HUMID AIR CAN BECOME TRAPPED BETWEEN STACKED SHEETS. WATER CAN ALSO BE TRAPPED BETWEEN THE STACKED SHEETS WHEN EXPOSED TO RAIN. THIS DISCOLORATION CAUSED BY TRAPPED MOISTURE IS OFTEN CALLED WET STORAGE STAIN.

THE STAIN IS USUALLY SUPERFICIAL AND HAS LITTLE EFFECT ON THE APPEARANCE OR SERVICE LIFE OF THE PANELS AS LONG AS IT IS NOT PERMITTED TO REMAIN ON THE PANELS. HOWEVER, MOISTURE IN CONTACT WITH THE SURFACE OF THE PANELS OVER AN EXTENDED PERIOD CAN SEVERELY ATTACK THEIR FINISH AND REDUCE THEIR EFFECTIVE SERVICE LIFE. THEREFORE, IT IS IMPERATIVE THAT ALL PANELS BE INSPECTED FOR MOISTURE UPON RECEIPT OF THE ORDER. IF MOISTURE IS PRESENT, DRY THE PANELS AT ONCE AND STORE IN A DRY, WARM PLACE, IF POSSIBLE.

WHEN HANDLING OR UNCRATING THE PANELS, LIFT, RATHER THAN SLIDE, THEM APART. BURNING EDGES MAY SCRATCH THE COATED SURFACES WHEN SHEETS ARE SLID OVER ONE ANOTHER. NEVER ALLOW PANELS TO BE WALKED ON WHILE ON THE GROUND.

ROUGH AND IMPROPER HANDLING OF PANELS IS INEXCUSABLE AND A PRIME EXAMPLE OF POOR JOB SUPERVISION.

CAUTION: PANELS ARE SLIPPERY. OIL OR WAX THAT HAS BEEN USED ON THE ROOF AND WALL PANELS FOR PROTECTION AGAINST WEATHER DAMAGE WILL MAKE THEM A VERY SLIPPERY WALKING SURFACE. WIPE DRY ANY OIL THAT HAS PUDDLED FROM BUNDLES STORED ON A SLOPE. DEW, FROST OR OTHER FORMS OF MOISTURE GREATLY INCREASE THE SLIPPERINESS OF THE PANELS.

**PANEL STORAGE NOTES**  
RC95  
AA


**\*\*NOT FOR CONSTRUCTION\*\***

CAROLINA DIESEL TRUCKS  
62 PROGRESS DRIVE  
FUQUAY VARINA, NC 27526  
THOMAS ANDREWS




DRAWING STATUS:  
**FOR APPROVAL ONLY**  
SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6  
JOB NUMBER: **A17B0157A** SHEET: **SED-008**

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					



BASE ANGLE DETAIL


BA01  
AB



SECTION AT BASE ANGLE

ARCHITECTURAL III, ARCHITECTURAL "V" RIB OR LONG SPAN III WALLS


BA02  
AB



OUTSIDE CLOSURE INSTALLATION AT EAVE

ARCHITECTURAL III WALLS

EA37  
AC




OUTSIDE CORNER FLASHING

ARCHITECTURAL III OR ARCHITECTURAL "V" RIB WALLS

FL08  
AC


- THINGS TO REMEMBER**
1. THINK SAFETY.
  2. CARE FOR PANELS IN ACCORDANCE WITH ERECTION GUIDE.
  3. ALIGN GIRT.
  4. PLUMB FIRST AND EVERY PANEL.
  5. CHECK COVERAGE ON EVERY PANEL.
  6. FOLLOW SCREW ATTACHMENT SEQUENCE: TRAILING TO LEADING. TOP TO BOTTOM.
  7. DO NOT EXCEED INSULATION THICKNESS (6" MAX.).
  8. DO NOT "RATCHET" OR OVERTIGHTEN WALL PANEL SCREWS. THIS WILL CAUSE "DIMPLING".
  9. USE THE RIB OF THE ARCHITECTURAL PANEL TO APPLY PRESSURE WHEN INSTALLING. (SEE EXAMPLE) DO NOT DISTORT PANEL FLATS.
  10. DO NOT USE ABRASIVE SAWS OR OTHER CUTTING TOOLS WHICH PRODUCE HOT METAL PARTICLES OR BURNED EDGES. THESE METHODS WILL DAMAGE THE PAINTED AND GALVALUME FINISH AND WILL VOID ANY WARRANTIES. USE DOUBLE CUT SHEARS, NIBBLERS OR OTHER CUTTING DEVICES WHICH DO NOT PRODUCE HOT METAL PARTICLES OR BURNED EDGES.



PANEL INSTALLATION NOTES


ARCHITECTURAL III WALL PANELS

GE04  
AC




DOWNSPOUT OUTLET DETAIL

GT01  
AA




DOWNSPOUT DETAIL

GT02  
AA



SECTION THROUGH DOWNSPOUT

GT03  
AA




RIVET LOCATIONS AT DOWNSPOUT LAP OR ELBOW

GT04  
AA

EAVE	DOWNSPOUTS	DOWNSPOUT CLIPS (FDC2)
10'	1 PC. FDS-14.4 & 1 PC. FDE2	2
12'	1 PC. FDS-14.4 & 1 PC. FDE2	2
14'	1 PC. FDS-14.4 & 1 PC. FDE2	3
16'	1 1/2 PC. FDS-14.4 & 1 PC. FDE2	3
18'	1 1/2 PC. FDS-14.4 & 1 PC. FDE2	4
20'	1 1/2 PC. FDS-14.4 & 1 PC. FDE2	4
22'	1 1/2 PC. FDS-14.4 & 1 PC. FDE2	4
24'	2 PC. FDS-14.4 & 1 PC. FDE2	5
26'	2 PC. FDS-14.4 & 1 PC. FDE2	5
28'	2 PC. FDS-14.4 & 1 PC. FDE2	6
30'	2 1/2 PC. FDS-14.4 & 1 PC. FDE2	6
32'	2 1/2 PC. FDS-14.4 & 1 PC. FDE2	6
34'	2 1/2 PC. FDS-14.4 & 1 PC. FDE2	7
36'	2 1/2 PC. FDS-14.4 & 1 PC. FDE2	7
38'	3 PC. FDS-14.4 & 1 PC. FDE2	8
40'	3 PC. FDS-14.4 & 1 PC. FDE2	8

DOWNSPOUT SCHEDULE

GT06  
AA



GUTTER LAP AND GUTTER ENDCAP FASTENER DETAIL

GT07  
AA

\*\*NOT FOR CONSTRUCTION\*\*

CAROLINA DIESEL TRUCKS  
62 PROGRESS DRIVE  
FUQUAY VARINA, NC 27526  
THOMAS ANDREWS



DRAWING STATUS:  
**FOR APPROVAL ONLY**









SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6

JOB NUMBER: **A17B0157A**

SHEET: **SED-009**

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					





- GENERAL NOTES:**
- CROWD OR STRETCH PANELS SLIGHTLY AS NECESSARY TO MAINTAIN 3'-0" COVERAGE PER PANEL.
  - PANELS MUST BE INSTALLED SQUARE WITH BUILDING FRAME.
  - PANEL SIDELAPS STITCHED 2'-0" ON CENTER WITH #14 WALL FASTENERS.
  - USE TOUCH UP PAINT WITH AN ARTIST TYPE BRUSH. DO NOT USE AEROSOL TYPE PAINT FOR TOUCH UP.
  - GIRTS ARE TO BE BLOCKED TO MAINTAIN VERTICAL GIRT FLANGES. FAILURE TO MAINTAIN VERTICAL GIRT FLANGES WILL CAUSE DIMPLING OF PANELS AT SCREW LOCATIONS.


**\*\*NOT FOR CONSTRUCTION\*\***

CAROLINA DIESEL TRUCKS  
62 PROGRESS DRIVE  
FUQUAY VARINA, NC 27526  
THOMAS ANDREWS

AMERICAN BUILDINGS  
A HUBCOR COMPANY  
MBMA  
ACCREDITED  
AC472

DRAWING STATUS:  
**FOR APPROVAL ONLY**  
SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6  
JOB NUMBER: **A17B0157A**  
SHEET: **SED-010**

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					




WALL FASTENERS		MISCELLANEOUS FASTENERS		SPECIAL CONDITION FASTENERS	
	<b>DESCRIPTION</b> #12 X 1 1/4 SELF DRILLING CARBON STEEL, HEX HEAD FASTENER WITHOUT WASHER MARK NO. #12X1 1/4 SDHH		<b>DESCRIPTION</b> 1/8 BLIND RIVET MARK NO. 1/8 RIVET		<b>DESCRIPTION</b> #12 X 1 1/4 TEK4 SELF DRILLING CARBON STEEL, HEX HEAD FASTENER WITHOUT WASHER MARK NO. #12X1 1/4 SDHHT4
<b>APPLICATION</b>	UNEXPOSED FASTENER CONNECTIONS, CLIPS AT OVERHEAD DOORS, WALK DOORS, ETC.	<b>APPLICATION</b>	(COLOR MATCHING) FLASHING LAPS AND FLASHING TO PANEL CONNECTIONS	<b>APPLICATION</b>	STEEL THICKNESS GREATER THAN 12 GA. AND UP TO AND INCLUDING 1/4". FIELD STRUCTURAL ATTACHMENTS
	<b>DESCRIPTION</b> #12 X 1 1/4 SELF DRILLING (COLOR MATCHING), HEX HEAD FASTENER WITHOUT WASHER MARK NO. #12X1 1/4 SDHH		<b>DESCRIPTION</b> 3/16 DIAMETER RIVET WITH WASHER MARK NO. SRV-1		<b>DESCRIPTION</b> #12 X 1 1/2 TEKS SELF DRILLING CARBON STEEL, HEX HEAD FASTENER WITHOUT WASHER MARK NO. #12X1 1/2 SDHHTS
<b>APPLICATION</b>	SHEET TO STRUCTURAL CONNECTIONS (BASE & GABLE ANGLE, GIRTS, EAVE STRUTS, ETC.)	<b>APPLICATION</b>	SIDELIGHT SIDELAP CONNECTIONS	<b>APPLICATION</b>	STEEL THICKNESS GREATER THAN 1/4" AND UP TO AND INCLUDING 1/2" FIELD STRUCTURAL ATTACHMENTS
	<b>DESCRIPTION</b> #14 X 3/4 SELF DRILLING (COLOR MATCHING), HEX HEAD FASTENER WITHOUT WASHER MARK NO. #14X3/4 SDHH		<b>DESCRIPTION</b> #10 X 1 1/2 SELF TAPPING CARBON STEEL, HEX HEAD FASTENER WITH WASHER MARK NO. #10X1 1/2 STHHW		<b>DESCRIPTION</b> #10 X 1 1/2 SELF TAPPING CARBON STEEL, HEX HEAD FASTENER WITH WASHER MARK NO. #10X1 1/2 STHHW
<b>APPLICATION</b>	PANEL SIDELAP CONNECTIONS, FLASHING TO PANEL CONNECTIONS AND OTHER SHEET TO SHEET CONNECTIONS	<b>APPLICATION</b>	PANELS TO WOOD STRUCTURE AT UNEXPOSED FASTENER CONNECTIONS (1/4" HEX HEAD SOCKET REQUIRED)	<b>APPLICATION</b>	PANELS TO WOOD STRUCTURE AT UNEXPOSED FASTENER CONNECTIONS (1/4" HEX HEAD SOCKET REQUIRED)


NOTE: ALL HEX HEAD SIZES SHALL REQUIRE A 5/16" HEX SOCKET UNLESS NOTED.

**BASIC PARTS AND PIECES**  
ARCHITECTURAL III WALL PANELS

WC61  
AC



**SAFETY PRECAUTION:**  
PANELS ARE SLIPPERY DUE TO  
OIL OR WAX APPLIED DURING  
MANUFACTURING FOR PROTECTION  
AGAINST WEATHER DAMAGE





ERECTION OF THE ARCHITECTURAL PANEL REQUIRES THAT THE PROPER DIRECTION OF ITS APPLICATION BE MADE. THE DESIGN OF THE PANEL INCORPORATES A BEARING LEG INTO ITS LEADING EDGE WHICH PROVIDES SUPPORT FOR PROPER NESTING OF THE OVERLAPPING RIB OF THE NEXT PANEL. THE INSTALLATION OF THE PANELS (SHOWN AT LEFT) PROCEEDS FROM LEFT TO RIGHT. HOWEVER, UNLESS FIELD CIRCUMSTANCES DICTATE OTHERWISE, INSTALLATION OF PANELS CAN PROCEED FROM EITHER LEFT TO RIGHT OR RIGHT TO LEFT AS LONG AS THE OVERLAPPING RIB IS LAPPED OVER THE BEARING RIB.

NOTE:  
ALUMINUM-COATED PANELS ARE SUBJECT TO STAINING DUE TO RESIDUE FROM BARE HANDS. ALUMINUM-COATED LINER PANELS THAT INCLUDE AN ACRYLIC FINISH DO HAVE ADDITIONAL PROTECTION BUT IT IS LIMITED AND DETERIORATES IN A RELATIVELY SHORT TIME MAKING THAT PANEL ALSO SUBJECT TO STAINING FROM BARE HANDS. IT IS RECOMMENDED THAT GLOVES BE USED FOR ALL HANDLING OF BOTH PRODUCTS AND THAT APPLICATION OF THESE PRODUCTS BE LIMITED TO AREAS NOT EXPOSED TO TOUCH.

**PANEL MARKING AND SIDELAP DETAILS**  
ARCHITECTURAL WALLS

WC63  
AC



PRIOR TO WALL SHEETING ALIGN WALL GIRTS AS SHOWN IN GE03/AA.  
INSULATION (BY OTHERS) IF REQUIRED, SHOULD BE INSTALLED PRIOR TO THE PANEL INSTALLATION AND CONTINUED IN THE SAME MANNER AS SHEETING PROGRESSES ALONG THE WALL.  
INSTALL THE FIRST WALL PANEL AT THE BUILDING CORNER AND ALIGN THE PANEL RIB WITH THE STRUCTURAL OR GIRT LINE AS SHOWN. IT IS EXTREMELY IMPORTANT THAT THE FIRST WALL PANEL BE INSTALLED PLUMB. USE A SPIRIT LEVEL OR TRANSIT ON EACH PANEL. IT IS RECOMMENDED THAT A SMALL WEDGE/SPACER BE PLACED UNDER THE PANEL AT THE BASE ANGLE. APPLY THE WALL PANEL OVER THE INSULATION AND INSTALL WALL FASTENERS AT ALL STRUCTURAL WALL MEMBERS BEGINNING WITH THE TOP MOST ATTACHMENT AND PROCEEDING DOWNWARD (SEE SUGGESTED NUMERICAL FASTENER SEQUENCE). REMOVE THE WEDGE/SPACER BEFORE ATTACHING PANEL AT BASE ANGLE. DO NOT ERECT PANEL BY ATTACHING AT BOTH ENDS WORKING TO THE MIDDLE OF THE PANEL. THIS PROCEDURE PROMOTES "OIL CANNING."  
INSTALL THE NEXT PANEL BY SIDELAPPING THE RIB WITH THE FIRST PANEL (AS SHOWN). CHECK FOR PLUMBNESS AND FASTEN THIS PANEL IN THE SAME MANNER AS THE FIRST PANEL. CONTINUE TO SHEET THE WALL USING THIS PROCEDURE. CUT PANELS AT DOORS, WINDOWS, LOUVERS AND OTHER WALL OPENINGS AS REQUIRED.  
SHEETING CAN USUALLY BE STARTED FROM EITHER END OF THE BUILDING AND CONTINUED EITHER IN THE DIRECTION OF LEFT TO RIGHT OR RIGHT TO LEFT AS SHOWN. HOWEVER BY APPLYING THE SHEETS TOWARD THE DIRECTION OF THE PREVAILING VIEW, THE OVERLAP LINE AT THE SIDELAP OF EVERY PANEL WILL BE LESS VISIBLE. THE SAME PRINCIPLE CAN BE APPLIED WHERE HEAVY PREVAILING WINDS OCCUR BY PLACING THE LAPPED EDGE ON THE LEEWARD SIDE (DOWNWARD SIDE) OF THE PANEL RIB.

**PRE-DRILLING OVERLAPPING RIB FOR STITCH SCREWS AS SHOWN WILL INSURE ALL SCREWS ARE ALIGNED. NOTE! TO AVOID DIMPLING DO NOT OVER TORQUE SCREWS.**

**WALL PANEL INSTALLATION**  
LONG SPAN III, ARCHITECTURAL III OR ARCHITECTURAL "V" RIB WALL PANELS

WC64  
AB

- ERECTION NOTES:**
- ALL AREAS WHERE MASTIC IS TO BE APPLIED SHOULD BE WIPED CLEAN WITH A MILD DETERGENT OR AN ALL PURPOSE CLEANER BEFORE MASTIC APPLICATION. THIS WILL INSURE A GOOD SEALING SURFACE AND IMPROVE WEATHER TIGHTNESS.
  - THE BLANKET INSULATION MANUFACTURER RECOMMENDS THAT DOUBLE SIDED TAPE BE USED TO SECURE THE INSULATION TO THE EAVE. THE METAL BUILDING SUPPLIER IS NOT RESPONSIBLE FOR THE INSTALLATION OR ATTACHMENT OF THE INSULATION. ADDITIONAL ATTACHMENTS (BY OTHERS) MAY BE REQUIRED.
  - ALL EXPOSED FASTENERS SHOULD PENETRATE THE SEALANT FOR THE MOST WEATHER TIGHT CONNECTION IN WALL AREAS WHERE APPLICABLE.
  - THE ARCHITECTURAL III PANEL IS DESIGNED FOR WALL APPLICATIONS ONLY AND SHOULD NEVER BE UTILIZED IN THE ROOF FOR PURPOSES OF PROVIDING A ROOF SYSTEM FOR BUILDINGS. THE INVERTED RIBS INCORPORATED INTO ITS DESIGN PRODUCE SMOOTH SHADOW LINES AND SEMI-CONCEALED FASTENERS. ALTHOUGH SHEETING CAN USUALLY BEGIN FROM EITHER END OF THE BUILDING, APPLICATION OF THIS PANEL IS DIRECTIONAL. PROPERLY INSTALLED, THE LAP EDGES OF THE ARCHITECTURAL III PANEL HAVE MINIMUM VISIBILITY.
  - WHEN FIELD CUTTING PANELS OR TRIM DO NOT USE ABRASIVE SAWS OR OTHER CUTTING METHODS WHICH PRODUCE HOT METAL PARTICLES OR BURN THE CUT EDGES. THESE METHODS WILL DAMAGE THE PAINTED AND GALVALUME FINISH AND VOID ANY WARRANTIES. USE DOUBLE CUT SHEARS, NIBBLERS OR OTHER CUTTING DEVICES WHICH DO NOT PRODUCE HOT METAL PARTICLES OR BURNED EDGES.

**ERECTION NOTES**  
ARCHITECTURAL III WALLS

WC91  
AC


**\*\*NOT FOR CONSTRUCTION\*\***

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					

CAROLINA DIESEL TRUCKS  
62 PROGRESS DRIVE  
FUQUAY VARINA, NC 27526  
THOMAS ANDREWS




DRAWING STATUS: <b>FOR APPROVAL ONLY</b>	
SOFTWARE VERSIONS	DESIGN: MSA 47.3 BIM: v20.6
JOB NUMBER: <b>A17B0157A</b>	SHEET: <b>SED-011</b>




ROOF PANEL	ROOF FASTENER (A) (1) PER CLIP	ROOF FASTENER (B) (1) PER CLIP	GUTTER CLIP (C)
LOC SEAM (LOC)	#14X1	#14X1	CGB
STANDING SEAM (S2P, S3P)	#14X1	#14X1	CGB


STANDARD GUTTER DETAIL EA01 AA




SECTION AT EAVE WITHOUT THERMAL BLOCKS EA04 SB




EAVE SUPPORT FLASHING ATTACHMENT EA10 AA




FASTENER INSTALLATION AT EAVE STRUT EA26 SA



STEP 1, SEE INSTRUCTION NO. 5 SEE NOTE



STEP 2, SEE INSTRUCTION NO. 5 SEE NOTE




STEP 3, SEE INSTRUCTION NO. 6 SEE NOTE

NOTE: SHADOW PANEL INSTALLATION SHALL VARY FROM THE DETAILS SHOWN. SEE THE SHADOW PANEL ERECTION DRAWINGS FOR FASTENER AND FLASHING DETAILS.

- INSTRUCTIONS
1. PRIOR TO SHEETING THE ROOF OR WALL, THE STRUCTURAL FRAMING MUST BE SQUARE AND PLUMB.
  2. BLOCK OR SUPPORT THE GIRTS AND EAVE STRUT TO PREVENT THE SUB FRAMING FROM SAGGING. BLOCKING MUST BE USED BETWEEN ENDWALL COLUMNS AND SIDEWALL COLUMNS AND SHOULD REMAIN IN PLACE UNTIL ALL WALL SHEETS ARE INSTALLED.
  3. PLACE THE EAVE SUPPORT FLASHING ON THE EAVE STRUT, LEAVING AN 1 1/2" OPENING BETWEEN THE OUTSIDE FACE OF THE EAVE STRUT AND THE INSIDE OF THE EAVE SUPPORT FLASHING. (A 2 X 4 WORKS WELL TO OBTAIN THIS SPACE). THE 1 1/2" OPENING WILL ACCOMMODATE THE ARCHITECTURAL III, ARCHITECTURAL "V" RIB OR LONG SPAN III WALL PANELS. AN OPENING OF 3 1/8" MUST BE MAINTAINED FOR SHADOW PANELS. SECURE THE EAVE SUPPORT FLASHING WITH #12 X 1 1/4" SELF DRILL FASTENERS LOCATED 1'-0" O.C. THESE ARE PERMANENT FASTENERS AND MUST BE INSTALLED. REMOVE ANY SPACERS USED FROM BEHIND THE EAVE SUPPORT FLASHING. INSTALL EAVE CLOSURE FLASHING (TFEC). EAVE CLOSURE IS HELD IN PLACE BY ROOF FASTENERS AT EAVE AND MUST BE INSTALLED WITH ROOF PANEL.
  4. INSTALL THE ROOF PANELS ACCORDING TO THE APPROPRIATE MANUAL AND/OR ERECTION DRAWINGS. REMEMBER THE PANEL OVERHANG DIMENSION IS USUALLY FROM THE FACE OF THE EAVE STRUT AND SHOULD BE MEASURED AS REQUIRED BY THE ERECTION DRAWINGS.
  5. WALL PANELS AND INSULATION MAY NOW BE INSTALLED. SECURE THE INSULATION TO THE FACE OF THE EAVE STRUT AND BASE ANGLE ACCORDING TO MANUFACTURERS RECOMMENDATIONS. SLIDE THE WALL PANEL BETWEEN THE EAVE STRUT AND EAVE CLOSURE FLASHING. PLUMB THE PANEL AND SECURE WITH THE WALL FASTENERS. FASTENERS MUST BE INSTALLED BELOW THE EAVE TRIM.
  6. INSTALL THE PANEL CLOSURES AND SECURE THE EAVE CLOSURE FLASHING TO THE WALL PANELS.

ROOF SHEETING PRIOR TO WALL SHEETING INSTRUCTIONS EA11 AA



LOW EAVE CAULK DETAIL EA27 SA

\*\*NOT FOR CONSTRUCTION\*\*

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					



CAROLINA DIESEL TRUCKS  
62 PROGRESS DRIVE  
FUQUAY VARINA, NC 27526  
THOMAS ANDREWS




DRAWING STATUS:  
**FOR APPROVAL ONLY**

SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6



JOB NUMBER: A17B0157A SHEET: SED-012



**MASTIC AND INSULATION APPLICATION AT EAVE**  
WITHOUT THERMAL SPACERS  
**EA28**  
**AB**



**AS YOU ARE SETTING EACH PANEL, INSTALL THE EAVE CLOSURE AS PER THE FOLLOWING INSTRUCTIONS**  
**STEP 1.** APPLY TAPE MASTIC TO TOP SIDE OF METAL CLOSURE. DO NOT REMOVE THE PAPER BACKING.  
**STEP 2.** POSITION CLOSURE UNDER MALE RIB AND INSTALL THE OUTSIDE FASTENER THROUGH THE PRE-PUNCHED HOLES.  
**STEP 3.** LIFT PANEL AND INSTALL THE INSIDE FASTENER. REMOVE THE PAPER FROM THE MASTIC AND PRESS THE PANEL FIRMLY IN PLACE.  
**STEP 4.** INSTALL EAVE FASTENERS IN THE FLAT OF THE PANEL IN THE CORRECT PATTERN. INSTALL A FASTENER THROUGH THE SIDE OF THE CLOSURE AS SHOWN ABOVE. APPLY CAULKING TO THE INSIDE FACE OF THE SEAM OVER THE CLOSURE.  
**STEP 5.** INSTALL THE NEXT PANEL RUN AND REPEAT STEPS 1 - 4. BE SURE TO INSTALL A ROOF FASTENER INTO THE SIDE OF THE NEXT PANEL AS SHOWN ABOVE.  
**INSIDE METAL CLOSURE INSTALLATION**  
STANDING SEAM 360  
**EA36**  
**TA**



**UNIVERSAL RAKE FLASHING**  
ALL ROOF PANELS  
**FL02**  
**AA**  
REF. DETAILS FL06AA, RC35AAA & RC35WAA

**ROOF FLASHING LAPS AND END TRANSITIONS EXPOSED TO ROOF CONDITIONS**

- ROOF FLASHING LAPS SHALL BE SEALED WITH 3/4 X 3/16 TAPE MASTIC (3/4 TM).
- FIELD CUT FEB-10.2 BACKUP FLASHING TO REINFORCE FLASHING ENDLAPS AND TERMINATIONS. INSTALL FEB AS SHOWN IN CONNECTION DETAILS (INBOARD) OF MASTIC, CLOSURES AND SUPPORT MEMBERS.

EXTRA CARE SHOULD BE TAKEN:  
DO NOT EXTEND FEB INTO THE MASTIC  
DO NOT EXTEND FEB BEYOND THE BUILDING ENVELOPE

FEB EXTENDED BEYOND THE BUILDING ENVELOPE INTERRUPTS THE GASKET CREATED BY THE CONTINUOUS MASTIC APPLICATION. ADJUST FIELD CUT FEB LENGTHS AS REQUIRED.

- STANDARD FASTENER SPACING AS SHOWN ON CONNECTION DETAILS WILL NEED TO VARY TO ENSURE A COMPLETE GASKET SEAL AT SOME LOCATIONS. INCLUDING (BUT NOT LIMITED TO) THE FOLLOWING.
  - DECREASE STITCH FASTENER SPACING FROM 6" O.C. TO 3" O.C. AT FLASHING LAPS AND TRANSITIONS.

EXAMPLES: RIDGE FLASHING TO RAKE CAP  
HIP FLASHING TO TRCZ AT EAVE  
RIDGE CAP TO PEAK BOX
- AT ALL EXPOSED ROOF FLASHINGS ENDLAPS INSTALL A STITCH FASTENER THROUGH THE UPPER FLASHING 2 1/2" FROM THE ENDLAP. (SEE DETAIL RC35WAA)

- VALLEY GUTTER LAPS SHALL BE SEALED WITH 2 X 3/16 TAPE MASTIC (2 TM) AND SHALL BE STITCHED WITH #14 ROOF FASTENERS 2" ON CENTER. QUANTITY WILL VARY WITH GUTTER SIZE.
- PREDRILL 1/4" Ø HOLES AT UPPER AND LOWER FLASHING FOR #14 FASTENERS. DO NOT PREDRILL FEB BACKUP FLASHING.
- FOR ROOF FLASHING LAPS NOT SHOWN IN DETAILS, THAT ARE EXPOSED TO ROOF CONDITIONS, USE THE FOLLOWING AS A GUIDE:
  - REINFORCE THE TOP SIDE OF ALL FLASHING END TRANSITIONS EXPOSED TO ROOF CONDITIONS USING #14 ROOF FASTENERS, 3" ON CENTER THROUGH MASTIC AND FIELD CUT FEB-10.2 (AS SPACE ALLOWS)


**FLASHING LAPS NOT SHOWN AND NOT EXPOSED TO ROOF CONDITIONS**

- FOR FLASHING LAPS NOT SHOWN AND NOT EXPOSED TO ROOF CONDITIONS, USE THE FOLLOWING AS A GUIDE:
  - USE 1/8 INCH BLIND RIVETS 3" ON CENTER.


**GENERAL REQUIREMENTS**

- ALL FLASHING LAPS SHALL BE TWO INCHES.


**FLASHING LAPS AND TRANSITIONS - GENERAL REQUIREMENTS**  
**FL06**  
**AA**




**STANDARD GUTTER**  
**FL09**  
**AA**



**EAVE CLOSURE FLASHING**  
STANDARD FLASHING LAP  
**FL14**  
**AA**



**SUGGESTED INSULATION ATTACHMENTS AT EAVE**  
**INO1**  
**AA**



**UNIVERSAL RAKE DETAIL**  
LOC SEAM AND STANDING SEAM ROOF / ARCHITECTURAL III, ARCHITECTURAL IV RIB OR LONG SPAN III WALLS  
**RA02**  
**AA**


**\*\*NOT FOR CONSTRUCTION\*\***

CAROLINA DIESEL TRUCKS  
62 PROGRESS DRIVE  
FUQUAY VARINA, NC 27526  
THOMAS ANDREWS




DRAWING STATUS:  
**FOR APPROVAL ONLY**  
SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6  
JOB NUMBER: **A17B0157A** SHEET: **SED-013**

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					




**UNIVERSAL RAKE CAP INSTALLATION**  
STANDING SEAM ROOF

RA03  
SA




**CORNER CAP BOX INSTALLATION**  
TYPICAL, ALL ROOF PANEL TYPES

RA04  
AA




**UNIVERSAL RAKE DETAIL**  
EXPANDED VIEW OF RAKE CONNECTION

RA05  
AA




**RIDGE FLASHING ENDCAP INSTALLATION**  
STANDING SEAM ROOF, LONG SPAN III & LOC SEAM

RA14  
AA




**UNIVERSAL RAKE ENDCAP INSTALLATION**  
LEFT HAND SHOWN

RA70  
AA




**DETAIL AT SIDELAP**  
STANDING SEAM 360

RC01  
TA



**DETAIL AT FINISHED SEAM**  
STANDING SEAM 360

RC05  
TA



**TYPICAL CLIP ATTACHMENT TO PURLIN**  
STANDING SEAM 360


RC17  
TA

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					


CAROLINA DIESEL TRUCKS  
62 PROGRESS DRIVE  
FUQUAY VARINA, NC 27526  
THOMAS ANDREWS




**\*\*NOT FOR CONSTRUCTION\*\***  
DRAWING STATUS:  
**FOR APPROVAL ONLY**  
SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6  
JOB NUMBER: A17B0157A SHEET: SED-014




**FIRST PANEL INSTALLATION (UNIVERSAL RAKE)**  
STANDING SEAM  
RC11  
TA




**PANEL CLIP INSTALLATION**  
STANDING SEAM 360 PANEL  
RC18  
TA




**RIDGE DETAIL**  
STANDING SEAM  
RC32  
SA




**EXPANSION RIDGE/HIP FLASHING LAP**  
ROOF  
RC33  
SA  
REF. DETAILS FLO6AA, RC35AAA & RC35WAA




**SEAM CLOSURE AND OUTSIDE METAL CLOSURE INSTALLATION**  
STANDING SEAM  
RC34  
SA




**SECTION THROUGH ROOF FLASHING LAP**  
RC35A  
AA



**RIDGE FLASHING OR HIGH SIDE EAVE ATTACHMENT**  
STANDING SEAM  
RC35  
SA



**EXPOSED ROOF FLASHING FASTENER REQUIREMENT**  
RC35W  
AA



**STANDING SEAM 360 PANEL SEAMING DETAIL**  
RC36  
TA

**\*\*NOT FOR CONSTRUCTION\*\***

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017


CAROLINA DIESEL TRUCKS  
62 PROGRESS DRIVE  
FUQUAY VARINA, NC 27526  
THOMAS ANDREWS

AMERICAN BUILDINGS  
A NUCOR COMPANY

DRAWING STATUS:  
**FOR APPROVAL ONLY**

SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6  
JOB NUMBER: SHEET:  
**A17B0157A SED-015**

MBMA  
MEMBER ACCREDITED AC-472




**RIDGE FLASHING ATTACHMENT**  
STANDING SEAM

RC37  
SA

REF. DETAILS RC34SA, RC33SA & RC35WAA

THE STANDING SEAM GAUGE BAR CAN BE USED IN ADDITION TO THE PANEL MODULARITY INSTALLATION DETAILS (RC71SA/RC72SA/RC73SA).




**STANDING SEAM PANEL GAUGE LOCATIONS**

RC42  
SA

STANDING SEAM 360 PANEL ROOF SYSTEM HAS UNIQUE SIDELAP SEAMS WHICH ENGAGE THE ADJACENT PANEL TO FORM A TIGHT PENETRATION FREE CONNECTION. THE PANEL IS ATTACHED TO THE SUPPORT FRAMING BY A SPECIAL STANDING SEAM 360 PANEL CLIP WHICH IS INTERLOCKED WITH THE SEAM AND FASTENED TO THE PURLIN WITH SELF-DRILLING FASTENERS. THE PROPER INSTALLATION OF THE PANEL WILL REQUIRE TOOLS SPECIALLY DESIGNED FOR THIS PURPOSE.


ILLUSTRATED BELOW ARE THE TOOLS USED ON A STANDING SEAM 360 ROOF PANEL SYSTEM.



\* AVAILABLE FOR PURCHASE OR RENTAL THROUGH:  
D.I. ROOF SEAMERS  
915 HIGHWAY 45  
CORINTH, MS 38834  
888.343.0456  
WWW.EAGLESEAMERS.COM

**STANDING SEAM 360 ERECTION TOOLS**

RC62  
TA



**HAND/EAVE SEAMING PROCESS**

THE METAL BUILDING SUPPLIER FURNISHES THE STANDING SEAM 360 ROOF SYSTEM IN NON-HANDED PANELS. GABLE, SINGLE SLOPE OR UNSYMMETRICAL BUILDINGS CAN BE SHEETED SIMULTANEOUSLY FROM EITHER END OF THE BUILDING.

THE SEAMING PROCESS INVOLVES TWO DIFFERENT TOOLS, THE STANDING SEAM 360 ELECTRIC ROOF SEAMER AND THE HAND/EAVE SEAMER. THE STANDING SEAM 360 HAND/EAVE SEAMER IS A TWO STAGE TOOL USED AT THE STARTING END OF EACH PANEL (EAVE OR RIDGE) PRIOR TO SEAMING WITH THE ELECTRIC SEAMER.

- IN THE FIRST STAGE PLACE PHASE 1 SIDE OF THE SEAMER ONTO THE OPEN SIDE OF THE SEAM AT THE END OF THE PANEL AND ENGAGE THE TOOL TO A FULLY CLOSED POSITION. REMOVE THE SEAMER AND MOVE UP THE SLOPE THE WIDTH OF THE SEAMER JAWS (APPROXIMATELY FOUR INCHES) AND ENGAGE THE TOOL TO A FULLY CLOSED POSITION. THIS SHOULD COMPLETE THE FIRST STAGE OF HAND/EAVE SEAMING.
- REMOVE THE SEAMER AND REVERSE THE DIRECTION SO THAT PHASE 2 SIDE OF THE SEAMER IS PRESSED ONTO THE OPEN SIDE OF THE SEAM. STARTING AT THE PANEL END ENGAGE THE TOOL TO A FULLY CLOSED POSITION TO COMPLETE THE SEAM. DO THIS STEP ONLY ONCE FOR THE SEAM IS NOW READY FOR THE ELECTRIC SEAMER.

THE STANDING SEAM 360 ELECTRIC ROOF SEAMER IS A SINGLE DIRECTION MACHINE USED FOR SEAMING THE PANELS TOGETHER AT THE SIDELAPS. GABLE BUILDINGS WILL REQUIRE THE SEAMER TO START AT THE EAVE ON ONE SIDE OF THE BUILDING AND TRAVEL UP THE SLOPE TO THE RIDGE AND THEN TRAVEL DOWN THE SLOPE TO THE EAVE ON THE OPPOSITE SIDE OF THE BUILDING. SINGLE SLOPE BUILDINGS WILL REQUIRE THE SEAMER TO START AT EITHER THE HIGH OR LOW SIDE OF THE BUILDING DEPENDING UPON THE SHEETING DIRECTION.


- TO START THE SEAMING PROCESS, PLACE THE ELECTRIC SEAMER IN POSITION WITH THE THREE HANDLES IN THE UNLOCKED POSITIONS. THE SEAM ROLLERS SHOULD BE ON THE OPEN SIDE OF THE SEAM AND THE BACK OF THE SEAMER SHOULD BE ALIGNED WITH THE END OF PANEL (THE HAND/EAVE SEAMING OPERATION AT THE STARTING END OF THE PANEL SHOULD HAVE ALREADY BEEN COMPLETED). LOCK THE THREE HANDLES INTO POSITION AND START THE SEAMER. ALLOW THE SEAMER TO COMPLETE ITS RUN TO THE OPPOSITE END OF THE PANEL. SHOULD FURTHER SEAMING BE REQUIRED AFTER COMPLETING THE RUN WITH THE ELECTRICAL SEAMER, FINISH WITH THE TWO STAGE HAND/EAVE SEAMING PROCESS. DO NOT RUN THE ELECTRIC SEAMER THROUGH ANY SECTION OF THE PANEL THAT HAS BEEN HAND/EAVE SEAMED.

THE SEAMER SHOULD NEVER BE ALLOWED TO BECOME A FALLING HAZARD TO ANYONE BENEATH THE ROOF. ALL SAFETY PRECAUTIONS AND OSHA SAFETY REGULATIONS SHOULD ALWAYS BE FOLLOWED FOR MAXIMUM WORKER SAFETY.

**PANEL SEAMING PROCESS**  
STANDING SEAM 360

RC38  
TA

NOTE:  
PANELS ARE DIMPLED AT BOTH ENDS. DIMPLES ARE USED FOR FASTENER LOCATIONS AT THE PANEL ENDLAPS ONLY.




NOTE:  
ALUMINUM-COATED PANELS ARE SUBJECT TO STAINING DUE TO RESIDUE FROM BARE HANDS. ALUMINUM-COATED LINER PANELS THAT INCLUDE AN ACRYLIC FINISH DO HAVE ADDITIONAL PROTECTION. BUT IT IS LIMITED AND DETERIORATES IN A RELATIVELY SHORT TIME MAKING THAT PANEL ALSO SUBJECT TO STAINING FROM BARE HANDS. IT IS RECOMMENDED THAT GLOVES BE USED FOR ALL HANDLING OF BOTH PRODUCTS AND THAT APPLICATION OF THESE PRODUCTS BE LIMITED TO AREAS NOT EXPOSED TO TOUCH.

**PANEL MARKING AND NOTCHING**  
STANDING SEAM 360

RC63  
TA

THE STANDING SEAM ROOF PANELS HAVE BEEN DESIGNED SO THAT BOTH SIDES OF A GABLED BUILDING CAN BE SHEETED SIMULTANEOUSLY.




PANEL STAGGER LAYOUT - TO ASSURE A WATER TIGHT CONNECTION. STANDING SEAM ENDLAPS ARE DESIGNED TO BE STAGGERED FROM ONE PANEL RUN TO THE NEXT. SEE ERECTION DRAWING FOR PROPER ENDLAP LOCATIONS.

**DIRECTION OF ROOF PANEL ERECTION**  
STANDING SEAM 360

RC64  
TA

THE STANDING SEAM GAUGE BAR CAN BE USED IN ADDITION TO THE PANEL MODULARITY INSTALLATION DETAILS (RC71SA/RC72SA/RC73SA).




SAFETY PRECAUTION:  
WIPE OIL AND OTHER SLIPPERY SUBSTANCES FROM ROOF PANELS. DO NOT STEP ON RIB OF PANEL OR WITHIN 6 FEET OF UNSECURED PANEL END. USE OSHA APPROVED TIE OFFS, NETTINGS OR RAILS WHEN WORKING ON ROOF.

PANEL COVERAGE GAUGES SUCH AS SHOWN ABOVE WILL HELP TO MAINTAIN CORRECT COVERAGE. PLACE ONE AT EACH END OF THE PANEL. GAUGE EACH PURLIN RUN AND ABOVE OR BELOW THE ENDLAP.  
A STRING LINE SET AT THE NEXT RAFTER IS RECOMMENDED FOR TAKING MEASUREMENTS BACK TO THE PANELS TO ENSURE THAT THEY ARE RUNNING STRAIGHT AND SQUARE.

**PANEL GAUGING**  
STANDING SEAM PANEL

RC41  
SA

THE STANDING SEAM GAUGE BAR CAN BE USED IN ADDITION TO THE PANEL MODULARITY INSTALLATION DETAILS (RC71SA/RC72SA/RC73SA).



**STANDING SEAM GAUGE BAR ASSEMBLY DETAIL**

RC43  
SA

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					

CAROLINA DIESEL TRUCKS  
62 PROGRESS DRIVE  
FUQUAY VARINA, NC 27526  
THOMAS ANDREWS


**\*\*NOT FOR CONSTRUCTION\*\***

AMERICAN BUILDINGS  
A HUCOR COMPANY

DRAWING STATUS:  
**FOR APPROVAL ONLY**

SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6  
JOB NUMBER: A17B0157A SHEET: SED-016

MBMA ACCREDITED




Shown above is the Hand Seamer tool. This tool is used at different locations prior to electrically seaming the roof.

PHASE 1 - 90° BEND  
PHASE 2 - 360° BEND

REFER TO THE OWNER'S MANUAL INCLUDED WITH THE STANDING SEAM PANEL HAND SEAMER / SEAM STARTER FOR SAFE AND PRACTICAL SEAMING INSTRUCTIONS

STANDING SEAM 360 PANEL HAND SEAMER TOOL RC68A TA



The standing seam installation clamp will help keep roof runs on module and clamp will remain out of the work area when in use. This will not need to be used on every panel run but only when required to help modify sheets to stay within tolerance. They are also adjustable to allow for broader ranges of corrections.

By slipping the flat tab (located below the hinge point of the clamp) under the seam of the roof panels and then squeezing the handles closed, the two base angles grip the lower trapezoid of the panels and shorten the distance between the vertical legs of the roof sheets. When used at end laps and ridge/high eave locations of the roof, you can manipulate the growth of the sheets caused by the increasing amount of insulation being laid under roof systems.

STANDING SEAM INSTALLATION CLAMP RC70 SA  
STANDING SEAM II/360

First Panel Installation - (RC10SA) then (RC12SA at Custom Rake/RC11SA at Universal Rake)


- 1) Install panel/panels from eave to ridge/high eave, straight and square with the building. Be sure to overhang the panel at eave the correct amount. Install all panel clips (RC67EA/RC18TA). If there are endlaps, complete the endlaps (RC06SA/RC07SA).
- 2) Determine where the center line of the panel rib will fall, based upon the width of the starter panel. Mark a line on the vertical part of the eave flashing at this point.
- 3) From the first vertical mark on the eave flashing, lay out the entire length of the building, putting a mark on the vertical leg of the flashing at 1'-0" O.C.. These marks will be used as the roof progresses to position the panel and to position the SSMC-I closure.
- 4) Mark the center line of all SSMC-I closures with a vertical mark. Install the first closure (EA36EA/EA36TA), with the mark on the eave flashing and the mark on the closure aligned.
- 5) Installed eave fasteners will pass through the panel, lobe mastic, eave flashing and TFSE(T). Fastener locations upslope from dimples at the end of the panel.
- 6) After the clips are installed on this first panel run, measure from the center of the fasteners which hold the panel clips to the purlins, at each panel endlap location and at the ridge/high eave purlin, and put a mark on the top of the purlin at 2'-0" O.C.. Then put in one #12X1 1/4" clip fastener or drill a small hole at each 2'-0" mark. These holes or fasteners will be used as the roof progresses to position the panel clips in these locations at a perfect 2'-0" coverage, thus maintaining module and panel straightness/alignment.

PANEL MODULARITY AT CONNECTING PANEL RC71 SA  
STANDING SEAM II/360


All Subsequent Panel Runs

- 7) Caulk the first 6" of the top of male rib of the panel (RC11\_A).
- 8) Lay panel in position next to previous panel.
- 9) Position a small framing square at the 1'-0" mark on the eave. Align the center of the (middle minor rib) of the panel with the edge of the square positioned at the 1'-0" mark, if this is a Standing Seam 360 panel, hook the female leg to the male leg of the preceding panel the entire length (RC01TA), then align center of panel with edge of square.
- 10) Holding the middle of the rib at the edge of the square, push the panel uphill or downhill to get the proper overhang amount (See Erection Drawings). This can be read right off the markings on the square. Note, the dimension shown is typically from face of eave strut. Subtract wall panel depth for correct overhang from eave flashing.
- 11) Once in position, install one fastener through the flat of the panel at the center of the flat.
- 12) If Standing Seam II panel, the panel can now be seamed at this time (RC36EA).
- 13) Install fasteners in panel flat from the center to completed seam and into the SSMC-I closure.
- 14) Using another SSMC-I, install closure by aligning the mark in the center of the closure, with the next 1'-0" mark on the eave trim (EA36EA/EA36TA).
- 15) Install remainder of fasteners in panel flat towards newly installed SSMC-I, then install fastener from trapezoid into eave.
- 16) Install panel clip at endlap or ridge/high eave location by either removing fastener or finding the pre-drilled hole at 2'-0" increments and then installing the fastener through the panel clip base into the pre-drilled hole. Then add the second fastener to the clip.
- 17) Panel should now be straight and on module, and the balance of the clips can be installed.
- 18) If there is a panel endlap, you would next lay the overlapping panel, make up the endlap utilizing the suggested clamps (RC66EA/RC66TA), and put on the panel clip at the next uphill pre-drilled location. Then fill in the balance of the clips (RC57EA/RC18TA).
- 19) Depending on insulation thickness and other job site variables, you may choose to lay out one or more additional purlins at panel midspans on these 2'-0" centers for proper clip/panel modularity.

PANEL MODULARITY-ALL SUBSEQUENT PANEL RUNS RC72 SA  
STANDING SEAM II/360




STEP 1



STEP 2

SAFETY PRECAUTION: DO NOT STEP ON RIB OF PANEL. ALWAYS STEP ON FLAT SURFACE.




Panel coverage gauges such as shown above will help to maintain correct coverage. Place one at each end of the panel, one at midspan, and if applicable, one above or below the lap.

STANDING SEAM 360 GAUGE RC77 TA


ERECTION NOTES:

1. ALL AREAS WHERE MASTIC IS TO BE APPLIED SHOULD BE WIPED CLEAN WITH A MILD DETERGENT OR AN ALL PURPOSE CLEANER BEFORE MASTIC APPLICATION. THIS WILL ENSURE A GOOD SEALING SURFACE AND IMPROVE WEATHER TIGHTNESS.
2. THE BLANKET INSULATION MANUFACTURER RECOMMENDS THAT DOUBLE SIDED TAPE BE USED TO SECURE THE INSULATION TO THE EAVE. THE METAL BUILDING SUPPLIER IS NOT RESPONSIBLE FOR THE INSTALLATION OR ATTACHMENT OF THE INSULATION.
3. DO NOT USE THE DIMPLES IN THE END OF THE PANELS TO LOCATE FASTENERS AT THE EAVE. DIMPLES ARE FOR THE FASTENERS AT THE PANEL ENDLAPS ONLY.
4. ALL EXPOSED FASTENERS SHOULD PENETRATE THE SEALANT FOR THE MOST WEATHER TIGHT CONNECTION.
5. WHEN FIELD CUTTING PANELS OR TRIM DO NOT USE ABRASIVE SAWS OR OTHER CUTTING METHODS WHICH PRODUCE HOT METAL PARTICLES OR BURN THE CUT EDGES. THESE METHODS WILL DAMAGE THE PAINTED AND GALVALUME FINISH AND VOID ANY WARRANTIES. USE DOUBLE CUT SHEARS, NIBBLERS OR OTHER CUTTING DEVICES WHICH DO NOT PRODUCE HOT METAL PARTICLES OR BURNED EDGES.

ERECTION NOTES - STANDING SEAM RC91 SA



STEP 3



STEP 4

PANEL MODULARITY INSTALLATION RC73 SA  
STANDING SEAM II/360

\*\*NOT FOR CONSTRUCTION\*\*


CAROLINA DIESEL TRUCKS  
62 PROGRESS DRIVE  
FUQUAY VARINA, NC 27526  
THOMAS ANDREWS



DRAWING STATUS:  
**FOR APPROVAL ONLY**  
SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6  
JOB NUMBER: A17B0157A  
SHEET: SED-017


NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					






JAMB TO GIRT CONNECTION

OF01  
AA




JAMB BASE CONNECTION

OF11  
AA




GIRT TO JAMB CONNECTION

OF16  
AA




HEADER TO JAMB CONNECTION

OF21  
AA



TYPICAL ANCHOR ROD LAYOUT



FRAMED OPENING ANCHOR ROD DETAIL

OF61  
AA

GENERAL NOTES FOR FIELD LOCATED FRAMED OPENINGS :


- OVERHEAD DOORS ARE FIELD LOCATED. CUT STANDARD PANELS AND GIRTS AS REQUIRED.
- MAXIMUM HEIGHT OF DOOR IS 2'-0" LESS THAN EAVE HEIGHT.
- ALL STRUCTURAL CONNECTIONS TO BE MADE AS SHOWN ON APPROPRIATE DETAILS.
- JAMBS MUST BE LOCATED A MINIMUM OF 1'-0" FROM CENTER LINE OF COLUMNS.

GENERAL NOTES FOR SHOP LOCATED FRAMED OPENINGS :

- OVERHEAD DOORS ARE SHOP LOCATED. SOME PANELS MAY REQUIRE FIELD CUTTING.
- ALL STRUCTURAL CONNECTIONS TO BE MADE AS SHOWN ON APPROPRIATE DETAILS.

FIELD AND SHOP LOCATED FRAMED OPENING NOTES


OF91  
AA



FRAMED OPENING KEY

JAMB TO GIRT CONDITION


OFOA  
AA



SECTION AT HEADER AND JAMB TRIM


ARCHITECTURAL III, ARCHITECTURAL "V" RIB AND LONG SPAN III WALLS

OT01  
AA



SECTION AT HEADER AND COVER FLASHING


OT21  
AB



SECTION AT FRAMED OPENING JAMB

ARCHITECTURAL III PANEL WALLS

OT26  
AC



NOTE: FIELD SLIT PANELS AND SLIDE HEAD OR SILL FLASHING BEHIND PANELS

SHEETING AND FLASHING ELEVATION

ARCHITECTURAL III, ARCHITECTURAL "V" RIB, LONG SPAN III AND MULTI-RIB PANEL WALLS

OTOA  
AB

\*\*NOT FOR CONSTRUCTION\*\*

CAROLINA DIESEL TRUCKS  
62 PROGRESS DRIVE  
FUQUAY VARINA, NC 27526  
THOMAS ANDREWS




DRAWING STATUS:  
**FOR APPROVAL ONLY**

SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6


JOB NUMBER: A17B0157A

SHEET: SED-018


NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					




HANGER DETAIL AT PURLINS SH01 AA




HANGER DETAIL AT PURLINS ROD HANGER WITHOUT REINFORCING ANGLE SH01A AA




HANGER DETAIL AT PURLINS ROD HANGER WITH REINFORCING ANGLE SH01B AA




HANGER DETAIL AT PURLINS PURLIN CLAMP SH02 AA




HANGER DETAIL AT PURLINS PURLIN CLAMP WITHOUT REINFORCING ANGLE SH02A AA




HANGER DETAIL AT PURLINS PURLIN CLAMP WITH REINFORCING ANGLE SH02B AA




HANGER DETAIL BETWEEN PURLINS SH03 AA




SH06 AA



HANGER DETAIL AT PURLINS ROOF SLOPES LESS THAN OR EQUAL TO 1:12 SH11 AA



HANGER DETAIL AT PURLINS SIDEWINDER PIPE HANGER FOR SLOPES LESS THAN OR EQUAL TO 1:12 SH11A AA



HANGER DETAIL AT PURLINS ROOF SLOPES LESS THAN 8:12 SH12 AA

\*\*NOT FOR CONSTRUCTION\*\*

CAROLINA DIESEL TRUCKS  
62 PROGRESS DRIVE  
FUQUAY VARINA, NC 27526  
THOMAS ANDREWS




DRAWING STATUS:  
**FOR APPROVAL ONLY**

SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6


JOB NUMBER: A17B0157A SHEET: SED-019

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					



HANGER DETAIL AT PURLINS  
SWIVEL PIPE HANGER FOR SLOPES LESS THAN 8:12

SH12A
AA



HANGER DETAIL AT PURLINS  
ROOF SLOPES GREATER THAN OR EQUAL TO 8:12

SH13
AA

CADDY PURLIN CLAMP MODEL 315 IS AVAILABLE VIA THE MANUFACTURER'S WEBSITE:

[www.erico.com](http://www.erico.com)

SAMMY X-PRESS SWIVEL PIPE HANGER MODEL SXP 35  
SAMMY X-PRESS SIDEWINDER PIPE HANGER MODEL SWXP 35  
AND INSTALLATION TOOLS ARE AVAILABLE VIA THE MANUFACTURER'S WEB SITE:

[www.sammysuperscrew.com/sammyxpress.htm](http://www.sammysuperscrew.com/sammyxpress.htm)

WEBSITES FOR PREAPPROVED HANGER DEVICES

SH14
AA

## WARNING

THE HANGER CAPACITIES SHOWN ON THE AMERICAN BUILDINGS COMPANY DETAILS REPRESENT THE MAXIMUM ALLOWABLE SINGLE HANGING LOAD THAT A TYPICAL PURLIN CAN SAFELY SUPPORT UNDER THE BEST OF CIRCUMSTANCES USING THE PARTICULAR HANGER DEVICE SHOWN IN THE DETAIL.

MANY FACTORS BEYOND THE CONTROL OF THE METAL BUILDING SUPPLIER AFFECT THE ABILITY OF A PURLIN TO SAFELY SUPPORT HANGING LOADS COMBINED WITH OTHER REQUIRED ROOF LOADS. DUE TO THE VARIABLES INVOLVED IN HANGING LOADS AND THEIR ATTACHMENTS TO THE PURLINS, THE METAL BUILDING SUPPLIER CANNOT ASSURE THAT THE PURLINS FOR A PARTICULAR BUILDING PROJECT CAN SAFELY SUPPORT THE MAXIMUM ALLOWABLE HANGING LOADS IN COMBINATION WITH OTHER ROOF LOADS.

IT IS THE RESPONSIBILITY OF THE HANGER SYSTEM INSTALLER TO COORDINATE WITH THE ENGINEER OF RECORD FOR THE OVERALL PROJECT TO ENSURE A SAFE HANGING LOAD INSTALLATION. THE METAL BUILDING ENGINEER IS NOT THE ENGINEER OF RECORD FOR THE OVERALL PROJECT. WITHOUT SPECIFIC CERTIFICATION FOR INDIVIDUAL HANGING LOADS, THE NET EFFECTS OF APPLIED HANGER LOADS INSTALLED ON A PARTICULAR PURLIN SHALL NOT EXCEED THE NET EFFECTS OF THE CERTIFIED UNIFORMLY APPLIED DESIGN COLLATERAL LOAD. SEE SHEET ABC-1.

HANGER CAPACITIES WARNING

SH16
AA

NOTE:  
OTHER METHODS OF ATTACHING HANGING LOADS, NOT DEPICTED ON DETAILS SH01, SH02, SH03, SH11, SH12, AND SH13, ARE GENERALLY PERMITTED.  
HOWEVER, THE HANGER LOAD MUST NOT EXCEED 50 POUNDS PER HANGER LOCATION (WITHOUT SPECIFIC PRIOR APPROVAL FROM A QUALIFIED DESIGN PROFESSIONAL FOR A PARTICULAR LOAD).

GENERAL HANGER NOTES

SH15
AA

**\*\*NOT FOR CONSTRUCTION\*\***

NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE	NO	RELEASE / REVISION	DWN: / CKD:	ENGR	DATE
2	REVISED APPROVALS	HRH /	JV	08/03/2017	1	REVISED APPROVAL	RCC / RCC	JV	06/14/2017
0	FOR APPROVAL ONLY	RCC / RCC	JV	06/12/2017					

CAROLINA DIESEL TRUCKS  
62 PROGRESS DRIVE  
FUQUAY VARINA, NC 27526  
THOMAS ANDREWS



DRAWING STATUS:  
**FOR APPROVAL ONLY**

SOFTWARE VERSIONS DESIGN: MSA 47.3 BIM: v20.6

JOB NUMBER: **A17B0157A** SHEET: **SED-020**