



25

## Application for Plan Review

Application # 18-50043021

Date Received: 1/2/18 Received By: dylanism

Name of Project: Crepe Myrtle Animal Hospital

Physical Address of Project: 8632 South NC 55 HWY  
Angier, NC 27501

Plans Submitted By: Bradley Built, Inc

Project Phone: (919) - 639 - 2073

Contact Person/Address: Bo Bridgers  
466 Stencil Rd  
Angier, NC 27501

Contact Email: bo@bradleybuiltinc.com

Contact Phone: C (919) - 669 - 9611

Contractor's Name/Info: Bradley Built, Inc  
466 Stencil Rd  
Angier, NC 27501

Contractor's Phone: (919) - 639 - 2073

- Plans that are submitted will be reviewed as quickly as possible with an average time of review between 7-10 working days.
- Status checks may be conducted on plan reviews by visiting the website <http://hteweb.harnett.org/Click2GovBP/Index.jsp> or by calling the Harnett County Central Permitting Office (910-893-7525, Option #2), or the Harnett County Fire Marshal's Office (910-893-7580).
- Approved plans must be picked up from the Central Permitting Office and all fees paid before any required inspections can be conducted.



## Plan Review, Inspection, and Permit Fees

Application Number : 18-50043021

\$200.00	<input type="checkbox"/>	Explosive Material (90 Days)	\$	-
\$100.00	<input type="checkbox"/>	Explosive Materials (72 Hours)	\$	-
\$100.00	<input type="checkbox"/>	Fireworks Public Display	\$	-
\$50.00	<input checked="" type="checkbox"/>	Final Inspection	\$	50.00
\$35.00 + \$2.00 per device	<input type="checkbox"/>	Fire Alarm Testing	\$	-
\$35.00 + \$2.00 per nozzle	<input type="checkbox"/>	Fixed Fire Suppression	\$	-
\$75.00	<input type="checkbox"/>	Insecticide Fog/Fumigation	\$	-
\$100.00	<input type="checkbox"/>	Pipe Test/UST/AGST	\$	-
\$50.00	<input checked="" type="checkbox"/>	Plans up to 5000 sq ft	\$	50.00
\$100.00	<input type="checkbox"/>	Plans 5001 sq ft to 10,000 sq ft	\$	-
\$150.00	<input type="checkbox"/>	Plans 10,001 sq ft to 25,000 sq ft	\$	-
\$250.00	<input type="checkbox"/>	Plans 25,001 sq ft and over	\$	-
\$35.00 + 2.00 per head	<input type="checkbox"/>	Sprinkler Certification Test	\$	-
\$50.00	<input type="checkbox"/>	Standpipe Testing	\$	-
\$50.00	<input type="checkbox"/>	Special Assembly (ie. amusement buildings, carnivals, fairs)	\$	-
\$75.00	<input type="checkbox"/>	Tents/Canopies/Air Supported Structure	\$	-
\$100.00	<input type="checkbox"/>	Tank Installation (charge for each tank)	\$	-
\$100.00	<input type="checkbox"/>	Tank Removal (charge for each tank)	\$	-
		Total Devices/Heads	\$	-
		<b>Total Cost</b>	<b>\$</b>	<b>100.00</b>

Code Enforcement Official

Rodney Daniels

1/9/2018



# Plan Review, Inspection, and Permit Fees

Application Number	Description	Fee
	Explosive Material (30 Days)	\$200.00
	Explosive Materials (72 Hours)	\$100.00
	Fireworks Public Display	\$100.00
	Final Inspection	\$50.00
	Fire Alarm Testing	\$35.00 + \$2.00 per device
	Fixed Fire Suppression	\$35.00 + \$1.00 per nozzle
	Insecticide Fog/Dispersion	\$75.00
	Pipe Test/UST/AGST	\$100.00
	Plans up to 2000 sq ft	\$250.00
	Plans 2001 sq ft to 10,000 sq ft	\$300.00
	Plans 10,001 sq ft to 25,000 sq ft	\$350.00
	Plans 25,001 sq ft and over	\$500.00
	Sprinkler Certification Test	\$35.00 + 2.00 per head
	Standpipe Testing	\$50.00
	Special Assembly	\$50.00
	(el. amusement devices, carnivals, fairs)	
	Tents/Canopies/Air supported structures	\$75.00
	Tank Installation (charge for each tank)	\$100.00
	Tank Removal (charge for each tank)	\$200.00
	Total Devices/Heads	
	<b>Total Cost</b>	<b>100.00</b>

Code Enforcement Official: Rodney Daniels      1/15/2018



**Fire Marshal Division**

January 9, 2018

Bradley Built, LLC  
466 Stancil Road  
Angier, NC 27501

**RE: Crepe Myrtle Animal Hospital  
8632 South NC 55 Hwy  
Angier, NC 27501**


**Application Number – 18-50043201**

Mr. Bridgers,

Thank you for submitting plans for the animal hospital. The plans have been reviewed by a qualified code enforcement official for compliance with the North Carolina Fire Prevention code and all other fire protection regulations. The following are items that will need to be addressed before a final inspection of this project can be completed. The items are listed and described below.

- **503 Fire Department Access**
  - The fire department access shall extend to within 150 feet of all portions of the facility.
  - The fire department access road shall be of an unobstructed width of not less than 20 feet and shall have an unobstructed vertical clearance of not less the 13 feet 6 inches.
  
- **505.1 Physical Address**
  - The physical address of the building shall be posted in a conspicuous place so that it can be seen on approach from the road, access road, and/or parking lot.
  - The numbers used to make up the physical address shall be at least 5 inches in height.
  
- **906.1 Fire Extinguishers**
  - Fire extinguishers shall be placed in approved locations and may be field verified on final inspection. The fire extinguishers provided shall have a minimum rating of 2A 10 B: C.





- Fire extinguisher shall be installed not to exceed 75' distance of travel.
  
- **1006.1 / 1006.2 Emergency Illumination**
  - Emergency illumination is required to meet minimum foot candle illumination.
  
- **1011 Exit Signs**
  - Exit signs shall be installed at all required exits. Exit signs shall meet all provisions of chapter 10.
  
- **506.1 Knox Box**
  - A Knox box is required to be installed on the building.
  - An application /order form has been attached to the review comments.
    - <https://www.knoxbox.com/commercial-knox-boxes/>
  
- **Notes**
  - Please contact the Fire marshal's office to schedule fire final inspection when work is complete, 910-893-0743

Please review the plans and adhere to any notes and alterations that were made in addition to the original designed plans. These remarks are for the plans that were submitted and its original intent. If you have any questions please do not hesitate to contact me. We look forward to working with you during the construction period.

Sincerely,

Rodney Daniels  
Chief Deputy Fire Marshal