



25

Application for Plan Review

Application # 18 - 50043351

Date Received: 2/21/18 Received By: Both

Name of Project: Anderson Creek Landfill

Physical Address of Project: 1086 Poplar Drive
Spring Lake, NC 28390

Plans Submitted By: Bryan Ritter

Project Phone: (919) - 770-4530

Contact Person/Address: Bryan Ritter
1015 Frazier Drive PO Box 5231
Sanford 27330

Contact Email: Sanfordmetalbuilding@gmail.com

Contact Phone: () - - () - -

Contractor's Name/Info: Same

Contractor's Phone: () - -

- Plans that are submitted will be reviewed as quickly as possible with an average time of review between 7-10 working days.
- Status checks may be conducted on plan reviews by visiting the website <http://hteweb.harnett.org/Click2GovBP/Index.jsp> or by calling the Harnett County Central Permitting Office (910-893-7525, Option #2), or the Harnett County Fire Marshal's Office (910-893-7580).
- Approved plans must be picked up from the Central Permitting Office and all fees paid before any required inspections can be conducted.



Plan Review, Inspection, and Permit Fees

Application Number : 1850043351

\$200.00	<input type="checkbox"/>	Explosive Material (90 Days)	\$	-
\$100.00	<input type="checkbox"/>	Explosive Materials (72 Hours)	\$	-
\$100.00	<input type="checkbox"/>	Fireworks Public Display	\$	-
\$50.00	<input checked="" type="checkbox"/>	Final Inspection	\$	50.00
\$35.00 + \$2.00 per device	<input type="checkbox"/>	Fire Alarm Testing	\$	-
\$35.00 + \$2.00 per nozzle	<input type="checkbox"/>	Fixed Fire Suppression	\$	-
\$75.00	<input type="checkbox"/>	Insecticide Fog/Fumigation	\$	-
\$100.00	<input type="checkbox"/>	Pipe Test/UST/AGST	\$	-
\$50.00	<input checked="" type="checkbox"/>	Plans up to 5000 sq ft	\$	50.00
\$100.00	<input type="checkbox"/>	Plans 5001 sq ft to 10,000 sq ft	\$	-
\$150.00	<input type="checkbox"/>	Plans 10,001 sq ft to 25,000 sq ft	\$	-
\$250.00	<input type="checkbox"/>	Plans 25,001 sq ft and over	\$	-
\$35.00 + 2.00 per head	<input type="checkbox"/>	Sprinkler Certification Test	\$	-
\$50.00	<input type="checkbox"/>	Standpipe Testing	\$	-
\$50.00	<input type="checkbox"/>	Special Assembly (ie. amusement buildings, carnivals, fairs)	\$	-
\$75.00	<input type="checkbox"/>	Tents/Canopies/Air Supported Structure	\$	-
\$100.00	<input type="checkbox"/>	Tank Installation (charge for each tank)	\$	-
\$100.00	<input type="checkbox"/>	Tank Removal (charge for each tank)	\$	-
		Total Devices/Heads	\$	-
		Total Cost	\$	100.00

Code Enforcement Official

Rodney Daniels

3/8/2018



March 8, 2018

**Bryan Ritter
1015 Fraizer Drive
Sanford, NC 27330**

**RE: Anderson Creek Landfill
1086 Poplar Drive
Spring Lake, NC 28390**

Application Number 18-50043351

Mr. Ritter,

Thank you for submitting the plans for the new building. The plans have been carefully reviewed by a qualified code enforcement official to examine for full compliance with the North Carolina Fire Prevention Code and all other fire protection regulatory documents. There are some items that were found during the plan review process that need to be addressed before a final inspection of the new facility can be given. These items are outlined and described below.

- **906.1 Fire Extinguishers**
 - Fire extinguishers shall be placed in approved locations as drawn on the approved plans.
 - The fire extinguishers provided shall have a minimum rating of 2A 10B: C and shall not be installed higher than 5 feet above the finished floor.
- **505.1 Address Numbers**
 - The physical address shall be installed on the building so that it is visible from the approach side contrasting color and a minimum size of 6 inch.
- **506.1 Knox Box**
 - A Knox Box is required to be installed on the building. Please see the link below to order Knox box. Paper order form available upon request.
<https://www.knoxbox.com/store/Knox-Box-3200-Series.cfm>
- **1006.1 Emergency Lighting**
 - The means of egress, including the exit discharge, shall be illuminated at all time the building space is served by the means of egress is occupied.
 - Means of egress consist of three separate and distinct parts: the



- exit access, the exit and the exit discharge.
- Please provide emergency lighting in restroom.
 - The means of egress illumination shall not be less than 1 foot-candle at the walking surface.


Notes

Please call to schedule fire final through the Fire Marshal's Office at (910) 893-7580.

Thank you again for submitting the plans for the new building. Please review the plans and adhere to any notes and alterations that were made in addition to the original drawings. These remarks are for the plans that were submitted and its original intent. These remarks do not apply if the original intent changes or what was submitted on the above date changes. If you have any questions, please do not hesitate to call this office

Again, thank you and we look forward to working with you during the construction period!

Sincerely,



Rodney Daniels
Fire Marshal