



## Application for Plan Review

Application # 18-50043676  
Date Received: 3/29/18 Received By: [Signature]  
Name of Project: Town of Coats  
Physical Address of Project: 186-234 heman St  
Coats, NC 27521  
Plans Submitted By: Talon Construction Inc  
Project Phone: (919)-938-2500  
Contact Person/Address: Roy Pope  
Po Box 148  
Smithfield NE 27577  
Contact Email: roy@talonconstruction.net  
Contact Phone: (919)-631-2388  
Contractor's Name/Info: Talon Construction Inc  
Po Box 148  
Smithfield NE 27577  
Contractor's Phone: (919)-631-2388

- Plans that are submitted will be reviewed as quickly as possible with an average time of review between 7-10 working days.
- Status checks may be conducted on plan reviews by visiting the website <http://htweb.harnett.org/Click2GovBP/Index.jsp> or by calling the Harnett County Central Permitting Office (910-893-7525, Option #2), or the Harnett County Fire Marshal's Office (910-893-7580).
- Approved plans must be picked up from the Central Permitting Office and all fees paid before any required inspections can be conducted.



## Plan Review, Inspection, and Permite Fees

Application Number : 18-50043676

\$100.00	<input type="checkbox"/>	DRB Major Sub Division Prelim Site Plans	\$	-
\$200.00	<input type="checkbox"/>	Explosive Material (90 Days)	\$	-
\$100.00	<input type="checkbox"/>	Explosive Materials (72 Hours)	\$	-
\$100.00	<input type="checkbox"/>	Fireworks Public Display	\$	-
\$50.00	<input checked="" type="checkbox"/>	Final Inspection	\$	50.00
\$35.00 + \$2.00 per device	<input type="checkbox"/>	Fire Alarm Testing	\$	-
\$35.00 + \$2.00 per nozzle	<input type="checkbox"/>	Fixed Fire Suppression	\$	-
\$75.00	<input type="checkbox"/>	Insecticide Fog/Fumigation	\$	-
\$100.00	<input type="checkbox"/>	Pipe Test/UST/AGST	\$	-
\$50.00	<input checked="" type="checkbox"/>	Plans up to 5000 sq ft	\$	50.00
\$100.00	<input type="checkbox"/>	Plans 5001 sq ft to 10,000 sq ft	\$	-
\$150.00	<input type="checkbox"/>	Plans 10,001 sq ft to 25,000 sq ft	\$	-
\$250.00	<input type="checkbox"/>	Plans 25,001 sq ft and over	\$	-
\$35.00 + 2.00 per head	<input type="checkbox"/>	Sprinkler Certification Test	\$	-
\$50.00	<input type="checkbox"/>	Standpipe Testing	\$	-
\$50.00	<input type="checkbox"/>	Special Assembly (ie. amusement buildings, carnivals, fairs)	\$	-
\$75.00	<input type="checkbox"/>	Tents/Canopies/Air Supported Structure	\$	-
\$100.00	<input type="checkbox"/>	Tank Installation (charge for each tank)	\$	-
\$100.00	<input type="checkbox"/>	Tank Removal (charge for each tank)	\$	-
		Total Devices/Heads	\$	-
		<b>Total Cost</b>	\$	<del>50.00</del> 50.00

Code Enforcement Official

Roger Sullivan

4/9/2018



**Fire Marshal Division**

April 09, 2018

Talon Construction  
P.O. Box 148  
Smithfield, NC 27577

Re: Town of Coats  
186 – 234 Lemon Street  
Coats, NC 27521

Application Number 18-50043676

To whom it may concern,

Thank you for submitting the plans for the Town of Coats. The plans have been carefully reviewed by a qualified code enforcement official to examine for full compliance with the North Carolina Fire Prevention Code and all other fire protection regulatory documents. There are some items that were found during the plan review process that need to be addressed before a final inspection of the new facility can be given. These items are outlined and described below.

- **505.1 Physical Address**
  - The physical address of the building shall be posted in a conspicuous place so that it can be seen on approach from the road, access road, and/or parking lot.
  - The numbers used to make up the physical address shall be at least 6 inches in height.
  
- **506.1 Knox Box**
  - A secure key box shall be installed on the new building that houses all keys to all the doors within the building in which the fire department would need access to in the event of an emergency.
  - Knox Box ID stickers shall be placed on all exterior doors in which entry to the building may be gained.
  - The box shall be mounted not to exceed 48 – 60 inches in height.
  - The basic model for the buildings should be at least a selection from the 3200 Series listed on the order form.
    - <https://www.knoxbox.com/store/departmentSearch.cfm>
  
- **Fire Extinguishers**



- Fire Extinguishers shall be 2A:20BC and shall be placed with a travel distance to not exceed 75'
- Fire extinguishers are to be mounted no higher than 5' above the finished floor.
  
- **1006.1 Illumination Required**
  - The exit discharge shall be illuminated at all times the building spaces served by the means of egress is occupied
  - Illumination level in all areas of the means of egress shall not be less than 1 foot-candle at the walking surface and shall have emergency power supply.
  
- Notes
  - **A final fire inspection is required. Please contact this office direct to schedule fire inspection at 910-893-0743.**

Thank you again for submitting the plans for Town of Coats. Please review the plans and adhere to any notes and alterations that were made in addition to the original drawings. These remarks are for the plans that were submitted and its original intent. These remarks do not apply if the original intent changes or what was submitted on the above date changes. If you have any questions, please do not hesitate to call this office

Again, thank you and we look forward to working with you during the construction period!

Sincerely,

Roger Sullivan  
Deputy Fire Marshal