



Plan Review, Inspection, and Permit Fees

Application Number : **15-50036509**

\$75.00	<input type="checkbox"/>	DRB Major Sub Division Prelim Site Plans	\$	-
\$150.00	<input type="checkbox"/>	Explosive Material (90 Days)	\$	-
\$75.00	<input type="checkbox"/>	Explosive Materials (72 Hours)	\$	-
\$50.00	<input type="checkbox"/>	Fireworks Public Display	\$	-
\$50.00	<input checked="" type="checkbox"/>	Final Inspection	\$	50.00
\$35.00 + \$2.00 per device	<input type="checkbox"/>	Fire Alarm Testing	\$	-
\$35.00 + \$2.00 per nozzle	<input type="checkbox"/>	Fixed Fire Suppression	\$	-
\$25.00	<input type="checkbox"/>	Insecticide Fog/Fumigation	\$	-
\$50.00	<input type="checkbox"/>	Pipe Test/UST/AGST	\$	-
\$50.00	<input checked="" type="checkbox"/>	Plans up to 5000 sq ft	\$	50.00
\$100.00	<input type="checkbox"/>	Plans 5001 sq ft to 10,000 sq ft	\$	-
\$150.00	<input type="checkbox"/>	Plans 10,001 sq ft to 25,000 sq ft	\$	-
\$250.00	<input type="checkbox"/>	Plans 25,001 sq ft and over	\$	-
\$35.00 + 2.00 per head	<input type="checkbox"/>	Sprinkler Certification Test	\$	-
\$35.00	<input type="checkbox"/>	Standpipe Testing	\$	-
\$25.00	<input type="checkbox"/>	Special Assembly	\$	-
\$25.00	<input type="checkbox"/>	Temporary Kiosks/Displays	\$	-
\$25.00	<input type="checkbox"/>	Tents/Canopies/Air Supported	\$	-
\$50.00	<input type="checkbox"/>	Tank Installation (charge for each tank)	\$	-
\$50.00	<input type="checkbox"/>	Tank Removal (charge for each tank)	\$	-
		Total Devices/Heads	\$	-
		Total Cost	\$	100.00

Code Enforcement Official

Buddy Walters



Fire Marshal Division

September 8, 2015

Katelyn Gerhard
84 Tingen Road
Broadway, NC. 27505

Re: Independence Montessori Academy
84 Tingen Road
Broadway, NC. 27505

Application Number 15-50036509

Mrs. Gerhard,

Thank you for submitting the plans for the new Independence Montessori Academy. The plans have been carefully reviewed by a qualified code enforcement official to examine for compliance with the North Carolina Fire Prevention Code and all other fire protection regulatory documents. There are some items that were found during the plan review process that need to be addressed before a final inspection of the new facility can be given. These items are outlined and described below.

- **901.6.1 Fire Alarm Systems NFPA 72**
 - Provide shop drawings from the installing contractor.
 - Shop drawings shall include all information listed in section 907.1.2 of the North Carolina Fire Prevention Code.
 - System additions and modifications shall be in accordance with NFPA 72.
 - A Construction permit will be required for the installation of the fire alarm system and related equipment in accordance with 105.7.5 of the North Carolina Fire Prevention Code
 - Ensure proper visual and audible notification devices are installed in each classroom and in accordance with NFPA 72
 - Zone maps shall be posted and available on site in accordance with NFPA 72

- **906.2 Fire Extinguishers NFPA 10**
 - Fire extinguishers shall be installed. One 2A-10BC extinguisher in each classroom near the main entrance/exit door. Recommend they be placed in extinguisher cabinets.



- **506.1 Knox Box**
 - A Knox Box is required to be installed on the building.
 - An order form is attached to the plan review letter package.
- **505.1 Address Numbers**
 - The physical address numbers shall be installed on the building.
 - Numbers should be of contrasting color and visible from the road/street.
- **703.5 Identification**
 - Rated walls and partitions shall be permanently identified in all concealed or above ceiling locations.
 - **Ex. (2-HOUR FIRE BARRIER PROTECT ALL OPENINGS)**
- **503.1.1 Fire Apparatus Roads**
 - Approved fire apparatus roads/access shall extend to within 150 feet of all exterior portions of the building.
- **1008.1.4.4 Access-Controlled Doors**
 - All entrance/egress control systems installed must be approved by the Fire Marshal's Office.
- **Notes**
 - Please call **910-893-0741** to schedule all Fire Marshal inspections.

Thank you again for submitting the plans for the new Montessori Academy. Please review the plan review notes and if you have any questions, please do not hesitate to call this office.

Sincerely,



Buddy Walters
Chief Deputy Fire Marshal