

HTE# 15-5-3509

Harnett County Department of Public Health

28530

Improvement Permit

Montessori Independent School

A building permit cannot be issued with only an Improvement Permit
PROPERTY LOCATION: TINGEN RD

ISSUED TO: ALLISON DANIEL SUBDIVISION _____ LOT # 5

NEW REPAIR EXPANSION

Site Improvements required prior to Construction Authorization Issuance:

Type of Structure: SCHOOL (5000sqft)

Proposed Wastewater System Type: PUMP TO 25% REDUCTION

Projected Daily Flow: 960 GPD STUDENTS

Number of bedrooms: _____ Number of Occupants: 96 max

Basement Yes No

Pump Required: Yes No May be required based on final location and elevations of facilities

Type of Water Supply: Community Public Well Distance from well 100 feet

Permit valid for: Five years
 No expiration

Permit conditions: _____

Authorized State Agent: [Signature] Date: 9/8/15 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: ALLISON DANIEL PROPERTY LOCATION: TINGEN RD

SUBDIVISION _____ LOT # 5

Facility Type: SCHOOL (5000sqft) New Expansion Repair

Basement? Yes No Basement Fixtures? Yes No

Type of Wastewater System** PUMP TO 25% REDUCTION SYSTEM (Initial) Wastewater Flow: 960 GPD

(See note below, if applicable)

Installation Requirements/Conditions

Septic Tank Size 1700 gallons MIN.

Number of trenches 4
Exact length of each trench 135 feet

Trench Spacing: 9 Feet on Center

Pump Tank Size 1200 gallons MIN.

Trenches shall be installed on contour at a Maximum Trench Depth of: 18-36 inches
(Trench bottoms shall be level to +/-1/4" in all directions)

Soil Cover: 6-24 inches
(Maximum soil cover shall not exceed 36" above the trench bottom)

Pump Requirements: _____ ft. TDH vs. _____ GPM

Aggregate Depth: _____ inches below pipe
_____ inches above pipe
_____ inches total

Conditions: _____

**WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.**

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 9/8/15

Construction Authorization Expiration Date: 9/8/20

HTE# 15-5-36509

Permit # 28530

Harnett County Department of Public Health

Site Sketch

Montessori Independence School

PROPERTY LOCATOR: TINGEN RD

ISSUED TO: ALLISON DANIEL

SUBDIVISION

LOT # 5

Authorized State Agent:

~~REVIS (OLIVER TOLKSON)~~

Date: 7/8/15

* STAKE LINES
@ 18"

