

Harnett County

Inspections
108 East Front Street
Lillington , NC 27546

Phone: 910-893-7525
Fax: 910-893-2793

Inspection Report

Permit: CSED17-50042439

OWNER: CAMPBELL UNIVERSITY

Site Address: 445 LESLIE CAMPBELL AVE LILLINGTON, NC 27546

Harnett County Inspections Department

Inspection Type: FINAL**

Inspection Date: 04/17/2020

Result: DISAPPROVED

Remarks:

- Notes:
1. Support condensate drains on roof at max 4' intervals.
 2. Seal slab edge at roof level landing and reapply fire coating to steel.
 3. All accessible sinks shall have kick plates or drains and lines wrapped. Rm241 noted.
 4. Nightlights in all multiple occupancy bathrooms.
 5. Backflow on carbonated soda system.
 6. All 120v receptacles in kitchens must be GFCI.
 7. All bathrooms must have mirror that meets ANSI 117 (35 "MAX AFF)
 8. All accessible toilet stalls, and single occupant bathrooms must have self closing doors.

All violations are subject to reinspection fees at the inspectors discretion.

Brad Sutton
Inspector