

OPERATIONS PERMIT

Name: (owner) Gregory INC

New Installation Septic Tank

Property Location: SR# Hwy 55

Repairs Nitrification Line

Subdivision Braxton

Lot # 15

TAX ID# _____

Quadrant # _____

Contractor: Larry Sharpe

Registration # _____

Basement with Plumbing: Garage:

Water Supply: Well Public Community

Distance From Well: 50' ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other Pump to Conventional

Size of tank: Septic Tank: 1000 gallons Pump Tank: 1000 gallons

Subsurface Drainage Field No. of ditches 3 exact length of each ditch 80 ft. width of ditches 3 ft. depth of ditches 18-20 in.

French Drain: — Linear feet

Date: 3-21-02

PERMIT NO. 16875

Inspected by: James E. Markert, S.S.
Environmental Health Specialist

